



Iowa Department of Transportation

UTILITY BID ATTACHMENT

County:

Cass

Project Classification:

Non-Point 25

Project No.:

STPN-092-2(37)--2J-15 (ROW)

BRF-092-2(36)--38-15 (CONST)

District Utility Coordinator:

Eric Keiner

Iowa Department of Transportation

District Utility Coordinator

Highway Route Number or Name:

IA 92

300 West Broadway, Suite 401

Council Bluffs, IA 51503

Segment or Section:

Ia. 92 Over Small Stream 1 Mile W. Of Ia. 148

Utilities:

Some of the utility work described below is dependent on prior work being performed by the Contractor at a specific site. In such situations the Contractor shall provide the Engineer and the affected utility a good faith notice of when the utility is to start work at the site. The notice shall be given 14 calendar days in advance of when the Contractor expects to complete the prior work and the site will be available to the utility. The Contractor shall follow up with a confirmation notice to the Engineer and the utility not less than 3 working days before the site will be ready for the utility to begin its' work.

Additional detailed information regarding the location of relocated utility facilities is available on the permits issued to the utility companies. These permits can be viewed at the District office during normal working hours. Contact the **District Utility Coordinator at 712-323-6125.**

Facilities- Affected: The following utilities have relocated or plan to relocate prior to construction to avoid conflict.

Alliant Energy (Electric Distribution): Alliant (Interstate Power and Light) operates an OHE line in the north ROW. Plan is to relocate to the north prior to construction to avoid conflict with construction and to stay clear of staging area.

Century Link/LightCore (formerly Digital Teleport) (Fiber Optic): CenturyLink is currently in the process of designing a relocation for LightCore facilities to accommodate this project, per Bob Sampson (1-29-13). Relocation will consist of directional bore through project area. Relocation planned for March 2013. Existing facilities labeled as "FO" on plans.

Massena Telephone Company (Telephone): Massena Telephone Co. (formerly attached to existing bridge - shown as "T1" on plans) has been relocated to the north throughout project area via directional boring. Design depth sufficient to avoid conflict. Work completed in 2012. Permit #15U-2012-004.

Facilities- Not Affected: The following utilities are located within the project limits, but do not anticipate any conflicts with proposed construction.

MCI (Fiber Optic): No relocation needed per field locate data and review of preliminary plans by Steve Bonczkowski(MCI/Verizon). Existing fiber labeled as "F02" on plans.

Southern Iowa Rural Water Association (Water): 6" water line is located on private easement north of current north ROW. It was determined that SIRWA facilities are of sufficient depth to avoid conflict, with minimal grading taking place over their line. General depth is 4-5 ft. Depth increases as line approaches stream and is approx. 10 ft. beneath streambed.

No Facilities: The following utilities may be in the general vicinity of this project, but are not located within the project limits.

B&L Technologies LLC (Cable TV), Black Hills Energy (Gas), City of Massena (Water), MidAmerican Energy Company (Gas):

-- END --