

07-16-91

213-6

The backfilling and associated embankment construction shall be completed within 14 working days after the curing period has expired for culvert extension.

The immediate embankment shall be placed to provide 8:1 slopes away from the culvert top.