

04-25-00

214-1

The roadbed shall be trimmed to within 0.05 foot of the final subgrade elevation. Trimmed material shall be placed in a windrow on either foreslope for use in earth shoulder fill after paving. No ponding of water shall be allowed by the stored materials.

Trimming of material shall be included in excavation required for Earth Shoulder Construction. Granular surfacing material, if placed over the winter, is included in the trimmed volume.