

01-20-84

223-2

Construction of fillets at non-paved entrances will be required on this project. Material for these fillets is included in the appropriate items of the "Estimate of Quantities". The Engineer may increase or decrease the number of fillets required.