

**EROSION CONTROL: (Salvage and removal projects)**

Following completion of work in a disturbed area, the area shall be seeded and fertilized as follows:

**SEEDING MIXTURE:** Seeding Rate: 3 lbs. per 1000 sq. ft.  
Tall Fescue or Fawn

**FERTILIZER:**

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

**ESTIMATED AREA:** \_\_\_\_\_ acres.

The preparation of the seedbed and the furnishing and application of seed and fertilizer shall be considered incidental to mobilization and no extra compensation will be allowed.