

CHAPTER 11 STRUCTURES

11.00 INTRODUCTION	11-1
11.01 REMOVAL OF BRIDGES	11-1
11.02 GUIDANCE FOR HEAVY EQUIPMENT & MATERIALS ON BRIDGES	11-1
11.03 TEMPORARY STRUCTURES FOR THE PROTECTION OF THE PUBLIC	11-3
11.04 RESERVED FOR FUTURE USE	11-3
11.05 PILE DRIVING CAP AND HAMMER INFORMATION	11-3
11.10 EARTHWORK FOR STRUCTURES	11-5
11.11 EXCAVATION	11-5
11.12 BACKFILLING STRUCTURES	11-5
Culverts	11-5
Bridge Abutments	11-5
Measurement and Payment	11-6
11.20 FOUNDATIONS	11-7
11.21 STAKING AND CHECKING LOCATIONS OF STRUCTURES	11-7
Check and Double Check	11-7
Documentation	11-8
Common Survey Errors to Avoid	11-8
Encountering Old Substructures	11-8
Setting Bench Marks (Post Construction)	11-8
11.22 PILING AND PILE DRIVING	11-9
Pile Driving	11-9
Vibratory Hammers	11-9
Gravity Hammers	11-10
Diesel Hammers	11-10
Bearing and Penetration	11-11
Retaps	11-11
Dynamic Pile Analyzer	11-12
Static Load Tests	11-13
11.23 SPLICING PILE	11-13
Welding Steel Pile	11-13
Concrete Pile	11-16
11.24 PILING ACCEPTANCE	11-17

	Steel Pile -----	11-17
	Wood Pile -----	11-17
	Steel Pile Cutoffs -----	11-17
11.25	WAVE EQUATION-----	11-18
	Hammer Data Form-----	11-18
	Driving Graphs -----	11-18
	Log of Piling Driven-----	11-20
11.26	PREBORED HOLES -----	11-21
	Typical Preboring-----	11-21
	Special Prebore Situations-----	11-22
	Bentonite -----	11-22
11.27	DRILLED SHAFTS-----	11-23
11.30	BRIDGES -----	11-24
11.31	FALSEWORK -----	11-24
	Temporary Fastenings -----	11-24
	Falsework Plans -----	11-24
	Falsework Inspection-----	11-25
	Falsework Foundations-----	11-25
	Materials-----	11-26
	Project Quality -----	11-28
	Miscellaneous Items-----	11-30
	Falsework Adjacent To Traffic -----	11-30
	Field Changes-----	11-30
	Inspection during Concrete Placement-----	11-30
	Removal of Falsework -----	11-31
11.32	BRIDGES - STEEL BEAM -----	11-31
	Prebolting Meeting-----	11-32
	Erecting Steel Beams -----	11-33
	High Strength Fasteners -----	11-34
	Painting -----	11-43
11.33	BRIDGES - CONCRETE BEAM-----	11-43
	Precast - Prestressed Deck Panels -----	11-43
	Pretensioned Prestressed Concrete Beam (PPC Beam) Erection -----	11-44
	Diaphragms (Steel or Concrete) -----	11-44

11.40 REINFORCEMENT	11-46
General Placement Guidelines for Bridge Reinforcing Steel	11-46
11.41 PLACEMENT AND CHECKING (BRIDGE FLOORS)	11-46
Slab Thickness	11-46
Clearance of Bottom Reinforcement	11-46
Clearance of Top Mat Reinforcement	11-47
Cover Over Top Mat of Reinforcement	11-47
Slab Bridges	11-47
Special Attention Areas	11-47
11.42 EPOXY COATED REINFORCEMENT	11-48
Care and Handling	11-48
Field Inspection	11-50
Repair of Damaged Coating	11-50
11.43 CAGE STEEL (DRILLED SHAFTS)	11-51
11.44 SPLICING	11-51
Splice Approval	11-51
11.45 PAYMENT FOR REINFORCING STEEL	11-52
11.50 CONCRETE (STRUCTURAL, CLASS X, AND FLOWABLE MORTAR)	11-53
11.51 PCC PLANT PAGE (FORMS 800240E AND 800240M)	11-53
11.52 USE OF READY MIXED STRUCTURAL CONCRETE	11-53
Prepour Meeting	11-53
Inspector's Checklist	11-53
11.53 ADMIXTURES	11-58
Air Entraining Admixtures	11-58
Water Reducing Admixtures – Regular	11-58
Water Reducing Admixtures - Super Plasticizers	11-59
Retarding Admixtures	11-59
Accelerating Admixtures	11-60
Corrosion Inhibiting Admixtures	11-60
Finely Divided Mineral Admixtures	11-61
Pozzolanic Materials	11-61
Fly Ash (Class C & F)	11-61
Silica Fume	11-61
Cementitious Materials	11-61

	Ground Granulated Blast Furnace Slag (GGBFS)-----	11-62
11.54	USE OF INSULATED FORMS FOR PROTECTION -----	11-62
	Checking Temperature of Concrete -----	11-63
11.55	DECK PLACEMENT AND HEAT OF HYDRATION -----	11-63
	Deck Placement -----	11-63
	Deck Concrete Temperature and Curing-----	11-64
	Placement Considerations -----	11-65
	Field Documentation -----	11-66
	Heat of Hydration-----	11-66
11.56	PLACEMENT METHODS (PUMPING, BELTING, AND CRANE BUCKET) -----	11-67
	Crane and Bucket -----	11-67
	Belt Placement -----	11-67
	Pump Placement -----	11-67
11.57	FORM REMOVAL-----	11-68
	Setting Beams -----	11-68
11.58	CLASS 3 CONCRETE SURFACE FINISH (RAIL AND BEAMS) -----	11-69
	Approval of Materials-----	11-69
	Application of Finish -----	11-69
	Concrete Railings -----	11-69
11.59	FLOWABLE MORTAR -----	11-69
	Backfilling Culverts - Typical Grading-----	11-70
	Plugging Culverts -----	11-71
	Backfilling Culverts - Under Bridges-----	11-71
	Filling Voids Between Culverts -----	11-72
11.60	DECKS AND OVERLAYS -----	11-74
11.61	DECK OVERLAY PREPARATION -----	11-74
	Class A Floor Repair -----	11-74
	Class A Surface Preparation -----	11-75
	Work on Adjacent Lanes -----	11-75
11.62	SEQUENCE OF POURING -----	11-76
	Use of Retarders -----	11-77
	Concrete Bridge Floors -----	11-80
	Placement Methods -----	11-86
11.63	INSTALLATION OF JOINTS -----	11-87

	Preformed Neoprene Joints -----	11-87
	Steel Extruded Expansion Joints (Strip Seals) -----	11-88
11.64	BRIDGE FLOORS -----	11-89
	Finishing and Equipment -----	11-89
	Profile Grades - Overlays -----	11-89
	Transverse Grooving -----	11-90
	Longitudinal Grooving In Hardened Concrete -----	11-90
	Missed Texturing -----	11-91
11.65	CONCRETE -----	11-91
	Concrete Mobile Mixers -----	11-91
	Frequency of Checks -----	11-92
	Density Testing -----	11-92
11.66	APPROACH SECTIONS -----	11-93
	Approach Pavements to Bridge Abutments -----	11-93
	“Movable” Abutments -----	11-94
	“Fixed” Abutments -----	11-94
	Bridge Approach Tapers -----	11-94
	Shoulder Maintenance -----	11-95
11.67	SMOOTHNESS OF BRIDGE DECKS -----	11-95
	Checklist -----	11-95
	Specification 2428 -----	11-96
	Surface Checking -----	11-98
11.70	BARRIER RAILS -----	11-99
11.71	CONCRETE F-SHAPE, OPEN, AND RETROFIT RAIL -----	11-99
	Rail Concrete Placement and Bridge Deck Falsework -----	11-99
11.72	SLIP FORM BARRIER RAIL -----	11-100
	Longitudinal Cracks -----	11-100
	Reinforcement -----	11-100
	Reinforcement Bar Cover -----	11-100
	Misalignment and Nonuniform Top Elevation -----	11-100
	Shadowing -----	11-101
	Mix Design for Slip Form and Cast-in-Place -----	11-101
	Curing of Slip Form Barrier Rail -----	11-102
	Expansion Joint Construction in Barrier Rail -----	11-102

11.73 CAST-IN-PLACE (RETROFIT) BARRIER RAIL-----11-103
 Preventing Dowel Installation Damage of Conduit-----11-104

11.74 CAST-IN-PLACE OPEN BARRIER RAIL FORM REMOVAL -----11-104

11.80 REINFORCED CONCRETE CULVERTS-----11-105

11.81 DESIGN CHANGES ON CULVERTS-----11-105

11.82 INSTALLING REINFORCING STEEL, PLACING CONCRETE, AND FORM
 REMOVAL -----11-105
 Installing Reinforcing Steel -----11-105
 Placing Concrete -----11-106
 Removal of Wall Forms-----11-106
 Removal of Slab Forms-----11-107

11.83 BOX CULVERT CURTAIN WALLS-----11-107
 Sheet Pile Curtain Wall -----11-107
 Reinforcement Placement -----11-107

11.84 BOX CULVERT BELL JOINTS -----11-108