

---

**GUIDELINES FOR WAIVING MATERIAL FROM  
THE FINAL MATERIALS REVIEW**

<b><u>MATERIAL</u></b>	<b><u>UNITS</u></b>	<b><u>MAXIMUM QUANTITY BY ITEM</u></b>
Aggregate	Tons	200
Asphalt, Cutback	Gal.	100
Asphalt, Emulsified	Gal.	100
Asphalt, Hot Mix	Tons	50
Aprons: RCP or CMP	Ea.	4
Base Repair: HMA or PCC	S.Y.	100
Conduit	Ft.	50
Culvert Pipe: RCP, CMP or PE	Ft.	30
Delineators	Ea.	10
Delineator Posts	Ea.	10
Dowel Baskets, Epoxy Coated	Ea.	10
Fabric Engineering, Erosion Control	S.Y.	100
Fabric Engineering, Silt Fence	Ft.	100
Iron Casting, Manhole Covers, Etc.	Ea.	1
Joint Filler, Preformed	Ft.	100
Lighting Material, Ground Rods	Ea.	2
Lighting Material, Wire/Cable	Ft.	250
Paint, Bridge	Sq.Ft.	250
Pavement	S.Y.	100
Pavement Markings	Sta.	25
Pipe, Rodent Guard for CMP	Ea.	5
Pipe, Rodent Guard for P.E. Pipe	Ea.	5
Seed, Fertilizer/Mulch	Acres	5
Signing Materials, Finished Sign	Sq. Ft.	20
Signing Materials, Wood Posts	Ft.	50
Steel Reinforcement, Epoxy Coated	Lbs.	500
Steel Reinforcement, Uncoated	Lbs.	500
Structural Concrete	C.Y.	25
Subdrain, CMP	Ft.	250
Subdrain, CMP Outlet	Ea.	5
Subdrain, P.E.	Ft.	250
Subdrain, P.E. Outlet	Ea.	5