

CHAPTER 8
HOT MIX ASPHALT (HMA) PAVEMENT, BASES, AND SUBBASES

8.00	TABLES AND REPORT FORMS -----	8-1
8.01	TABLES FOR BITUMINOUS MATERIALS AND HMA CONSTRUCTION -----	8-1
8.02	REPORT FORMS-----	8-1
	Form Identification and Use -----	8-1
8.10	ACCEPTANCE AND TESTING -----	8-2
8.11	FIELD TESTS AND CERTIFICATION OF MATERIALS -----	8-2
	Asphalt Materials -----	8-2
	Aggregates-----	8-2
8.12	RESPONSIBILITY AND DOCUMENTING HMA MIXTURE PROPORTIONING CHANGES -----	8-3
	Adjusting Asphalt Binder Contents -----	8-3
	Documenting Corrective Action for Noncomplying Air Voids Test on Specimens Taken from Constructed Pavement-----	8-4
	Adjusting Aggregate Proportions-----	8-4
	Filler/Bitumen Ratio-----	8-5
8.13	DENSITY CONTROLS FOR HMA CONSTRUCTION-----	8-5
	Uncompacted HMA Samples -----	8-5
	Compacted HMA Samples-----	8-6
	Procedures for Construction of Test Strips -----	8-8
	Resolving Density-Void Conflicts-----	8-11
8.14	TESTING FOR SMOOTHNESS-----	8-12
	Use of Straightedge and Rolling Surface Checker -----	8-12
8.15	CHECKING TRANSVERSE JOINTS FOR SMOOTHNESS -----	8-13
8.20	MEASUREMENTS AND PAYMENT COMPUTATIONS -----	8-14
8.21	ASPHALT BINDER -----	8-14
	Tank Measurement and Asphalt Binder Content Determination -----	8-14
	Measuring Asphalt Binder for Small Quantities-----	8-15
	Asphalt Binder Quantities and Pay Adjustments-----	8-15
8.22	TARGET VALUES FOR ASPHALT BINDER CONTENT IN JOB MIXES -----	8-15
8.23	WEIGHING OF HMA MATERIALS -----	8-16
8.30	EQUIPMENT USE AND INSPECTION -----	8-17

8.31	INSPECTION AT HMA PLANTS -----	8-17
8.32	INSPECTING THE MIXING TIME OF HMA PLANTS -----	8-18
8.40	GENERAL CONSTRUCTION -----	8-19
8.41	UNSTABLE SUBGRADES AND SUBBASES -----	8-19
	Locating Unstable Areas -----	8-19
	Determining Cause -----	8-19
	Overdepth Aeration and Recompaction -----	8-19
	Special Treatments -----	8-20
8.42	STAKING METHOD FOR HMA PAVEMENTS -----	8-20
8.43	GUIDELINE STRINGS AND EDGE ALIGNMENT -----	8-20
8.44	LONGITUDINAL JOINTS -----	8-21
8.45	TACK COATS USING EMULSIONS -----	8-21
	For Dilution-----	8-21
	Application Rate for Diluted Emulsion -----	8-21
	Sample for Compliance-----	8-22
	Measurement for Pay -----	8-22
	Settlement of Diluted Emulsions -----	8-22
8.50	BASE, INTERMEDIATE, AND SURFACE COURSES -----	8-23
8.51	HMA WEDGE CONSTRUCTION FOR SUPERELEVATION OF CURVES-----	8-23
	Automatic Slope Control-----	8-23
	Placement of Wedge -----	8-24
	Sequence of Placement -----	8-24
8.52	LAYING WIDTHS FOR HMA-----	8-25
8.53	SPREAD RATES FOR HMA BASE, INTERMEDIATE, AND SURFACE COURSES -----	8-25
8.54	HMA RESURFACING ON CITY STREETS-----	8-26
	Preliminary Layout -----	8-26
	Construction -----	8-27
	Thickness Taper at Curb Line-----	8-28
	Extending Paver Width -----	8-28
8.55	COLD WEATHER HMA CONSTRUCTION -----	8-28
	Temperature Determination for Placing HMA and Liquid Bitumens-----	8-29
8.56	RELEASE AGENTS AND SOLVENTS -----	8-29
8.60	RUMBLE STRIPS IN HMA SHOULDERS -----	8-30

8.61 CONSTRUCTION CONSIDERATIONS – MILLED RUMBLE STRIPS----- 8-30

8.62 RESERVED FOR FUTURE USE ----- 8-30

8.70 INSPECTOR’S GUIDE - HMA PAVING & RESURFACING----- 8-31

 Additional Requirements for Interstate Projects----- 8-33

 Additional Requirements for Full-Depth Paving ----- 8-33

 Additional Requirements for Winter Shutdown ----- 8-33

8.80 USE OF SPECIAL EQUIPMENT ----- 8-34

 Material Transfer Vehicles ----- 8-34

 Other Material Transfer Vehicles----- 8-34

 Mat Smoothness Machine ----- 8-36

 Windrow Pick-up Equipment ----- 8-36

