

\*\*\*\*THIS IS A NEW APPENDIX. – PLEASE READ CAREFULLY.\*\*\*\*

**PCC NON-STRUCTURAL & MISCELLANEOUS - FIELD AND PLANT SAMPLING AND TESTING GUIDE**  
(See Specifications for Complete Details.)

Article	Work Type	Field Acceptance	Plant Acceptance	
		Air & Slump	Gradation QC	Gradation Verification
2212	Base Repair	1/30 yd3 (1)	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2405	seal course	n/a	n/a	n/a
2416	Pipe collars	n/a	n/a	n/a
2503	Catch basins, abandonment collars	n/a	n/a	n/a
2506	Flowable Mortar	n/a	S/T for Mix Design only	n/a
2507	Revetment Grout	1/day	S/T for Mix Design only	n/a
	Fabric Formed Revetment	1/day	S/T for Mix Design only	n/a
2511	Sidewalks	1/30 yd3 (1)	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2511	Trails	1/100 yd3	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2512	Curb & Gutter	1/30 yd3 (1)	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2515	Driveways	1/30 yd3 (1)	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2517	Railroad Approach Sections	1/30 yd3 (1)	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2519	Fence construction	n/a	n/a	n/a
2524	Type A and B	n/a	n/a	n/a
2529	Patching (Full depth), rumble strip	1/30 yd3 (1)	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2530	Patching (Partial depth)	1/30 yd3 (1)	S/T 1st week, S/T 1 per month (3)	S/T 1/project (3)
2554	Thrust blocks	n/a	n/a	n/a

(1) If less than 20 yd3/ day, the engineer may waive air testing if inspection is not available and producer has exhibited consistency in prior placements

(3) Sampling and testing rate if no other concrete supplied. Use structural or paving test results to cover non structural concrete items.