


SPAN LENGTHS			
BRIDGE LENGTH	SPAN 1	SPAN 2	SPAN 3
160'-0	48'-0	64'-0	48'-0
180'-0	54'-0	72'-0	54'-0
200'-0	60'-0	80'-0	60'-0
220'-0	66'-0	88'-0	66'-0
240'-0	72'-0	96'-0	72'-0
260'-0	78'-0	104'-0	78'-0
280'-0	84'-0	112'-0	84'-0
300'-0	90'-0	120'-0	90'-0
320'-0	96'-0	128'-0	96'-0
340'-0	102'-0	136'-0	102'-0

REINFORCEMENT DIMENSIONS ℄-℄ ABUTMENT BEARINGS	160'-0	180'-0	200'-0	220'-0	240'-0	260'-0	280'-0	300'-0	320'-0	340'-0
X (F.T.-IN.)	163'-0	183'-0	203'-0	223'-0	243'-0	263'-0	283'-0	303'-0	323'-0	343'-0
Y (IN.)	3	3	3	3	3	3	3	3	3	3
Z (SPACES)	195	219	243	267	291	315	339	363	387	411

CONCRETE PLACEMENT DIAGRAM
SHOWING SLAB REINFORCING



TRANSVERSE SLAB
CONSTRUCTION JOINT

- NOTES:
- ROADWAY SLAB SHALL BE PLACED IN SECTIONS AND SEQUENCES INDICATED. ALTERNATE PROCEDURES FOR PLACING SLAB CONCRETE MAY BE SUBMITTED FOR APPROVAL TOGETHER WITH A STATEMENT OF THE PROPOSED METHOD AND EVIDENCE THAT THE CONTRACTOR POSSESSES THE NECESSARY EQUIPMENT AND FACILITIES TO ACCOMPLISH THE REQUIRED RESULTS.
 - WEIGHT OF STRUCTURAL STEEL SHOWN ON THIS SHEET INCLUDES: BEAMS, DIAPHRAGMS, SPLICES, SHEAR STUDS, BEARINGS, WELDS AND BOLT HARDWARE.
 - QUANTITY OF STRUCTURAL STEEL SHOWN ON THIS SHEET IS TABULATED FOR BENT PLATE DIAPHRAGM OPTION. PAYMENT FOR STRUCTURAL STEEL WILL BE BASED ON THE QUANTITIES SHOWN. THE CONTRACTOR MAY CHOOSE TO PROVIDE ROLLED CHANNEL DIAPHRAGMS AT NO ADDITIONAL COST.
 - QUANTITY OF STRUCTURAL STEEL SHOWN ON THIS SHEET IS BASED ON THE USE OF 5" HIGH SHEAR STUDS. CONTRACTOR WILL BE PAID ON AMOUNT SHOWN, BUT IS REQUIRED TO ADJUST HEIGHT OF STUDS AS REQUIRED PER "BEAM PLAN AND ELEVATION" SHEET.

CONCRETE PLACEMENT QTYs. (SUPERSTRUCTURE PLUS INTEGRAL ABUTMENTS)		160'-0	180'-0	200'-0	220'-0	240'-0	260'-0	280'-0	300'-0	320'-0	340'-0
SLAB, AND ABUT DIAPHRAGM, SECTION 1 & 3	CY	113.8	123.8	136.0	147.9	157.8	169.7	179.6	189.6	199.7	212.4
SLAB, SECTION 2	CY	42.1	47.4	52.7	58.0	63.2	68.7	74.0	79.2	84.5	89.8
SLAB, SECTION 4 & 5	CY	56.1	63.2	70.2	77.3	84.3	91.6	98.6	105.7	112.7	119.8
ABUTMENT WINGS	CY	7.2	7.2	7.2	7.6	7.6	7.6	7.6	7.6	7.6	13.9
ABUTMENT FOOTINGS	CY	35.0	35.0	35.0	35.0	35.0	35.0	35.0	35.0	35.0	42.8
TOTAL	CY	254.2	276.6	301.1	325.8	347.9	372.6	394.8	417.1	439.5	478.7

ESTIMATED QTYs. (SUPERSTRUCTURE PLUS INTEGRAL ABUTMENTS)		160'-0	180'-0	200'-0	220'-0	240'-0	260'-0	280'-0	300'-0	320'-0	340'-0
NO. OF STEEL H-PILES FOR TWO ABUTMENTS (HP 10 X 57)	NO.	16	16	16	18	18	18	20	20	20	24
STRUCTURAL CONCRETE, (BRIDGE)	CY	254.2	276.6	301.1	325.8	347.9	372.6	394.8	417.1	439.5	478.7
REINFORCING STEEL EPOXY COATED	LB	74,006	81,229	88,872	96,160	103,682	111,030	118,822	126,054	133,553	143,824
BARRIER RAILS	LF	354.0	394.0	434.0	474.0	514.0	554.0	594.0	634.0	674.0	734.0
STRUCTURAL STEEL	LB	117,817	154,924	189,366	232,911	293,565	334,558	388,340	469,620	520,956	573,615

LATEST REVISION DATE <i>Thomas E. Mc Donald</i> APPROVED BY BRIDGE ENGINEER		
	STANDARD DESIGN - 40' ROADWAY, 3 SPAN BRIDGES ROLLED STEEL BEAM BRIDGES JUNE, 2010	
	SUPERSTRUCTURE QUANTITIES 0° SKEW	RS40-031-10