

At Bridge End Drains, cut Scour Protection (Scourstop and TRM) or remove rock as required to place post(s) such that Bridge End Drains abut post(s).

- ① Guardrail mounting height at barrier connection is 32 inches. Transition guardrail mounting height down to 31 inches over the length of the Barrier Transition Section.
- 2 Possible curb. See project plans.
- 3 Depending on end anchor type, BTS Post #13 may be eliminated or modified. See BA-202.

Possible Contract Item:

Steel Beam Guardrail Barrier Transition Section

Materials included in the Contract Item:

(7) 6" x 8" x 6'-0" posts

(6) 6" x 8" x 7'-0" posts (12) 6" x 12" x 19" blockouts

(1) 6" x 12" x 14¹/₄" blockout

(1) Asymmetrical Transition Section (2) 12'-6" Thrie-Beam rail sections*

(1) 6'-3" Thrie-Beam rail section*


Approved bolts, nuts, and washers


Refer to BA-200 for guardrail components

* One 18'-9" Thrie-Beam rail section may be substituted for one of the 12'-6" sections and the 6'-3" section as



STEEL BEAM GUARDRAIL **BARRIER TRANSITION SECTION**





Guardrail mounting height at barrier connection is 32 inches. Transition guardrail mounting height down to 31 inches over the length of the Barrier Transition Section.

