


Elevations and dimensions not given are as specified in the contract documents.

- ① Drill four, 5/8 inch diameter holes, 3 inches from bottom of riser pipe and insert two, #4 bars in an "X" configuration. Length of bars = $D+16$ inches
- ② Provide perforation configuration as specified in the contract documents.

	<small>REVISION</small> 2 10-21-14
	SUDAS 9040.115
	<small>SHEET 1 of 1</small>
SUDAS Standard Specifications	
SEDIMENT BASIN DEWATERING DEVICE (PERFORATED RISER)	