

1000' 65 10001 9101 \* Speed Limit before Roadwork

300'

5001

7001

125'

245'

540'

770'

- LEGEND
- Traffic Sign

25

35

45

55

- x Drum
- Channelizing Device (Vertical Panel, Type I or Type II Barricade) (to be vetabled)
- Type II Barricade (to be weighted)
- Type III Barricade
- Sequencing Arrow (Type "C")
- Work Area

7. Type II barricades will be placed in the closed lane at 1000 ft. Intervals. Where core outs, holes or uncured concrete exist within the work area,

an additional Type || barricade shall be placed just ahead of each.

3. Cones may be used as channelizing devices in the tapers and along the

5. The maximum spacing between channelizing devices in a merging taper

shall be approximately equal in feet to the speed limit before roadwork. 6. Channelizing devices shall not be intermixed on the lane line through the

4. Downstream tapers shall contain a minimum of 4 channelizing devices.

miles in advance of the lane closure, respectively.

lane line during daylight hours only.

- 8. If a ramp exit or entrance taper falls within the work area, refer to Standard Road Plans RS-65A and RS-65B for traffic control details.
- 9. A flagger shall be used to alert motorists when equipment or workers encroach within 2 feet of an open lane. The flagger shall be posted adjacent to the open traffic lane and immediately upstream of each operation. Encroachment shall be held to a minimum.
- 10. A vehicle with an amber revolving light or amber strobe light may be substituted for the Type III Barricade. Use a truck mounted attenuator (TMA) for this location if TMA is available.
- 11. Channelizing devices may be placed up to 2 feet beyond the lane line only at specific locations where actual work activity is taking place. Channelizing devices shall be returned to the lane line when the work activity has passed.

- c) SPEED LIMIT 55 signs shall be removed or covered when workers are
- d) All existing signs that conflict with 55 mph speed limit shall be removed or covered while 55 moh speed limit is in effect.
- 13. The work area may be extended an additional 2 miles provided that once the traffic control devices have placed to extend the lane closure, the traffic control devices at the beginning of the traffic control zone are moved downstream to limit the work area to 4 miles.

## FOR LANE-LINE DROPOFF OR RISE:

- 14. When the nominal thickness, placed or removed, results in a drop-off or rise of more than 2 inches adjacent to the open traffic lane, the spacing of the lane line channelizing devices shall be reduced to 50 percent of that shown. The edge of the channelizing device shall be placed within 1 foot of the drop-off or rise.
- 15. If unplanned conditions result in a drop-off or rise that exceeds 3.5 inches overnight, the contractor shall also place a temporary edge line in the open lane, 1 foot from the drop-off or rise. If the contractor chooses to use drums for the channelizing devices, the temporary edge line may be omitted. In either case, the channelizing devices shall be placed in the closed lane during nonworking hours. The channelizing devices may be placed on either surface during nonworking hours.



48" X 48"

lowa Department of Transportation Highway Division

STANDARD ROAD PLAN RS-63A

REVISION: Revised the General Notes.	REVISION NO.
	11
William Q. Steen	REVISION DATE
	10-29-02
APPROVED BY DESIGN METHODS ENGINEER	10-29-02

TRAFFIC CONTROL LAYOUT FOR RIGHT LANE CLOSURE ON DIVIDED HIGHWAY