

GENERAL NOTES:

This plan illustrates the normal construction procedure for the following: Subgrade Treatment, "Compaction with Moisture Control," "Compaction with Moisture and Density Control," "Compacting Trench Bottom" and "Special Compaction of Subgrade."

Materials and methods of construction shall be in accordance with current Standard and Supplemental Specifications.

The pay quantity for Subgrade Treatment shall be in either megagrams or cubic meters of specified material as necessary. The volume shall be based on specified depth, the treatment type as indicated, and shall include the quantity allowed for

The pay quantity for "Compaction with Moisture and Density Control" or "Compaction with Moisture Control" shall be the absolute volume for the specified depth and subgrade width

The pay quantity for "Special Compaction of Subgrade" and "Compacting Trench Bottom" shall be in meters of centerline length for the work as detailed hereon.

All dimensions given in millimeters unless noted.



DENSITY CONTROL & SPECIAL COMPACTION