Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204 Appendix T (Metric) Units

BASE REPAIR (2212) PAVEMENT REPAIR (Patches)

October 2, 2001 Supersedes April 3, 2001

<u>Sections 2529</u> and <u>2530</u>

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS		QC/ACCEPTANCE S&T						ASSURANCE, CORRELATION AND VERIFICATION S&T						
				SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT		
SOURCE INSPEC	TION															
Aggregates Fine (4110)		AS	<u>209</u>													
Aggregates Coarse (4115)		AS	<u>209</u>													
Portland Cement (4101)	Quality	AS	<u>401</u>													
Fly Ash (<u>4108</u>)	Quality	AS	<u>491.17</u>													
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS	<u>491.14</u>													
Curing Compound (4105)	Lab Tested		<u>405</u>													
Air Entraining Admixture (4103)	Quality	AB	<u>403</u>													
Granular Backfill	Gradation Quality	AS AS	CERT CERT													
Drain Tubing	Quality	AS	<u>443</u>													
Epoxy Grout		AB	<u>491.11</u>													
Joint Seal (<u>4136.02</u>)	Lab Tested	AB	436.01 436.02													
Backer Rod (4136.02)		AB	<u>436.04</u>													
Steel Reinforcing	Quality	AS	<u>451</u>													
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert B-7 Cert C-7	Type A Certification Type B Certification Type C Certification Type D Certification			DME-Dis	RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor					ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204 Appendix T (Metric) Units

BASE REPAIR (2212) PAVEMENT REPAIR (Patches)

October 2, 2001 Supersedes April 3, 2001

Sections 2529 and 2530

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND		QC/ACCEPTANCE S&T						ASSURANCE, CORRELATION AND VERIFICATION S&T						
II E IVI		R	ELATED IMS	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT		
PLANT INSPECT	ION					•				•						
Aggregates-Coarse (4115)	Grad	302 <u>306</u> <u>336</u> <u>308</u>		CONTR	3/lot	<u>I.M.</u> 301	CONTR		CORR	CONTR	1 st day +10%	<u>IM 301</u>	RCE			
	Moist			CONTR	1 / half day	1000 gm	CONTR									
	Sp. Gr.		307	CONTR	<u>I.M. 527</u>	1000 gm	CONTR									
	Quality	AS	<u>209</u>													
Aggregate- Fine (4110)	Gradation		302, <u>306</u> 336	CONTR	3/lot	<u>IM</u> <u>301</u>	CONTR	830211	CORR	CONTR	1st day+10%	IM 301 IM 301	RCE			
	Moisture	3 +	<u>308, 528</u>	CONTR	1/lot	1000 gm	CONTR	830211							See IM 528 if Moisture Probe is used	
	Sp. Gr.		<u>307</u>	CONTR	<u>IM 528</u>	1000 gm	CONTR	830211								
	Quality	AS	<u>209</u>													
Portland Cement (4101)	Quality	AS	CERT D		Each Load											
Fly Ash	Quality	AS	CERT D		Each Load											
Air Entraining Admixture		AB	<u>403</u>	>→ DME	1/lot	0.5 L	CTRL								Sample lots not previously	
Water Reducing Admixture		AB	<u>403</u>	>→ DME	1/lot	0.5 L	CTRL								reported or as directed by DME	
Retarding Admixture		AB	<u>403</u>	DME	1/lot	0.5 L	CTRL									
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification					RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor					ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204 Appendix T (Metric) Units

BASE REPAIR (2212) PAVEMENT REPAIR (Patches)

October 2, 2001 Supersedes April 3, 2001

<u>Sections 2529</u> and <u>2530</u>

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T						ASSURANCE, CORRELATION AND VERIFICATION S&T						
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT		
GRADE INSPECT	ΓΙΟΝ														
Plastic Concrete	Air Slump	$\frac{318}{318}$ $\frac{327}{327}$	RCE RCE	2/half day 2/half day		RCE RCE	830224 830224								
Reinforcing Steel Epoxy-Coated Steel	Quality Quality	AS <u>451</u> AS <u>451</u>		Each Shipment											
Calcium Chloride	Concentr.	<u>373</u>	RCE	1/lot		RCE									
Asphalt Mixes Hardened Conc. Smoothness	3+												>	Approval by DME See Plans/Specs for exclusions	
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification	DME-Dist	dent Construction Materials Entral Materials Contractor	Engineer	Project Eng	gineer	ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor							