

GENERAL NOTES:

The intent of this plan is to detail the construction of a PCC Bridge Approach Section abutting HMA pavement. The length of this section shall be 60 feet

The following items shall be considered incidental to and included in the price bid for "Bridge Approach Section":

Furnishing and installing reinforcing steel, tie bars and dowel assemblies Excavation for Modified Subbase

Furnishing and installing Polymer Grid

Furnishing and backfilling with Modified Subbase

Placing, finishing, texturing, transverse grooving, curing, all joint construction and all other materials and labor to construct "Bridge Approach Section" as detailed on this sheet

- Build 4" Sloped Curb to end of Reinforced Bridge Approach Section. See Curb Location Details (Section B-B).
- For Section A-A, Section B-B, Section C-C, Detail 'A', and Detail 'C', see Standard Road Plan RK-19A.
- Longitudinal Joints

Single Pour - Saw cut joint per detail B on Standard Road Plan RH-51. Two Pours - Use 'KS' Joint.

- Excavation limits of Modified Subbase 2' outside of pavement edge, see Standard
- The contractor may be required to saw cut the HMA pavement full depth to
- accommodate the 'B' joint. Use 'RD' joint where PCC shoulder, 'B' joint otherwise.

Iowa Department of Transportation Highway Division

ROAD PLAN

REVISION: Removed option to use granular subbase. REVISION DATE William G. Stein APPROVED BY DESIGNMETHODS ENGINEER 10-29-02

> BRIDGE APPROACH SECTION (TWO LANE, HMA PAVEMENT)