

Sampling & Testing Guide-Minimum Frequency

April 20, 2010  
Supersedes October 21, 2008

**HOT MIX ASPHALT**  
Section 2303, & 2113

Matls. IM 204  
Appendix F (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE & RELATED IMs	QUALITY CONTROL					INDEPENDENT ASSURANCE, & VERIFICATION S&T						REMARKS
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ. Note 1	SAMPLE SIZE	TEST BY	REPORT	
<b>SOURCE INSPECTION</b>														
Aggregates-Coarse (4127)		AS 209												
Aggregates-Fine (4127)		AS 209												
Hydrated Lime (4127)		AS 491.04												
Asphalt Binder		AS 437												
Emulsions & Cutbacks		AS 437												
Release Agent		AS 491.15												
<b>PLANT INSPECTION</b>														
Aggregates (2303)	Quality							V	DME	1/20,000 Mg	22 kg	CTRL		
Combined Aggregate (4127)	Gradation		RCE/ CONTR	1/lot	IM 301	CONTR		V  IA	RCE/ CONTR	Sample 1/day, Test 1 <sup>st</sup> day + 20% Systems Approach*	IM 301	DME/RCE DME	IM 216  IM 216	
	Moisture		CONTR	1/halfday	1000 gm	CONTR								Dryer Drum Plants Only
AS-Approved Source		Cert A-Type A Certification					RCE-Resident Construction Engineer/Project Engineer					IA-Independent Assurance		
ASD-Approved Shop Drawing		Cert C-Type C Certification					DME-District Materials Engineer					V-Verification		
S&T-Sampling & Testing		Cert D-Type D Certification					CTRL-Central Materials Office							
							CONTR-Contractor							

\*A project approach may be applied at the discretion of the DME at the frequency 1/project.

**NOTE:** RCE/CONTR indicates that the contractor shall assist in the sampling at the direction of and witnessed by the project engineer.

Sampling & Testing Guide-Minimum Frequency

April 20, 2010  
Supersedes October 21, 2008

**HOT MIX ASPHALT**  
Section 2303, & 2113

Matls. IM 204  
Appendix F (Metric) Units

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE & RELATED IMS	QUALITY CONTROL					INDEPENDENT ASSURANCE, & VERIFICATION S&T					REMARKS	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
<b>PLANT INSPECTION</b>														
Mineral Filler								V	DME	1/project	5 kg	DME	821278	
Asphalt Binder	DSR  Quality	AS Cert D						V  V IA	RCE/ CONTR  DME	Sample 1/day, Test 1 <sup>st</sup> 1/week 1/20,000 Mg Systems Approach	120 ml  1 L	DME  CTRL		Log all shipments
Cutback	Quality Viscosity	AS 329												Log all shipments
Emulsion	Residue	AS 360						V	RCE	1/project	1 L	DME		Plastic bottle required
<b>GRADE INSPECTION</b>														
Uncompacted Mixture:	Lab Density & Lab Voids	321, 350 325G	RCE/ CONTR	As per 2303	14 kg	CONTR		V  IA	RCE/ CONTR	As per 2303, Test 1/day Systems Approach	14 kg	DME		
	AASHTO T283	Article 2303, Section E, 2 IM 510 App C						V	RCE/ CONTR	Test 1 <sup>st</sup> Sample at 500 tons Take 2 <sup>nd</sup> Sample at 2 <sup>nd</sup> Lot (test as needed)	32 Kg	CTRL		
Compacted Mixture	Density Thickness Voids	320, 321 337						V  IA	RCE/ CONTR DME	Lot 1 lot/project*	7/lot	RCE  DME		
	Smoothness	341	CONTR	100%	100%	CONTR		V	DME	10%		DME		
AS-Approved Source ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				IA-Independent Assurance V-Verification			

\* A system approach may be applied at the discretion of the DME.

**NOTE:** A Verification sample for asphalt binder quality and aggregate quality not required under 2000 Mg of mix.

**NOTE:** RCE/CONTR indicates that the contractor shall assist in the sampling at the direction of and witnessed by the project engineer.