

CHAPTER 9
PORTLAND CEMENT CONCRETE (PCC) PAVEMENT

9.00 GENERAL -----9-1
9.01 PRE-CONCRETING CONFERENCE-----9-1
9.02 "PCC PLANT PAGE" (FORMS 800240E AND 800240M)-----9-1
9.03 USE OF COMMERCIAL READY MIX CONCRETE ON PAVING PROJECTS -----9-1
9.04 CONCRETE DELIVERY TIMES -----9-2
9.10 EQUIPMENT -----9-3
9.11 TEMPLATE FOR CHECKING GRADES ON DRIVES ON URBAN PAVING
PROJECTS-----9-3
9.12 USE AND CARE OF WHEELED SURFACE CHECKER -----9-3
9.13 ACCUMULATION OF MATERIALS IN TRANSPORTING VEHICLES-----9-3
9.14 PCC FINISHING MACHINES-----9-4
9.15 OPERATING FINISHING EQUIPMENT ON PREVIOUSLY PLACED CONCRETE IN
MULTIPLE-LANE CONSTRUCTION WORK -----9-4
Protection of Pavement-----9-4
Surface Cleaning-----9-4
Other Equipment -----9-4
9.16 EQUIPMENT WEIGHT LIMITATIONS ON NEW PAVEMENTS & PCC
OVERLAYS -----9-5
Joint Cleaning & Sealing Equipment Used on New Pavement & Unbonded PCC
Overlays -----9-5
Sawing Equipment Used on Bonded PCC Overlays-----9-5
Joint Cleaning and Sealing Equipment Used on Bonded PCC Overlays -----9-5
9.20 PAVEMENT JOINTS-----9-6
9.21 JOINT SAWING -----9-6
9.22 CLEANING JOINTS -----9-6
9.23 SEALING SAWED JOINTS-----9-6
Joint Filling -----9-6
Sealing Equipment-----9-7
Backer Rod -----9-7

9.24 RESERVED FOR FUTURE USE -----9-7

9.25 CD, ED, EE & EF JOINTS, AND OTHER DOWELED SUPPORT ASSEMBLIES -----9-7

    Expansion Joints -----9-7

    Bond Breakers -----9-7

    Dowel Tolerances -----9-8

    Dowel Assembly Placement -----9-8

    Marking Joint Locations -----9-9

    Blanking Bands -----9-9

9.26 LONGITUDINAL JOINTS DESIGN -----9-9

    Tie Bar Placement -----9-10

9.27 LONGITUDINAL JOINT (L JOINT) TIE-STEEL INSPECTION ----- 9-10

    Procedure ----- 9-10

    Frequency ----- 9-11

    Documentation ----- 9-11

    Tolerance ----- 9-11

    Out-of-Tolerance ----- 9-11

    Retrofit ----- 9-12

    Price Adjustments ----- 9-12

**9.30 INTAKES AND UTILITY ACCESSES ----- 9-12**

9.31 INTAKE CONSTRUCTION ON PAVING JOBS ----- 9-12

9.32 BOX-OUTS FOR UTILITY ACCESSES ----- 9-12

9.33 BOX-OUTS FOR SLIPFORM PAVING ----- 9-12

**9.40 SURFACE FINISHING ----- 9-14**

9.41 USE OF WATER IN FINISHING CONCRETE ----- 9-14

9.42 MICROTEXTURE AND MACROTEXTURE ----- 9-14

9.43 GROOVE DEPTH DETERMINATION ----- 9-16

9.44 PAVEMENT CROWN ----- 9-16

9.45 STRAIGHTEDGEING PAVEMENT SURFACE ----- 9-17

9.46 PAVEMENT DATE STAMPING ----- 9-17

**9.50 PROTECTION, CURING, AND REPAIR ----- 9-18**

9.51 PREVENTION OF RAIN DAMAGE TO PLASTIC CONCRETE----- 9-18

9.52 CURING OF KEYED AND DOWELED JOINTS ----- 9-18

9.53 REPAIR OF DEFICIENT PAVEMENT ----- 9-18

    Recommended Repair Method ----- 9-19

9.54 MUD BALL REPAIR ----- 9-20

9.55 COLD WEATHER PAVING AND PLANT OPERATIONS ----- 9-21

    Cold Weather Pavement Protection ----- 9-21

    Cold Weather Plant Operation ----- 9-21

9.56 CURING ----- 9-22

**9.60 CONCRETE MATERIALS ISSUES ----- 9-23**

9.61 CONCRETE SAMPLING LOCATIONS----- 9-23

9.62 TESTING PROCEDURES ----- 9-23

9.63 AIR ENTRAINMENT IN PLASTIC CONCRETE----- 9-23

    Control of Air Content ----- 9-23

    Verification ----- 9-24

    Air Content Outside Tolerance----- 9-24

    Air Content More Than 0.5% Below Lower Target Content ----- 9-24

    Aggregate Correction Factor ----- 9-24

9.64 CONCRETE VIBRATION AND CONSOLIDATION ----- 9-25

9.65 PAVEMENT THICKNESS CORES ----- 9-26

9.66 PAVEMENT SMOOTHNESS----- 9-26

9.67 QUALITY MANAGEMENT CONCRETE (QM-C) ----- 9-26

    Measurement and Payment ----- 9-27

**9.70 PCC Patching ----- 9-28**

9.71 Full-Depth PCC Patches ----- 9-28

    Materials ----- 9-28

    PCC Placement----- 9-28

    Curing ----- 9-29

    Patch Thickness ----- 9-29

    Saw Cuts ----- 9-29

9.72 Partial-Depth PCC Patches----- 9-30

    Materials ----- 9-30

