

CHAPTER 11 STRUCTURES

11.00 INTRODUCTION	11-1
11.01 REMOVAL OF BRIDGES	11-1
11.02 GUIDANCE FOR HEAVY EQUIPMENT & MATERIALS ON BRIDGES	11-1
11.03 TEMPORARY STRUCTURES FOR THE PROTECTION OF THE PUBLIC	11-3
11.05 PILE DRIVING CAP AND HAMMER INFORMATION	11-3
11.10 EARTHWORK FOR STRUCTURES	11-5
11.11 EXCAVATION	11-5
11.12 BACKFILLING STRUCTURES	11-5
Culverts	11-5
Bridge Abutments	11-5
Measurement and Payment	11-6
11.20 FOUNDATIONS	11-7
11.21 STAKING AND CHECKING LOCATIONS OF STRUCTURES	11-7
Check and Double Check	11-7
Documentation	11-8
Common Survey Errors to Avoid	11-8
Encountering Old Substructures	11-8
Setting Bench Marks (Post Construction)	11-8
11.22 PILING AND PILE DRIVING	11-9
Pile Driving	11-9
Vibratory Hammers	11-9
Gravity Hammers	11-10
Diesel Hammers	11-10
Bearing and Penetration	11-11
Retaps	11-11
Dynamic Pile Analyzer	11-12
Static Load Tests	11-13
11.23 SPLICING PILE	11-13
Welding Steel Pile	11-13

	Concrete Pile-----	11-16
11.24	PILING ACCEPTANCE-----	11-17
	Steel Pile-----	11-17
	Wood Pile-----	11-17
	Steel Pile Cutoffs-----	11-18
11.25	WAVE EQUATION-----	11-18
	Hammer Data Form-----	11-18
	Driving Graphs-----	11-18
	Log of Piling Driven-----	11-20
11.26	PREBORED HOLES-----	11-21
	Typical Preboring-----	11-21
	Special Prebore Situations-----	11-22
	Bentonite-----	11-22
11.27	DRILLED SHAFTS-----	11-23
11.30	BRIDGES-----	11-24
11.31	FALSEWORK-----	11-24
	Temporary Fastenings-----	11-24
	Falsework Plans-----	11-24
	Falsework Inspection-----	11-25
	Falsework Foundations-----	11-25
	Materials-----	11-26
	Project Quality-----	11-28
	Miscellaneous Items-----	11-30
	Falsework Adjacent To Traffic-----	11-30
	Field Changes-----	11-30
	Inspection during Concrete Placement-----	11-30
	Removal of Falsework-----	11-31
11.32	BRIDGES - STEEL BEAM-----	11-31
	Prebolting Meeting-----	11-32
	Erecting Steel Beams-----	11-33
	High Strength Fasteners-----	11-34
	Painting-----	11-43
11.33	BRIDGES - CONCRETE BEAM-----	11-43

Precast - Prestressed Deck Panels ----- 11-43

Pretensioned Prestressed Concrete Beam (PPC Beam) Erection ----- 11-44

Diaphragms (Steel or Concrete) ----- 11-44

11.40 REINFORCEMENT ----- 11-46

 General Placement Guidelines for Bridge Reinforcing Steel----- 11-46

11.41 PLACEMENT AND CHECKING (BRIDGE FLOORS) ----- 11-46

 Slab Thickness----- 11-46

 Clearance of Bottom Reinforcement ----- 11-46

 Clearance of Top Mat Reinforcement----- 11-47

 Cover Over Top Mat of Reinforcement ----- 11-47

 Slab Bridges ----- 11-47

 Special Attention Areas----- 11-47

11.42 EPOXY COATED REINFORCEMENT ----- 11-48

 Care and Handling ----- 11-48

 Field Inspection ----- 11-50

 Repair of Damaged Coating ----- 11-50

11.43 CAGE STEEL (DRILLED SHAFTS) ----- 11-51

11.44 SPLICING ----- 11-51

 Splice Approval ----- 11-51

11.45 PAYMENT FOR REINFORCING STEEL ----- 11-52

11.50 CONCRETE (STRUCTURAL, CLASS X, AND FLOWABLE MORTAR) ----- 11-53

11.51 PCC PLANT PAGE (FORMS 800240E AND 800240M) ----- 11-53

11.52 USE OF READY MIXED STRUCTURAL CONCRETE ----- 11-53

 Prepour Meeting ----- 11-53

 Inspector’s Checklist ----- 11-53

11.53 ADMIXTURES ----- 11-57

 Air Entraining Admixtures ----- 11-58

 Water Reducing Admixtures – Regular ----- 11-58

 Water Reducing Admixtures - Super Plasticizers ----- 11-59

 Retarding Admixtures ----- 11-59

 Accelerating Admixtures ----- 11-60

 Corrosion Inhibiting Admixtures ----- 11-60

Finely Divided Mineral Admixtures-----	11-61
Pozzolan Materials -----	11-61
Fly Ash (Class C & F) -----	11-61
Silica Fume -----	11-61
Cementitious Materials -----	11-61
Ground Granulated Blast Furnace Slag (GGBFS)-----	11-61
11.54 USE OF INSULATED FORMS FOR PROTECTION -----	11-62
Checking Temperature of Concrete -----	11-62
11.55 DECK PLACEMENT AND HEAT OF HYDRATION -----	11-63
Deck Placement -----	11-63
Deck Concrete Temperature and Curing-----	11-63
Placement Considerations -----	11-64
Field Documentation -----	11-66
Heat of Hydration-----	11-66
11.56 PLACEMENT METHODS (PUMPING, BELTING, AND CRANE BUCKET) -----	11-66
Crane and Bucket -----	11-66
Belt Placement -----	11-67
Pump Placement -----	11-67
11.57 FORM REMOVAL-----	11-68
Setting Beams -----	11-68
11.58 CLASS 3 CONCRETE SURFACE FINISH (RAIL AND BEAMS) -----	11-68
Approval of Materials-----	11-68
Application of Finish -----	11-68
Concrete Railings -----	11-69
11.59 FLOWABLE MORTAR-----	11-69
Backfilling Culverts - Typical Grading-----	11-70
Plugging Culverts -----	11-72
Backfilling Culverts - Under Bridges-----	11-72
Filling Voids Between Culverts -----	11-72
11.60 DECKS AND OVERLAYS-----	11-74
11.61 DECK OVERLAY PREPARATION -----	11-74
Class A Floor Repair -----	11-74
Class A Surface Preparation -----	11-75

	Work on Adjacent Lanes -----	11-75
11.62	SEQUENCE OF POURING -----	11-76
	Use of Retarders -----	11-77
	Concrete Bridge Floors -----	11-80
	Placement Methods -----	11-86
11.63	INSTALLATION OF JOINTS -----	11-87
	Preformed Neoprene Joints -----	11-87
	Steel Extruded Expansion Joints (Strip Seals) -----	11-87
11.64	BRIDGE FLOORS -----	11-89
	Finishing and Equipment -----	11-89
	Profile Grades - Overlays -----	11-89
	Transverse Grooving -----	11-90
	Longitudinal Grooving In Hardened Concrete -----	11-90
	Missed Texturing -----	11-90
11.65	CONCRETE -----	11-91
	Concrete Mobile Mixers -----	11-91
	Frequency of Checks -----	11-91
	Density Testing -----	11-91
11.66	APPROACH SECTIONS -----	11-92
	Approach Pavements to Bridge Abutments -----	11-92
	“Movable” Abutments -----	11-93
	“Fixed” Abutments -----	11-94
	Bridge Approach Tapers -----	11-94
	Shoulder Maintenance -----	11-94
11.67	SMOOTHNESS OF BRIDGE DECKS -----	11-95
	Checklist -----	11-95
	Specification 2317 -----	11-96
	Surface Checking -----	11-97
11.70	BARRIER RAILS -----	11-98
11.71	CONCRETE F-SHAPE, OPEN, AND RETROFIT RAIL -----	11-98
	Rail Concrete Placement and Bridge Deck Falsework -----	11-98
11.72	SLIP FORM BARRIER RAIL -----	11-99
	Longitudinal Cracks -----	11-99

Reinforcement -----	11-99
Reinforcement Bar Cover -----	11-99
Misalignment and Nonuniform Top Elevation -----	11-99
Shadowing -----	11-100
Mix Design for Slip Form and Cast-in-Place -----	11-100
Curing of Slip Form Barrier Rail -----	11-101
Expansion Joint Construction in Barrier Rail -----	11-101
11.73 CAST-IN-PLACE (RETROFIT) BARRIER RAIL-----	11-102
Preventing Dowel Installation Damage of Conduit-----	11-103
11.74 CAST-IN-PLACE OPEN BARRIER RAIL FORM REMOVAL -----	11-103
11.80 REINFORCED CONCRETE CULVERTS-----	11-104
11.81 DESIGN CHANGES ON CULVERTS-----	11-104
11.82 INSTALLING REINFORCING STEEL, PLACING CONCRETE, AND FORM REMOVAL -----	11-104
Installing Reinforcing Steel -----	11-104
Placing Concrete -----	11-105
Removal of Wall Forms-----	11-105
Removal of Slab Forms-----	11-106
11.83 BOX CULVERT CURTAIN WALLS-----	11-106
Sheet Pile Curtain Wall -----	11-106
Reinforcement Placement -----	11-106
11.84 BOX CULVERT BELL JOINTS -----	11-107