

**Jasper County Rest Area I-80 WB
Purchasing Bid Proposal 13350**

Vendor Questions:

- 1. I need for the main structure, but no specific size(s) for the glulam wood members both Small and Large Shelter(s) on page A14.02.**

Response:

The sizes are as noted on sheet S.3.

- 2. Will you allow broken concrete to be placed in the lagoon area?**

Response:

No. Broken concrete should be removed from the project.

- 3. I've been looking thru the spec and plans, there is no mention of who is responsible for the lay out/ and surveying. Can you direct me where in the specifications or plans this is addressed?**

Response:

Section 2526.03.A of the Standard Specifications states that the contractor shall furnish all survey necessary for construction of the project before work begins in the area. This would be valid unless the consultant placed something to the contrary in their construction documents.