



Bid Response

		Date Bids Due: January 7, 2016	Time of Bid Opening: 1:00 P.M.	Bid Opening Location: 800 Lincoln Way, Ames, IA	
Proposal Number: 15602	Description: Electrical upgrade for Centerville Maintenance Garage Brine Building				
Contract to Begin:	Contract to End:	Proposal Guaranty Amount: N/A	Performance Bond (Y/N) Y	Liquidated Damages: \$150.00 per day	
Purchasing Agent: Laura Linduski	E-mail Address: laura.linduski@dot.iowa.gov	Phone: 515-239-1429	Fax: 515-239-1538		
Company Name:			Federal Tax ID:		
Street Address:		City:	State:	Zip Code:	
Supplier Contact (type or print)	E-mail Address:	Phone:	Fax:		
Supplier agrees to sell items/services at the same prices, terms and conditions to any other state agency. Regent or Political Subdivision upon request. Please check Yes or No. <input type="checkbox"/> Yes <input type="checkbox"/> No			Are you an Iowa Targeted Small Business? <input type="checkbox"/> Yes <input type="checkbox"/> No		

GENERAL INFORMATION/PROPOSAL STATEMENT

The entire contents of this Proposal, Addendums to the Proposal, Specifications, Supplemental Terms and Conditions, Standard Terms and Conditions, and Schedule of Prices shall become part of the contract or purchase order. **Faxed or email bids will be accepted.**

We certify that all materials, equipment and/or services proposed meet or exceed the specifications and will be supplied in accordance with the entire contents of this proposal including delivery schedules.

Standard Terms and Conditions for Quotations

Acceptance/Rejection: The State of Iowa reserves the right to accept or reject any or all bids and to waive irregularities or technicalities, provided such waiver does not substantially change the offer or provide a competitive advantage to any vendor, in the judgment of the Iowa DOT. The Iowa DOT also reserves the right to accept that bid which is deemed to be in the best interests of the state. Any unauthorized changes, additions, or conditional bids including any ties to another bid or proposal or any reservations about accepting an award or entering into a contract, may result in rejection of the bid.

Method of Award: Award shall be made to the lowest responsible, responsive bidder unless otherwise specified. By virtue of statutory authority preference will be given to products and provisions grown and coal produced within the State of Iowa.

Contracts: Successful contractor(s) may be sent either a formal Contract or a purchase order. The contractor may not assign the contract to another party without written authorization from the Iowa DOT Purchasing Section.

Pricing and Discount: Unit prices shown on the documents shall be quoted as the price per unit (e.g., gal., case, each, etc.) as stated on the request. If there is a discrepancy between the unit bid prices, extension, or total amount of bid, the unit prices shall prevail. Unless otherwise indicated, prices shall be firm for the duration of the contract or purchase. Discounts for early payment are allowed, but not considered in award of the contract.

Signed _____ Date _____

Schedule of Prices

Project Description: Electrical upgrade for an existing brine building located in Centerville Maintenance Garage.

Item No.	Description	Quantity	Unit/Price	Total Bid Amount
1	Vendor to provide all materials, labor, and equipment necessary to demolish the existing electrical system and install an electrical upgrade according to all plans and specification.	1 Job	Lump/Sum	\$ _____

I hereby certify that this Bid Response meets or exceeds the minimum requirements including specifications and addendums.

Contact Person: _____

 (Print Name)

Authorized
 Signature: _____

Company: _____

Address: _____

 (City) (State) (Zip Code)

Phone No: _____

Email: _____ Fax No.: _____

I acknowledge receipt of addendums.: _____



IOWA DOT
Iowa Department of Transportation
Standard Terms and Conditions
For
Bid Proposals/Contracts
-INFORMAL-

Informal - means a limited solicitation type of procurement where a sufficient number of quotation or bids from qualified sources are obtained and the aggregate amount of the purchase is less than \$50,000.

The entire contents of this bid proposal shall become a part of a contract or purchase order. In case of a discrepancy between the contents of the bid documents, the following items listed by descending order shall prevail:

- Addendums to the bid proposal
 - Bid Proposal-
 - Schedule of Prices
 - Specifications
 - Plans and Drawings
 - Supplemental Terms and Conditions
 - Standard Terms and Conditions
- (Example -if there is a statement in the specifications that contradicts a statement in the Standard Terms and Conditions, the statement in the specifications shall apply)

Preparation of Bid Response: All bid responses must address all aspects of the proposal including clearly answering all questions within the proposal. Bid responses must be typed or completed in ink and submitted on the forms supplied by the Iowa DOT.

Bid responses must be signed and received prior to the bid opening date and time as indicated on the Bid Response cover page or bid opportunity. The signed, submitted quotation or bidder's proposal shall become the official bid response to be considered for award.

Bid responses may be sent by email, fax, weblink, or delivered by a courier that ensures timely delivery.

A. Bid Proposal

1. **Bid Opening:** Bid openings are made public and conducted at the Iowa DOT, Ames complex unless otherwise specified. Bid Responses received after the time of the bid opening will be returned to the bidder and considered non-compliant.
2. **Communications:** Questions concerning this proposal should be directed to the purchasing agent listed on the bid proposal. Inquiries can be written, phoned, or faxed. In all cases, written communication will take precedence over verbal communication.
3. **Pricing and Discount:** Unit prices shown on the bid/response shall be quoted as the price per unit (e.g., gal., case, each, etc.) as stated in the bid proposal. If there is a discrepancy between the unit bid prices, extension, or total amount of bid, the unit prices shall prevail. Unless otherwise indicated, prices shall be firm for the duration of the contract or purchase. Discounts for early payment are allowed, but not considered in award of the contract.
4. **Acceptance/Rejection:** The Iowa DOT reserves the right to accept or reject any or all bids and to waive irregularities or technicalities, provided such waiver does not substantially change the offer or provide a competitive advantage to any supplier(s). The Iowa DOT also reserves the right to accept that bid which is deemed to be in the best interests of the state. Any unauthorized changes, additions, or conditional bids including any ties to another bid or proposal or any reservations about accepting an award or entering into a contract, may result in rejection of the bid. Bids must remain available for award for thirty (30) days from date of bid opening.
5. **Bid Results & Disclosure:** A bid tabulation will be sent to all responsive bidders and may be posted on the Iowa DOT website at www.iowadot.gov/purchasing under the *Bid Award link* referencing the proposal number with an award recommendation indicated. At the conclusion of the selection process, the contents of all received bid responses will be placed in the public domain and be open to inspection by interested parties, according to state law. Trade secrets or proprietary information that are recognized as such and are protected by law may be withheld if clearly identified as such in the proposal.

6. **Quality:** All material shall be new and of first quality. Items which are used, demonstrators, refurbished, obsolete, seconds, or which have been discontinued are unacceptable without prior written approval by the Iowa DOT.
7. **Recycled Content:** The Iowa Code encourages purchase of products and materials with recycled content, including but not limited to paper products, oils, plastic products, compost materials, aggregate, solvents, and rubber products. Recycled items or alternatives must be noted in the bid response, if known.
8. **Shipping Terms:** Deliveries shall be F.O.B. Destination unless otherwise specified. All deliveries shall be accompanied by a packing slip indicating the Supplier, quantities shipped, and the purchase order number(s). All delivery charges shall be included in the bid price and paid by the Supplier. No collect C.O.D. deliveries shall be accepted. When entering into a contract, the Supplier shall notify the freight company that all freight and delivery charges are to be prepaid by the Supplier. Goods delivered to the Iowa DOT Distribution Center at 800 Lincoln Way, Ames, IA shall be received between the hours of 7:00 a.m. and 3:00 p.m. on any day except Saturday, Sunday, or a holiday. For deliveries to other Iowa DOT locations, the Supplier may contact the destination location for available times to deliver as not all Iowa DOT locations have the same business hours. The Iowa DOT will not be liable for any freight claims or unpaid freight bills arising from contract or purchase order issues.

B. Award

The binding agreement (award) may be issued in the form a purchase order or contract or both depending on the requirements and complexity of the agreement.

1. **Method of Award:** Award shall be made to the lowest responsible, responsive bidder whose bid meets the requirements of the solicitation and is the most advantageous to the Iowa DOT unless otherwise specified. An Iowa bidder will be given preference over an out-of-state bidder when bid responses are equal in all aspects and are tied in price. By virtue of statutory authority preference will be given to products and provisions grown and coal produced within the State of Iowa.
2. **Award Protests:** Protests of award recommendations are to be addressed to the Director of Purchasing, and shall be made in accordance with paragraph 761--20.4(6)"e" of the Iowa Administrative Code.
3. **Contracts:** Successful contractor(s) may be sent either a formal Contract, Notification of Award or purchase order as confirmation of acceptance and award. Any of these binding agreements shall be for the term stated in the bid proposal or on a purchase order and may be renewed for additional period(s) under the same terms and conditions upon mutual agreement as defined. The successful bidder may not assign a contract to another party without written authorization from the Iowa DOT Purchasing Section. A service contract, including all optional renewals, shall not exceed a term of six years unless a state agency obtains a waiver of this provision pursuant to rule 11-118-11(3).
4. **Payment Terms:** The Iowa DOT typically pays properly submitted vendor invoices within thirty (30) days of receipt, providing goods and/or services have been successfully delivered, installed or inspected (if required), and accepted. Invoices presented for payment must be only for quantities received by the Iowa DOT and must reference the purchase order number or contract to be submitted for processing.
5. **Default:** Failure of the Supplier to adhere to specified delivery schedules or to promptly replace rejected materials shall render the Supplier liable for all costs in excess of the bid price when alternate procurement is necessary. This shall not be the exclusive remedy and the Iowa DOT reserves the right to pursue other remedies available to it by law or under the terms of the binding agreement.
6. **Default:** Failure of a Contractor other than a Supplier to meet any specified project completion deadline shall render the Contractor liable for all costs incurred by the Iowa DOT that were: a) necessary to meet said deadline; or b) necessary to complete said project after said deadline. This shall not be the exclusive remedy and the Iowa DOT reserves the right to pursue other remedies available to it by law or under the terms of the agreement.

C. General

1. **Administrative Rules:** For Additional details on the rules governing the actions of the Iowa DOT Purchasing Section, refer to 761 IAC, Chapter 20, Iowa Administrative Code, entitled "Procurement of Equipment, Materials, Supplies and Services".
2. **Affirmative Action:** The Contractor (and also subcontractor, vendor or supplier) is prohibited from engaging in discriminatory employment practices forbidden by federal and state law, executive orders and rules of the Iowa Department of Management, pertaining to equal employment opportunity and affirmative action. Contractor may be required to have a copy of their affirmative action program on file, containing goal and time specifications. Contractors doing business with Iowa in excess of \$5,000 annually and employing 50 or more full time employees may be required to file with the Iowa Department of Management a copy of their affirmative action plan. Failure to fulfill these non-discrimination requirements may cause the contract to be canceled and the contractor declared ineligible for future state contracts or subject to other sanctions as provided by law or rule.
3. **Applicable Law:** The contract shall be governed under the laws of the State of Iowa. The contractor shall at all times comply with and observe all federal and state laws, local laws, ordinances, and regulations which are in effect during the period of a contract and which in any manner affect the work or its conduct. Any legal action relating to a contract shall only be commenced in the Story County, Iowa, District Court or the United States District Court for the Southern District of Iowa.
4. **Conflict of Interest:** No state or county official or employee, elective or appointive shall be directly or indirectly interested in any contract issued by the Iowa DOT, see Code of Iowa 314.2.
5. **Debarment and Vendor Suspension:** By submitting a proposal, the contractor is certifying that it and its principals and/or subcontractors are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by the State of Iowa or any Federal department or agency.
6. **Equal Opportunity:** Firms submitting bids must be an "Equal Opportunity Employer" as defined in the Civil Rights Act of 1964 and in Iowa Executive Order Number Thirty-four.
7. **Infringement:** Goods shall be delivered free of the rightful claim of any third party by way of infringement. Contractor shall indemnify and save harmless the State of Iowa and the Iowa DOT against all claims for infringement of, and/or royalties claimed under, patents or copyrights on materials and equipment furnished under this bid.
8. **Records Audit:** The contractor agrees that the Auditor of the State of Iowa or any authorized representative of the state, and where federal funds are involved, the Comptroller General of the U.S. Government, shall have access to and the right to examine, audit, excerpt, and transcribe any directly pertinent books, documents, papers, and records of the contractor relating to orders, invoices, or payments of a contract or purchase order.
9. **Targeted Small Businesses:** The Iowa DOT seeks to provide opportunities for women and/or minority small business enterprises. To apply for certification as an Iowa Targeted Small Business, contact the Iowa Department of Inspection and Appeals (515-281-5796). Contractors shall take documented steps to encourage participation from Targeted Small Businesses for the purpose of subcontracting and supplying of goods or services or both.
10. **Taxes:** Prices quoted shall not include state or federal taxes from which the state is exempt. Exemption certificates will be furnished upon request.
11. **Termination:**
 - **Termination Due to Lack of Funds or Change in Law**

The Iowa DOT shall have the right to terminate this Contract without penalty by giving thirty (30) days written notice to the vendor as a result of any of the following:
 - Adequate funds are not appropriated or granted to allow the Iowa DOT to operate as required and to fulfill its obligations under contract.
 - Funds are de-appropriated or not allocated or if funds needed by the Iowa DOT, at the Iowa DOT's sole discretion, are insufficient for any reason.
 - The Iowa DOT's authorization to operate is withdrawn or there is a material alteration in the programs administered by the Iowa DOT.
 - The Iowa DOT's duties are substantially modified.

Following a 30 day written notice, the Iowa DOT may terminate a binding agreement in whole or in part without the payment of any penalty or incurring any further obligation to the Supplier. Following termination upon notice, the Supplier shall be entitled to compensation upon submission of invoices and proper proof of claim for goods and services under contract up to and including the date of termination.

Section 1 Introduction

1.1 Purpose & Overview of the RFB Process

The purpose of this Request for Bid (RFB) is to solicit Bid Responses from responsible, responsive Bidders to provide the goods and/or services identified and described further in Section 3 of this RFB. The Iowa DOT may renew the contract(s) for up to the number of annual renewals as indicated. Any contract(s) resulting from the RFB shall not be an exclusive contract.

1.2 General

1.2.1 The owner of these projects is the Iowa Department of Transportation, 800 Lincoln Way, Ames, IA 50010

Project Location: Centerville Maintenance Brine Building, 23619 Hwy. 5 South, Centerville, IA 52544

2.1 Issuing Agent

The Issuing Agent, identified on the cover page is the sole point of contact regarding the RFB from the date of issuance until the notice of intent to award is issued (selection of the successful contractor).

2.2 Restriction on Communication

From the issue date of this RFB until the notice of intent to award is issued (announcement of the successful bidder), bidders may contact only the Issuing Agent.

The Issuing Agent will respond only to questions regarding the procurement process. Questions related to the interpretation of this RFB must be submitted in writing to the Issuing Officer by the deadline found in the Procurement Timetable listed immediately after the cover sheet. Verbal questions related to the interpretation of this RFB will not be accepted. Questions related to the interpretation of this RFB must be submitted as provided in section 2.5. Contractors may be disqualified if they contact any state employee other than the Issuing Agent. *Exception: Contractors may contact the State Targeted Small Business Office on issues related to the preference for Targeted Small Businesses. See Section 2.32.*

In NO CASE shall verbal communication override written communications. Only written communications are binding on the State.

The Iowa DOT assumes no responsibility for representations concerning conditions made by its officers or employees prior to the execution of a contract, unless such representations are specifically incorporated into this RFB. Verbal discussions pertaining to modifications or clarifications of this RFB shall not be considered part of the RFB unless confirmed in writing. All such requests for clarification shall be submitted in writing. Any information provided by the Contractor verbally shall not be considered part of that Contractor's proposal. Only written communications from the Contractor and received by the Department shall be accepted.

With the exception of the written Bid Response which must be submitted by Contractors in accordance with Section 2 herein, communications between the Issuing Agent and Contractors may be conducted by regular prepaid US mail, courier service, e-mail or facsimile transmission.

2.3 Downloading the RFB from the Internet

All correspondence for this Bid Proposal will be posted on the Iowa DOT's website at www.iowadot.gov/purchasing/lettingschedule. **Bidders are required** to visit the Iowa DOT's home page periodically for any and all addendums or other pertinent information regarding this bid opportunity.

2.4 Submission of Bid Responses

The Iowa DOT must receive Bid Responses addressed to the Department of Transportation, Purchasing Section, 800 Lincoln Way, Ames, Iowa 50010 before the deadline. **This is a mandatory requirement and will not be waived by the Iowa DOT.** Any Bid Response received after this deadline will be rejected and returned unopened to the contractor.

Contractors mailing Bid Responses must allow ample mail delivery time to ensure receipt by the Iowa DOT on or before the due date. Postmarking by the due date will not substitute for actual receipt of the Bid Response.

Electronic mail and faxed Bid Responses will be accepted.

Contractors must furnish all information necessary to evaluate the Bid Response. Bid Responses that fail to meet the mandatory requirements of the RFB will be disqualified. Verbal information provided by the Contractor shall not be considered part of the Contractor's Bid Response.

2.5 Nonmaterial and Material Variances

The Iowa DOT reserves the right to waive or permit cure of nonmaterial variances in the Bidder's Bid Response if, in the judgment of the Iowa DOT, it is in the Iowa DOT best interest to do so. Nonmaterial variances include minor informalities that do not affect responsiveness; that are merely a matter of form or format; that do not change the relative standing or otherwise prejudice other Contractors; that do not change the meaning or scope of the RFB; or that do not reflect a material change in the services. In the event the Iowa DOT waives or permits cure of nonmaterial variances, such waiver or cure will not modify the RFB requirements or excuse the Contractor from full compliance with RFB specifications or other contract requirements if the Contractor is awarded the contract. The determination of materiality is in the sole discretion of the Iowa DOT.

2.6 Reference Checks

The Iowa DOT reserves the right to contact any reference to assist in the evaluation of the Bid Response, to verify information contained in the Bid Response and to discuss the Contractor's qualifications and the qualifications of any subcontractor identified in the bidders Bid Response.

2.7 Information From Other Sources

The Iowa DOT reserves the right to obtain and consider information from other sources concerning a Contractor, such as the Contractor's capability and performance under other contracts, the qualifications of any subcontractor identified in the Contractor's Bid Response, specifically, the Contractor's financial stability, past or pending litigation, and publicly available information.

2.8 Verification of Bid Response Contents

The content of a Bid Response submitted by a Contractor is subject to verification. Misleading or inaccurate responses shall result in disqualification and rejection of the Bid Response.

2.9 Criminal History and Background Investigation

The Contractor hereby explicitly authorizes the Iowa DOT to conduct criminal history and/or other background investigation(s) of the Contractor, its officers, directors, shareholders, partners and managerial and supervisory personnel retained by the Contractor for the performance of the contract.

2.10 Bid Response Clarification Process

The Iowa DOT reserves the right to contact a Contractor after the submission of Bid Response for the purpose of clarification to ensure mutual understanding.

This contact may include written questions, interviews, site visits, a review of past performance if the Contractor has provided goods or services to the Iowa DOT or any other political subdivision wherever located, or requests for corrective pages in the Contractor's Bid Response. The Iowa DOT will not consider information received if the information materially alters the content of this Bid Proposal or alters the type of goods and services the Contractor is offering to the Iowa DOT. An individual authorized to legally bind the Contractor shall sign responses to any request for clarification. Responses shall be submitted to the Iowa DOT within the time specified in the Iowa DOT request. Failure to comply with requests for additional information may result in rejection of the Bid Response as non-compliant.

2.11 No Contract Rights until Execution

The full execution of a written contract shall constitute the making of a contract for services and no Contractor shall acquire any legal or equitable rights relative to the contract services until the contract has been fully executed by the successful Contractor and the Iowa DOT.

2.12 Restrictions on Gifts and Activities

Iowa Code Chapter 68B restricts gifts which may be given or received by state employees and requires certain individuals to disclose information concerning their activities with state government. Contractors are responsible to determine the applicability of this Chapter to their activities and to comply with the requirements. In addition, pursuant to Iowa Code section 722.1, it is a felony offense to bribe or attempt to bribe a public official.

The laws of Iowa provide that it is a felony to offer, promise, or give anything of value or benefit to a state employee with the intent to influence that employee's acts, opinion, judgment or exercise of discretion with respect to that employee's duties. Evidence of violations of this statute will be submitted to the proper prosecuting attorney.

2.13 No Minimum Guaranteed

The Iowa DOT anticipates that the selected Contractor will provide services as requested by the Iowa DOT. The Iowa DOT will not guarantee any minimum compensation will be paid to the Contractor or any minimum usage of the Contractor's services.

2.14 Conflicts Between Terms

The Iowa DOT reserves the right to accept or reject any exception taken by the Contractor to the terms and conditions contained in this RFB. Should the Contractor take exception to the terms and conditions required by the Iowa DOT, the Contractor's exceptions may be rejected and the entire proposal declared nonresponsive. The Iowa DOT may elect to negotiate with the Contractor regarding contract terms that do not materially alter the substantive requirements of the request for proposals or the contents of the Contractor's Bid Response.

2.15 Contractors Responsibilities

2.15.1 Codes, Laws and Regulations

The laws of the State of Iowa in relation to and pertaining to public improvements shall apply to these projects. All construction, materials and methods shall comply with the State and Local Building Codes and with Local Ordinances, except where plans and specifications establish a higher standard.

2.15.2 Licenses, Permits and Inspections

The Bidders shall comply with all codes, laws, ordinances, rules and regulations of any public authority having jurisdiction that bears on the performance of its work. Bidders shall pay for all licenses, permits and inspection fees required for its work. Bidders must furnish copies of all approved inspection certificates and approvals from authorities having jurisdiction in a timely fashion upon completion of the work.

2.16 Consideration of Bids

2.16.1 Rejection of Bids

- The Iowa DOT reserves the right to reject any bid if the evidence submitted by, or investigation of, such bidder fails to satisfy the Iowa DOT that such bidder is properly qualified to carry out the obligations of the Contract and to complete the work contemplated therein.
- Conditional bids will not be accepted.

2.16.2 Qualification of Bidder

The Iowa DOT may make such investigations as they deem necessary to determine the ability of the Bidder to perform the required work, and the bidder shall furnish to the Iowa DOT all such information and data for this purpose as the Iowa DOT may request.

2.17 Performance and Payment Bonds

2.17.1 Bonds

If the contracted estimated value is \$25,000 or more, the Bidder shall furnish bonds covering the faithful performance of 100% of the Contract and the payment of all obligations arising thereunder. One copy of the bond shall be submitted on Iowa Department of Transportation Form 131070. All items must be properly filled in, including Bidder's signature. Resident commission agent or attorney-in-fact must file a copy of the power of attorney.

2.17.2 Power of Attorney

Attorney-in-fact who signs the Proposal Guarantee, Performance Bond, and Labor and Material Payment Bond must file with each bond a certified and effectively dated copy of the Power of Attorney.

2.18 Labor Regulations

All Bidders, before entering into a contract with the Department, must be registered with the Division of Labor in the Iowa Department of Workforce Development (515-281-3606) according to chapter 91C, Code of Iowa 2003.

Section 3 General Requirements

3.1 Scope of Work

Successful Bidder shall be required to provide all materials, labor, and equipment necessary for the electrical upgrade for an existing brine building at Centerville according to all plans and specifications. Project includes:

- Demolition of existing electrical system
- Installation of new conduits, circuits, panels and electrical components
- Start Date: January 13, 2016 Completion Date: March 18, 2016

3.2 Adoption of General Conditions

3.2.1 The General Requirements of this Contract shall include the "General Conditions", "Plans and Specifications" and any and all requirements of this RFB, as herein stated.

3.2.2 "THE GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION", A.I.A. FORM #A-201, LATEST EDITION AND A.I.A. DOCUMENT, "INSTRUCTIONS TO BIDDERS", FORM #A-701, LATEST EDITION, SHALL BE INCLUDED, AS MODIFIED IN THE "SUPPLEMENTARY INSTRUCTIONS TO BIDDERS" AND "SUPPLEMENTARY GENERAL CONDITIONS", AND BOUND WITH THE STANDARD FORM OF AGREEMENT BETWEEN THE CONTRACTOR AND OWNER", A.I.A. FORM #101, LATEST EDITION, AS A PART OF THIS CONTRACT SPECIFICATION.

3.2.3 All bidder information and conditions, bid check lists and similar documents included in the specifications issued by the Iowa DOT, Ames, Iowa are hereby made a part of the General Conditions.

3.3 Contractor Response

3.3.1 Guidelines

- Contractors shall comply with Iowa Occupational Safety and Health Standards as found in 29 CFR Parts 1910 and 1926. Of particular importance are those standards referring to the use of personal protective equipment (PPE), fall protection and ventilation.
- Contractor may be required to make available to the Iowa DOT all Material Safety Data Sheets (MSDS) for all products provided at time the apparent low bidder has been determined. MSDS shall be sent to the Issuing Agent (when applicable) prior to issuance of the contract.

3.3.2 Guarantee

The Contractor shall guarantee all work executed under this contract, both as the workmanship and materials, for a period of twelve (12) months after the substantial completion date. Neither the final payment nor any provision of the contract documents shall relieve the Contractor of responsibility for faulty materials or workmanship. The Contractor shall remedy any defect thereto and pay for any damage to other work resulting therefrom, which shall appear within a period of one (1) year from the date of the final acceptance. With one month remaining in

the guarantee period, the Contractor shall notify the Iowa DOT and set up a complete walk-through inspection.

- All materials, items of equipment, and workmanship furnished under this division of the specifications shall carry the standard warranty against all defects in material and workmanship. Any fault due to defective or improper material, equipment, or workmanship which may develop, shall be made good, forthwith.
- The Guarantee shall include, but not be limited to the following elements and services:
 - a. Repair or replace defective materials, equipment, workmanship and installation that develops within the guarantee period, promptly and to Iowa DOT's satisfaction and correct damage caused in making necessary repairs and replacements, including all other damage done to areas, materials, and other systems resulting from the failure or defect, under guarantee by and at the expense of the Contractor.
 - b. Replace material or equipment that requires excessive service during guarantee period, as defined and as directed by the Iowa DOT.
 - c. Make all service calls, replacements, repairs and adjustments during the guarantee period without cost to the Iowa DOT.

3.3.3 Workmanship

Work shall be performed in best, most workmanlike manner by mechanics, Contractor personnel. Installation shall be made by the manufacturer or their authorized installer where specified. Unsatisfactory work shall be replaced at Contractor's expense.

3.3.4 Shop Drawings and Samples (change this section depending on the project need)

- Shop drawings, specification data, and samples shall be submitted to the Iowa DOT for approval and/or selection prior to the placing of orders for any equipment and materials.
- Shop Drawings: Submit details of materials, systems and equipment to the Iowa DOT for review. The Contractor shall provide three (**3**) copies of each shop drawing for all systems and equipment as indicated in each Division of the specifications: (Note: Submission of Shop Drawings not in binders, but in loose sheet form, may be considered cause for rejection with resubmission in proper form required).
- Product Data: Submit manufacturer's product data to the Iowa DOT for approval, consisting of complete specifications, test report data, installation instructions, and other pertinent technical data required to complete product.
 - a. Intent of Shop Drawings and Product Data review is to check for capacity, rating and certain construction features. Ensure that work meets requirements of Contract Documents regarding information that pertains to fabrication processes or means, methods, techniques, sequences and procedures of construction, and for coordination of work of this and other Sections.
 - b. Perform work in accordance with submittals marked "No Exception Taken" to extent that they agree with Contract Documents. Submittal review shall not diminish responsibility under this Contract for dimensional coordination, quantities, installation, wiring, supports, access, service and errors, nor for deviations from requirements of Contract Documents. Requirements of Contract Documents are not

- limited, waived, nor superseded by Shop Drawing Review.
- c. Submittals of various systems shall indicate equipment supplier used and that all equipment of particular system is being furnished by same supplier. Supplier shall be qualified to supervise installation, connection and testing of system and have competent maintenance service for respective systems.
 - d. Shop Drawings and samples will be reviewed with reasonable promptness and will be stamped indicating appropriate action as follows:
 - 1) **"No Exception Taken"** means that fabrication, manufacture, or construction may proceed providing submittal complies with Contract Documents.
 - 2) **"Make Corrections Noted"** means that fabrication, manufacture, or construction may proceed providing submittal complies with Engineer's notation and Contract Documents. If, for any reason, notations cannot be complied with, resubmit as described for submittals stamped **"Reject"**.
 - 3) **"Revise and Resubmit"** means submittal information is incomplete or ambiguous and therefore clarification or additional information is required to ascertain compliance with the contract documents, and that fabrication, manufacture or construction shall not proceed. Provide additional data required by the contract documents and resubmit.
 - 4) **"Reject"** means that submittal does not comply with Contract Documents and that fabrication, manufacture, or construction shall not proceed. Resubmit in accordance with requirements of Contract Documents.

3.3.5 Use of Premises

- All Contractors shall confine all apparatus, storage of materials and construction to areas as directed by the Iowa DOT and shall not encumber the premises with materials.
- Notwithstanding any approvals or instructions which must be obtained by the Contractors from the Iowa DOT in connection with use of premises, the responsibility for the safe working conditions at the site shall remain that of the Contractors.

3.3.6 Cutting and Patching

Similarly, each Contractor shall perform all necessary patching that result from cutting of holes. The Prime Contractor shall resolve any conflict between trades, and it will be the Contractor's responsibility to see all patches are made. Any and all through-wall penetration requiring structural modifications and or structural members shall be provided by the Prime Contractor.

3.3.7 Clean-Up

Throughout the period of construction, the Contractor shall clean up all work and yard areas and keep the area reasonably free of debris, etc., as required for proper protection of the work. Prior to final acceptance, the Contractor shall remove all debris, tools and equipment from the project site.

3.3.8 Inspection and Supervision

- All work shall be according to the approved design and shall be under the direct supervision of the Iowa DOT.
- Periodic site inspections will be carried on by the Iowa DOT with the Contractor to ensure coordination of the project.
- The Iowa DOT will provide a list of items requiring inspection prior to or during installation. The Contractor is to give the Iowa DOT notice no less than 24 hours in advance of installation.
- The Iowa DOT contact after the contract award shall be: Daniel Apatiga 515-239-1627 or Daniel.apatiga@dot.iowa.gov.

3.3.9 Contractors Construction Schedule

The Successful Bidder will, at the pre-construction meeting, submit a detailed construction schedule including dates of commencement and completion on each phase of the proposed construction. Upon acceptance of the schedule, the Contractor will be expected to adhere to these dates as proposed.

3.3.10 Verifying Work of Other Contractors

- When a Contractor's work depends on proper execution of work by other contractors, such Contractor shall promptly report to the Iowa DOT project lead any defects in such work and/or discrepancies between executed work plans, drawings or specifications.
- Contractors shall employ such methods and means in carrying out work as will not cause interruption or interference with any other Contractor. General Contractors shall give other Contractors sufficient notice to permit installation of sleeves, piping, conduit, and other items, prior to placing concrete or laying masonry. Any Contractor failing to comply with above shall be responsible for expense caused by such failure.

3.4 Sub-Contractors

- Specific attention shall be given by the Contractor to Article 5 of the A.I.A. Document A-201, "The General Conditions of the Contract for Construction".
- The Successful Bidder for the project shall furnish the Iowa DOT with a complete list of subcontractors, schedule of values, and major material suppliers at the pre-construction meeting.
- The Iowa DOT shall approve and maintain the list of subcontractors and major suppliers and issue a general approval of same after official award of the contract, subject to the specific requirements of the Plans, Specifications and the "General Conditions of the Contract, and of these supplementary Conditions," "Special Provisions," and elsewhere with contract documents, as applicable. Deviations from the list of subcontractors and material suppliers shall be made only with the specific approval of, or at the request of the Iowa DOT.

3.5 Protection of Persons and Property

3.5.1 Safety and Health Regulations

The Contractor, serving in the role of the employer for the project, shall exercise at all times the protection of all persons and property. Contractor shall comply with all requirements of the Occupational Safety and Health Act of 1970, Iowa Bureau of Labor and all applicable state and municipal laws, as well as building and construction codes. It is the Contractor's responsibility to enforce all regulations that apply to these projects.

3.5.2 Protection of Site

The Contractor shall furnish all permanent and temporary guards, signs, fencing, shoring, and underpinning and other protection necessary in the performance of the contract and for the necessary protection of all public and private property and shall be responsible for any damage caused by failure to comply with this requirement.

- After building operations are completed, the Contractor shall replace or satisfactorily repair all damaged walks or pavements which shall have become damaged due to operations of these projects.
- The Contractor shall take care of all underground pipes, conduits, etc., encountered in the excavations, and protect same from damage until such time as they can be permanently disposed of.
- The Contractor shall continuously maintain adequate protection of all work from damage and shall protect the Owner's property and adjacent property from damage arising in connection with this contract.

3.6 Miscellaneous Provisions

3.6.1 Iowa State Building Code

- All construction under this section shall conform to the requirements of the Iowa State Building Code. The provisions of the Iowa State Building Code will be strictly adhered to, and will take precedence over any local Governmental Body Regulations. Work not regulated by the Iowa State Building Code shall be performed in accordance with local Governmental Body Regulations.
- All construction shall conform to the Standard Specifications for Highway and Bridge Construction, Series 2012 where applicable.

3.6.2 Discriminatory Practices

- All Contractors or subcontractors working under the terms of these projects are prohibited from engaging in discriminatory employment practices as forbidden by the Iowa Civil Rights Act of 1965. These provisions shall be fully enforced, as directed through Executive Order Number 34 dated July 22, 1988. Any breach of the provisions contained in the Iowa Civil Rights Acts of 1965 shall be regarded as a material breach of contract.

- Bidder agrees that if awarded a contract to construct and/or remodel any portion of the project described in these Specifications, neither the Contractor nor any subcontractors will engage in any discriminatory employment practices based on race, color, creed, religion of natural origin and that they will in all contracts comply with all statutes of the State of Iowa against discrimination. Failure to do so could be deemed a material breach of contract.

3.7 Contractors Responsibilities

3.7.1 Pre- bid / Site Visit

- A pre- bid meeting is recommended, prospective bidders on these projects shall attend the scheduled pre- bid meeting. Prior to submitting a quotation.

Pre-bid Date: December 30, 2015 Time: 10:30 a.m. Location: Centerville Maintenance Garage Brine Building located at 23619 Hwy. 5 South, Centerville, IA 52544

Contact for Site Visit: Laura Linduski, Contractors interested in attending this recommended pre-bid meeting must register with Laura Linduski at laura.linduski@dot.iowa.gov or by phone at 515-239-1429 by December 28, 2015.

- No considerations or revision in the contract price or scope of the project will be considered by the Iowa DOT for any item which could have been revealed by a thorough on-site inspection and examination.

3.7.2 Conditions of Work

Bidders must inform themselves fully of the conditions relating to the construction of the project and the employment of labor thereon. Failure to do so will not relieve successful bidders of their obligation to furnish all material and labor necessary to carry out the provisions of this contract. Insofar as possible, the Contractor, in carrying out the work, must employ such methods or means as will not cause any interruption of, or interference with the work of any other Contractor.

3.7.3 Obligation

- At the time of the bid opening, each bidder will be presumed to have read and become thoroughly familiar with the drawings, specifications, and other contract documents, including all addenda.
- Bidders are responsible for the proper submission of bids. Omissions by a bidder to examine a form, instrument, or document shall in no way relieve that bidder from any obligations in respect to their bid.

3.8 Bid Proposal Documents

3.8.1 Plans and Specifications

- Electronic Plans and specifications are available on the Iowa DOT's website, www.iowadot.gov/purchasing. The Bidder is responsible for all copies of plans and specifications necessary for the execution of the work.
- In the event of a conflict between the specifications and the drawings, the specifications shall take precedence.

3.8.2 Materials and Equipment

- Manufacturers and products, in addition to those specifically listed, may be acceptable when it is proven to the satisfaction of the Iowa DOT that:
 - a. The level of quality proposed is equal to or better than that of the referenced manufacturer/Bidder's quality.
 - b. The technical characteristics of the proposed product meet or exceed the requirements of the drawings and specifications.
 - c. The use of the materials or equipment does not require major revisions of the drawings and specifications to permit their use.
- Any additional cost in other work incurred as a result of these approvals shall be borne by the Contractor, including all costs for modifying other related materials/systems and the cost of any additional engineering or design fees required to accommodate the substitution/approval.
- Contractors must be confident that a proposed product or material meets or exceeds the requirements shown on the drawings and specifications. It will be the responsibility of the Contractor to verify and demonstrate that a proposed product meets or exceed the drawings and specifications at time of shop drawing reviews. If a proposed product or material is determined to be technically unacceptable as judged by the Iowa DOT, the Contractor shall be required to supply products or materials that meet the requirements required to supply products or materials that meet the requirements stated in the drawings and specifications at no cost increase to the Iowa DOT. Under no circumstances will the Iowa DOT be required to prove that proposed substitutions is not equal to the project requirements. The decision of the Iowa DOT on all requested proposals/substitutions is final.

3.8.3 Alternates or Exceptions- alternates or exceptions must be evaluated prior to the letting date listed in this proposal.

Section 4 Contract Terms & Conditions

4.1 Contract Award

Award will be based on the total lump sum amount of bid price shown on the Schedule of Prices. The DOT will award to the lowest, most responsive, responsible bidder. The Iowa DOT reserves the right to accept the bid(s) which best serves the interest of the State.

Bid price will include all requirements listed in Section 3 to complete this proposed project. The Prime Contractor shall be responsible for taking all sub-bids and for all coordination between trades.

A "Prime" contract shall be awarded for each project for all work shown on the Drawings and described in the Specifications including Site work, General construction, Demolition, Plumbing, Mechanical, Energy management and control and Electrical work. The Prime Contractor shall be responsible for taking all sub-bids and for all coordination between trades.

Protests of award recommendations shall be made in accordance with Paragraph 761--20.4(6)"e", Iowa Administrative Code.

4.2 Contract Period

See Bid Proposal timeline for dates. The date of completion shall be stated in calendar days on the Bidder's Bid Response, and if necessary, adjusted by mutual agreement between the Iowa DOT and successful bidder prior to executing the contract documents.

The Iowa DOT realizes that deliveries and site conditions have a definite bearing on the completion date. The Iowa DOT will demand diligence in the prosecution of the work, but with good cause and satisfactory past performance by the Contractor, the Iowa DOT may revise the completion date to another mutually-acceptable date, when requested in writing and in good faith by the Contractor.

4.3 Liquidated Damages

Time is an essential component of the contract, and it is important that the work be to completed on the or before the dates listed on the Procurement Timetable. For each calendar day that any work shall remain uncompleted beyond the substantial completion date and beyond the final completion date or any extension granted under Extension of Contract Period, the amount per calendar day specified in the Bid Response cover page will be assessed, not as a penalty but as predetermined and agreed upon liquidated damages. If work remains uncompleted on more than one portion for which calendar days and liquidated damages have been specified, the liquidated damages assessed will be the total of the damages per day listed for each uncompleted portion. The Iowa DOT shall prepare and forward to the Contractor an invoice or credit change order for such liquidated damages. The final payment shall be withheld until payment of the invoice has been made or the credit change order has been agreed upon.

Assessment of liquidated damages will be based only on the number of calendar days required to complete the contract beyond the contract completion date, plus authorized extensions.

The provision for the assessment of liquidated damages for failure to complete work within the contract period does not constitute a waiver of the Iowa DOT's right to collect any additional damages other than time delays, which the Iowa DOT may sustain by the failure of the Contractor to carry out the terms of the contract.

4.4 Immunity of Iowa Department of Transportation

The Contractor shall defend, indemnify and hold harmless the Iowa DOT and its officials and employees from liability arising out of or resulting from the Contractor's activities at the designated work site, its performance or attempted performance of the contract, as well as the Contractor's activities with Sub-Contractors and all other third parties.

4.5 Payments and Completion of Contract

4.5.1 Payments on contract will be made monthly by means of state warrants to the extent of ninety-seven percent (97%) of the value of work performed, including acceptable material stored at the building site, as determined by the Contractor as governed by the Iowa DOT Standard Specifications for Highway and Bridges Construction, Series 2012 and General Supplemental Specifications.

4.5.2 At the Pre-Bid Conference, the contractor shall submit a schedule of values of the various parts of the work, aggregating the total sum of the contract, made out in such form as the Iowa DOT may direct and, if required, supported by evidence as to its correctness. This schedule, when approved by the Iowa DOT, shall be used as a basis for requests for payment.

4.5.3 Final payment shall be authorized not later than thirty (60) days following the completion and final acceptance of the contract, provided that the provisions herein and all other contract requirements have been fulfilled, accepted and approved, where no claims have been filed or following adjudication or release of claims as provided in Chapter 573 of the Code of Iowa.

4.5.4 No notification of payment being processed, no payment made to the Contractor, no partial payment, nor the entire use or occupancy of the work by the Iowa DOT shall be held to constitute an acceptance, in whole or in part, by the Iowa DOT prior to making the final payment and acceptance in full completion of the contract.

4.6 Insurance Requirements

Contractor's Insurance

- It shall be the Contractor's responsibility to have liability insurance covering all of the project operations incident to contract completion and the Contractor(s) must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor(s) including a subcontractor, persons employed by a subcontractor(s), or by an independent contractor(s).
- In addition to the above, the Iowa DOT shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Iowa DOT as an insured party.

- The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows:
 - Commercial General Liability including Contractual Liability;
 - Contingent Liability; Explosion, Collapse and Underground Drainage
 - Damage; Occurrence Basis Bodily Injury; Broad Form Personal Injury; Broad Form Property Damage.

Bodily Injury

The contractor will purchase and maintain throughout the term of this contract the follow minimum limits and coverage:

- Each person \$750,000
- Each accident/occurrence \$750,000
- Workers Compensation \$750,000
- Statutory Limits \$750,000
- Employer's liability \$750,000
- Occupation Disease \$750,000

Operations

- Property Damage \$250,000 each occurrence

Builders Risk Insurance

- Each Contractor holding a valid contract with the Iowa DOT shall furnish and pay for builder's risk insurance, providing coverage for at least the following losses: fire, extended coverage, vandalism and malicious damage to materials incorporated in the project, and materials purchased to be incorporated in the project, either stored on or off the permanent job site. If this insurance coverage is not provided, the Contractor shall assume all responsibility for the perils outlined above which may occur prior to project completion and acceptance.
- Failure on the part of the Contractor(s) to comply with the requirements of this Article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor(s) any further contract awards, as provided in Article 1103.01.
- The Contractor(s) shall require all subcontractor(s) meet the above insurance requirements.

The Certificate of Insurance must include the following

- Iowa Department of Transportation must be listed as an additional insured
- Proposal Number
- Proposal Description
- Letting Date
- Contract Period

4.7 Public Contract Termination

The provisions of Iowa law as contained in Chapter 573A of the Code of Iowa, an Act to provide for termination of contracts for the construction of public improvements when construction or work thereon is stopped because of national emergency, shall apply to and be a part of this Contract, and shall be binding upon all parties hereto, including sub-contractors and sureties upon any bond given or filed in connection herewith.

**SECTION 00 0101
PROJECT TITLE PAGE**

**PROJECT MANUAL
FOR
CENTERVILLE BRINE BUILDING ELECTRICAL**

**IOWA DEPARTMENT OF TRANSPORTATION
23619 IOWA S
CENTERVILLE, IOWA 52544
PROJECT NUMBER: BG-4C26(001)--80-04**

DATE: 19 NOVEMBER 2015

**SECTION 00 0110
TABLE OF CONTENTS**

PROCUREMENT AND CONTRACTING REQUIREMENTS

1.01 DIVISION 00 -- PROCUREMENT AND CONTRACTING REQUIREMENTS

- A. 00 0101 - Project Title Page
- B. 00 0110 - Table of Contents

SPECIFICATIONS

2.01 DIVISION 01 -- GENERAL REQUIREMENTS

- A. 01 1000 - Summary
- B. 01 2000 - Price and Payment Procedures
- C. 01 3000 - Administrative Requirements
- D. 01 4000 - Quality Requirements
- E. 01 5000 - Temporary Facilities and Controls
- F. 01 5713 - Temporary Erosion and Sediment Control
- G. 01 6000 - Product Requirements
- H. 01 7000 - Execution and Closeout Requirements
- I. 01 7800 - Closeout Submittals

2.02 DIVISION 02 -- EXISTING CONDITIONS (NOT USED)

2.03 DIVISION 03 -- CONCRETE (NOT USED)

2.04 DIVISION 04 -- MASONRY (NOT USED)

2.05 DIVISION 05 -- METALS (NOT USED)

2.06 DIVISION 06 -- WOOD, PLASTICS, AND COMPOSITES (NOT USED)

2.07 DIVISION 07 -- THERMAL AND MOISTURE PROTECTION

- A. 07 9005 - Joint Sealers

2.08 DIVISION 08 -- OPENINGS (NOT USED)

2.09 DIVISION 09 -- FINISHES (NOT USED)

2.10 DIVISION 10 -- SPECIALTIES (NOT USED)

2.11 DIVISION 11 -- EQUIPMENT (NOT USED)

2.12 DIVISION 12 -- FURNISHINGS (NOT USED)

2.13 DIVISION 13 -- SPECIAL CONSTRUCTION (NOT USED)

2.14 DIVISION 14 -- CONVEYING EQUIPMENT (NOT USED)

2.15 DIVISION 21 -- FIRE SUPPRESSION (NOT USED)

2.16 DIVISION 22 -- PLUMBING (NOT USED)

2.17 DIVISION 23 -- HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC) (NOT USED)

2.18 DIVISION 26 -- ELECTRICAL

- A. 26 0501 - Minor Electrical Demolition
- B. 26 0526 - Grounding and Bonding for Electrical Systems
- C. 26 0534 - Conduit
- D. 26 0537 - Boxes
- E. 26 0553 - Identification for Electrical Systems
- F. 26 2416 - Panelboards

G. 26 2717 - Equipment Wiring

H. 26 2726 - Wiring Devices

I. 26 5100 - Interior Lighting

J. 26 5600 - Exterior Lighting

2.19 DIVISION 27 -- COMMUNICATIONS (NOT USED)

2.20 DIVISION 28 -- ELECTRONIC SAFETY AND SECURITY (NOT USED)

2.21 DIVISION 31 -- EARTHWORK

A. 31 2316.13 - Trenching

2.22 DIVISION 32 -- EXTERIOR IMPROVEMENTS (NOT USED)

2.23 DIVISION 33 -- UTILITIES (NOT USED)

END OF SECTION

SECTION 01 1000
SUMMARY

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Contract description.
- B. Owner supplied products.
- C. Contractor's use of site and premises.
- D. Owner occupancy.
- E. Specification Conventions.

1.02 PROJECT

- A. Project Name: Centerville Brine Building Electrical
- B. Owner's Name: Iowa Department of Transportation.
- C. The Project consists of the construction of Electrical service, equipment, and lighting. Demolition of existing electrical when new electrical is completed, tested, and approved..

1.03 CONTRACT DESCRIPTION

- A. Contract Type: Stipulated Price as described in Purchase Order.

1.04 OWNER SUPPLIED PRODUCTS

- A. Owner's Responsibilities:
 - 1. Arrange for and deliver Owner-reviewed Shop Drawings, Product Data, and Samples, to Contractor.
 - 2. Arrange and pay for delivery to site.
 - 3. On delivery, inspect products jointly with Contractor.
 - 4. Submit claims for transportation damage and replace damaged, defective, or deficient items.
 - 5. Arrange for manufacturers' warranties, inspections, and service.
- B. Contractor's Responsibilities:
 - 1. Review Owner-reviewed Shop Drawings, Product Data, and Samples.
 - 2. Receive and unload products at site; inspect for completeness or damage jointly with Owner.
 - 3. Handle, store, install and finish products.
 - 4. Repair or replace items damaged after receipt.
- C. Products furnished to site and installed by Owner:
 - 1. Brine maker
 - 2. Brine pumps, tanks, and brine piping

1.05 OWNER OCCUPANCY

- A. Construction, including punch list items, must be completed no later than the following date: as indicated on Bid Response Document.
 - 1. Extension requests must be in writing and must be accompanied by appropriate documentation supporting the reason for the extension request.
 - 2. No extensions or additional payments will be allowed for cold weather construction.
- B. Cooperate with Owner to minimize conflict and to facilitate Owner's operations.
- C. Schedule the Work to accommodate Owner occupancy.

1.06 CONTRACTOR USE OF SITE AND PREMISES

- A. Arrange use of site and premises to allow:
 - 1. Owner occupancy.
 - 2. Work by Others.
- B. Provide access to and from site as required by law and by Owner:

1. Emergency Building Exits During Construction: Keep all exits required by code open during construction period; provide temporary exit signs if exit routes are temporarily altered.
2. Do not obstruct roadways, sidewalks, or other public ways without permit.

1.07 SPECIFICATION CONVENTIONS

- A. These specifications are written in imperative mood and streamlined form. This imperative language is directed to the Contractor, unless specifically noted otherwise. The words "shall be" are included by inference where a colon (:) is used within sentences or phrases.
- B. The following terms are used throughout the specifications and defined as follows:
 1. Contractor: General Contractor or contractor responsible for Work of specified section
 2. Owner: Representative of building occupants.
 3. Architect/Engineer: Representative of Facilities Support.
 4. Iowa DOT: Standard Specifications for Highway and Bridge Construction - Series 2012: Iowa DOT SSHBC - Series 2012.

1.08 SPECIFICATION SECTIONS APPLICABLE TO ALL CONTRACTS

- A. Unless otherwise noted, all provisions of the sections listed below apply to all contracts. Specific items of work listed under individual contract descriptions constitute exceptions.
- B. Section 01 2000 - Price and Payment Procedures.
- C. Section 01 3000 - Administrative Requirements.
- D. Section 01 3216 - Construction Progress Schedule.
- E. Section 01 4000 - Quality Requirements.
- F. Section 01 5000 - Temporary Facilities and Controls.
- G. Section 01 5713 - Temporary Erosion and Sediment Control.
- H. Section 01 6000 - Product Requirements.
- I. Section 01 7000 - Execution and Closeout Requirements.
- J. Section 01 7419 - Construction Waste Management and Disposal.
- K. Section 01 7800 - Closeout Submittals.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 01 2000
PRICE AND PAYMENT PROCEDURES

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Documentation of changes in Contract Price and Contract Time.
- B. Change procedures.
- C. Correlation of Contractor submittals based on changes.
- D. Procedures for preparation and submittal of application for final payment.

1.02 RELATED REQUIREMENTS**1.03 SCHEDULE OF VALUES**

- A. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit draft to Architect for approval.
- B. Forms filled out by hand will not be accepted.
- C. Submit Schedule of Values in duplicate within 15 days after date of Owner-Contractor Agreement.
- D. Format: Utilize the Table of Contents of this Project Manual. Identify each line item with number and title of the specification Section. Identify site mobilization, bonds and insurance, and General Requirements as separate line items for each structure.
- E. Include separately from each line item, a direct proportional amount of Contractor's overhead and profit.
- F. Revise schedule to list approved Change Orders, with each Application For Payment.

1.04 APPLICATIONS FOR PROGRESS PAYMENTS

- A. Payment Period: Lump Sum Payment at end of Project.
- B. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit sample to Architect for approval.
- C. Forms filled out by hand will not be accepted.
- D. For each item, provide a column for listing each of the following:
 - 1. Item Number.
 - 2. Description of work.
 - 3. Scheduled Values.
 - 4. Previous Applications.
 - 5. Work in Place and Stored Materials under this Application.
 - 6. Authorized Change Orders.
 - 7. Total Completed and Stored to Date of Application.
 - 8. Percentage of Completion.
 - 9. Balance to Finish.
 - 10. Retainage.
- E. Execute certification by signature of authorized officer.
- F. Use data from approved Schedule of Values. Provide dollar value in each column for each line item for portion of work performed and for stored products.
- G. Include the following with the application:
- H. When Architect requires substantiating information, submit data justifying dollar amounts in question. Provide one copy of data with cover letter for each copy of submittal. Show application number and date, and line item by number and description.

1.05 MODIFICATION PROCEDURES

- A. For minor changes not involving an adjustment to the Contract Price or Contract Time, Architect will issue instructions directly to Contractor.
- B. Contractor may propose a change by submitting a request for change to Architect, describing the proposed change and its full effect on the Work, with a statement describing the reason for the change, and the effect on the Contract Price and Contract Time with full documentation and a statement describing the effect on Work by separate or other contractors. Document any requested substitutions in accordance with Section 01 6000.
- C. Computation of Change in Contract Amount: As specified in the Agreement and Conditions of the Contract.
 - 1. For change requested by Architect for work falling under a fixed price contract, the amount will be based on Contractor's price quotation.
 - 2. For change requested by Contractor, the amount will be based on the Contractor's request for a Change Order as approved by Architect.
 - 3. For change ordered by Architect without a quotation from Contractor, the amount will be determined by Architect based on the Contractor's substantiation of costs as specified for Time and Material work.
- D. Substantiation of Costs: Provide full information required for evaluation.
 - 1. On request, provide the following data:
 - a. Quantities of products, labor, and equipment.
 - b. Overhead and profit.
 - 1) Profit and overhead not to exceed 15 percent total between General Contractor and Sub Contractor.
 - c. Justification for any change in Contract Time.
- E. Execution of Change Orders: Architect will issue Change Orders for signatures of parties as provided in the Conditions of the Contract.
- F. After execution of Change Order, promptly revise Schedule of Values and Application for Payment forms to record each authorized Change Order as a separate line item and adjust the Contract Price.
- G. Promptly revise progress schedules to reflect any change in Contract Time, revise sub-schedules to adjust times for other items of work affected by the change, and resubmit.

1.06 APPLICATION FOR FINAL PAYMENT

- A. Prepare Application for Final Payment as specified for progress payments, identifying total adjusted Contract Price, previous payments, and sum remaining due.
- B. Application for Final Payment will not be considered until the following have been accomplished:
 - 1. All closeout procedures specified in Section 01 7000.
 - 2. All punch list items have been completed.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 01 3000
ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Preconstruction meeting.
- B. Construction progress schedule.
- C. Coordination drawings.
- D. Submittals for review and for information.
- E. Number of copies of submittals.
- F. Submittal procedures.

1.02 RELATED REQUIREMENTS

- A. Section 01 7000 - Execution and Closeout Requirements: Additional coordination requirements.
- B. Section 01 7800 - Closeout Submittals: Project record documents, construction progress schedules, closeout submittals.

1.03 COORDINATION AND PROJECT CONDITIONS

- A. Coordinate scheduling, submittals, and Work of various sections of Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements, with provisions for accommodating items installed later.
- B. Verify utility requirements and characteristics of operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent responsibilities for installing, connecting to, and placing in service, operating equipment.
- C. Coordinate space requirements, supports, and installation of mechanical and electrical Work indicated diagrammatically on Drawings. Follow routing shown for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
- D. In finished areas except as otherwise indicated, conceal pipes, ducts, and wiring within construction. Coordinate locations of fixtures and outlets with finish elements.
- E. Coordinate completion and clean up of Work of separate sections in preparation for Substantial Completion.
- F. After Owner occupancy of premises, coordinate access to site for correction of defective Work and Work not in accordance with Contract Documents, to minimize disruption of Owner's activities.

1.04 PROJECT COORDINATION

- A. Project Coordinator: Project Manager.
- B. Cooperate with the Project Coordinator in allocation of mobilization areas of site; for field offices and sheds, for vehicular access, traffic, and parking facilities.
- C. During construction, coordinate use of site and facilities through the Project Coordinator.
- D. Comply with Project Coordinator's procedures for intra-project communications; submittals, reports and records, schedules, coordination drawings, and recommendations; and resolution of ambiguities and conflicts.
- E. Comply with instructions of the Project Coordinator for use of temporary utilities and construction facilities.
- F. Coordinate field engineering and layout work under instructions of the Project Coordinator.
- G. Make the following types of submittals to Architect through the Project Coordinator:
 - 1. Requests for interpretation.
 - 2. Requests for substitution.

3. Shop drawings, product data, and samples.
4. Test and inspection reports.
5. Design data.
6. Manufacturer's instructions and field reports.
7. Applications for payment and change order requests.
8. Progress schedules.
9. Coordination drawings.
10. Correction Punch List and Final Correction Punch List for Substantial Completion.
11. Closeout submittals.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PRECONSTRUCTION MEETING

- A. Owner will schedule a meeting after Notice of Award.
- B. Project Coordinator will schedule a meeting after Notice of Award.
- C. Attendance Required:
 1. Owner.
 2. Architect/Engineer.
 3. Contractor.
 4. All major Sub-Contractors.
- D. Agenda:
 1. Review Owner-Contractor Agreement and contract conditions.
 2. Submission of executed bonds and insurance certificates.
 3. Distribution of Contract Documents.
 4. Review list of Subcontractors, list of Products, schedule of values, and progress schedule.
 5. Designation of personnel representing the parties to Contract, Owner and Architect.
 6. Designation of personnel representing the parties to Contract, Owner and Architect/Engineer.
 7. Review procedures and processing of field decisions, submittals, substitutions, applications for payments, proposal request, Change Orders, and Contract closeout procedures.
 8. Coordinate commencement of construction.
 9. Use of premises by Owner and Contractor.
 10. Construction facilities and controls provided by Owner.
 11. Temporary utilities provided by Contractor.
 12. Security and housekeeping procedures.
 13. Procedures for testing.
 14. Procedures for maintaining record documents.
 15. Requirements for start-up of equipment.
 16. Inspection and acceptance of equipment put into service during construction period.
 17. Scheduling.
- E. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.

3.02 CONSTRUCTION PROGRESS SCHEDULE

- A. If preliminary schedule requires revision after review, submit revised schedule within 10 days.
- B. Within 20 days after review of preliminary schedule, submit draft of proposed complete schedule for review.
 1. Include written certification that major contractors have reviewed and accepted proposed schedule.
- C. Within 10 days after joint review, submit complete schedule.
- D. Submit updated schedule with each Application for Payment.

3.03 CUTTING AND PATCHING

- A. Employ skilled and experienced installer to perform cutting and patching.
- B. Submit written request in advance of cutting or altering elements affecting:
 - 1. Structural integrity of element.
 - 2. Integrity of weather-exposed or moisture-resistant elements.
 - 3. Efficiency, maintenance, or safety of element.
 - 4. Visual qualities of sight exposed elements.
 - 5. Work of Owner or separate contractor.
- C. Execute cutting, fitting, and patching including excavation and fill, to complete Work, and to:
 - 1. Fit the several parts together, to integrate with other Work.
 - 2. Uncover Work to install or correct ill-timed Work.
 - 3. Remove and replace defective and non-conforming Work.
 - 4. Remove samples of installed Work for testing.
 - 5. Provide openings in elements of Work for penetrations of mechanical and electrical Work.
- D. Execute work by methods to avoid damage to other Work, and to provide proper surfaces to receive patching and finishing.
- E. Cut masonry and concrete materials using masonry saw or core drill.
- F. Restore Work with new products in accordance with requirements of Contract Documents.
- G. Fit Work tight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- H. Maintain integrity of wall, ceiling, or floor construction; completely seal voids.
- I. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material in accordance with Section 07840, to full thickness of penetrated element.
- J. Refinish surfaces to match adjacent finishes. For continuous surfaces, refinish to nearest intersection; for assembly, refinish entire unit.
- K. Identify hazardous substances or conditions exposed during the Work to Architect/Engineer for decision or remedy.

3.04 COORDINATION DRAWINGS

- A. Provide information required by Project Coordinator for preparation of coordination drawings.
- B. Review drawings prior to submission to Architect.

3.05 SUBMITTALS FOR REVIEW

- A. When the following are specified in individual sections, submit them for review:
 - 1. Product data.
 - 2. Shop drawings.
 - 3. Samples for selection.
 - 4. Samples for verification.
- B. Submit to Architect for review for the limited purpose of checking for conformance with information given and the design concept expressed in the contract documents.
- C. Samples will be reviewed only for aesthetic, color, or finish selection.
- D. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article below and for record documents purposes described in Section 01 7800 - Closeout Submittals.

3.06 SUBMITTALS FOR INFORMATION

- A. When the following are specified in individual sections, submit them for information:
 - 1. Design data.
 - 2. Certificates.
 - 3. Test reports.
 - 4. Inspection reports.

5. Manufacturer's instructions.
 6. Manufacturer's field reports.
 7. Other types indicated.
- B. Submit for Architect's knowledge as contract administrator or for Owner. No action will be taken.

3.07 NUMBER OF COPIES OF SUBMITTALS

- A. Electronic Documents: Submit one electronic copy in PDF format; an electronically-marked up file will be returned. Create PDFs at native size and right-side up; illegible files will be rejected.
- B. Documents for Information: Submit one copy electronically.
- C. Samples: Submit the number specified in individual specification sections; one of which will be retained by Architect.
 1. After review, produce duplicates.
 2. Retained samples will not be returned to Contractor unless specifically so stated.

3.08 SUBMITTAL PROCEDURES

- A. Shop Drawing Procedures:
 1. Prepare accurate, drawn-to-scale, original shop drawing documentation by interpreting the Contract Documents and coordinating related Work.
 2. Generic, non-project specific information submitted as shop drawings do not meet the requirements for shop drawings.
- B. Transmit each submittal with a copy of approved submittal form.
- C. Transmit each submittal with approved form.
- D. Sequentially number the transmittal form. Revise submittals with original number and a sequential alphabetic suffix.
- E. Identify Project, Contractor, Subcontractor or supplier; pertinent drawing and detail number, and specification section number, as appropriate on each copy.
- F. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of Products required, field dimensions, adjacent construction Work, and coordination of information is in accordance with the requirements of the Work and Contract Documents.
- G. Deliver submittals to Owner in electronic format only.
 1. Only physical samples to be submitted to Owner's address.
- H. Schedule submittals to expedite the Project, and coordinate submission of related items.
- I. For each submittal for review, allow 15 days excluding delivery time to and from the Contractor.
- J. Identify variations from Contract Documents and Product or system limitations that may be detrimental to successful performance of the completed Work.
- K. Provide space for Contractor and Architect review stamps.
- L. When revised for resubmission, identify all changes made since previous submission.
- M. Distribute reviewed submittals as appropriate. Instruct parties to promptly report any inability to comply with requirements.
- N. Submittals not requested will not be recognized or processed.

END OF SECTION

SECTION 01 4000
QUALITY REQUIREMENTS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. References and standards.
- B. Control of installation.
- C. Tolerances.
- D. Inspection services.

1.02 RELATED REQUIREMENTS

- A. Section 01 3000 - Administrative Requirements: Submittal procedures.
- B. Section 01 6000 - Product Requirements: Requirements for material and product quality.

1.03 SUBMITTALS

- A. Design Data: Submit for Architect's knowledge as contract administrator for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents, or for Owner's information.
- B. Test Reports: After each test/inspection, promptly submit two copies of report to Architect and to Contractor.
 - 1. Include:
 - a. Date issued.
 - b. Project title and number.
 - c. Name of inspector.
 - d. Date and time of sampling or inspection.
 - e. Identification of product and specifications section.
 - f. Location in the Project.
 - g. Type of test/inspection.
 - h. Date of test/inspection.
 - i. Results of test/inspection.
 - j. Conformance with Contract Documents.
 - k. When requested by Architect, provide interpretation of results.
 - 2. Test report submittals are for Architect's knowledge as contract administrator for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents, or for Owner's information.
- C. Certificates: When specified in individual specification sections, submit certification by the manufacturer and Contractor or installation/application subcontractor to Architect, in quantities specified for Product Data.
 - 1. Indicate that material or product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
 - 2. Certificates may be recent or previous test results on material or product, but must be acceptable to Architect.
- D. Manufacturer's Instructions: When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, for the Owner's information. Indicate special procedures, perimeter conditions requiring special attention, and special environmental criteria required for application or installation.
- E. Manufacturer's Field Reports: Submit reports for Architect's benefit as contract administrator or for Owner.
 - 1. Submit report in duplicate within 30 days of observation to Architect for information.
 - 2. Submit for information for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents.

- F. Erection Drawings: Submit drawings for Architect's benefit as contract administrator or for Owner.
 - 1. Submit for information for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents.
 - 2. Data indicating inappropriate or unacceptable Work may be subject to action by Architect or Owner.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce Work of specified quality.
- B. Comply with manufacturers' instructions, including each step in sequence.
- C. Should manufacturers' instructions conflict with Contract Documents, request clarification from Architect before proceeding.
- D. Comply with specified standards as minimum quality for the Work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Have Work performed by persons qualified to produce required and specified quality.
- F. Verify that field measurements are as indicated on shop drawings or as instructed by the manufacturer.
- G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, and disfigurement.

3.02 TOLERANCES

- A. Monitor fabrication and installation tolerance control of products to produce acceptable Work. Do not permit tolerances to accumulate.
- B. Comply with manufacturers' tolerances. Should manufacturers' tolerances conflict with Contract Documents, request clarification from Architect before proceeding.
- C. Adjust products to appropriate dimensions; position before securing products in place.

3.03 TESTING AND INSPECTION

- A. Contractor to Notify the following agencies for required inspections of work to be outlined in the Scope of Work and the Pre-Construction Meeting and provide reports, certifications, and permits as applicable:
 - 1. State Fire Marshall Division, Electrical Examining Board, 215 E. 7th Street, Des Moines, Iowa 50319 Phone: 515-281-6533 Fax: 515-210-7294
 - a. Contractor is responsible for obtaining electrical permit
 - b. Coordinate with local Electrical Service Provider for extending or replacing service to building
 - c. Electrical Rough-in Inspection
 - d. Electrical Service Inspection
 - e. Final Electrical Inspection
- B. Re-testing required because of non-conformance to specified requirements shall be paid for by Contractor.

3.04 DEFECT ASSESSMENT

- A. Replace Work or portions of the Work not conforming to specified requirements.
- B. If, in the opinion of Architect, it is not practical to remove and replace the Work, Architect will direct an appropriate remedy or adjust payment.

END OF SECTION

SECTION 01 5000
TEMPORARY FACILITIES AND CONTROLS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Temporary sanitary facilities.
- B. Temporary Controls: Barriers and enclosures.
- C. Vehicular access and parking.

1.02 RELATED REQUIREMENTS

- A. Section 01 5500 - Vehicular Access and Parking.

1.03 TEMPORARY UTILITIES

- A. Owner will provide the following:
 - 1. Electrical power and metering, consisting of connection to existing facilities.
 - 2. Water supply, consisting of connection to existing facilities.

1.04 TEMPORARY SANITARY FACILITIES

- A. Provide and maintain required facilities and enclosures. Provide at time of project mobilization.
- B. Maintain daily in clean and sanitary condition.

1.05 BARRIERS

- A. Provide barriers to prevent unauthorized entry to construction areas, to prevent access to areas that could be hazardous to workers or the public, to allow for owner's use of site and to protect existing facilities and adjacent properties from damage from construction operations and demolition.
- B. Provide barricades and covered walkways required by governing authorities for public rights-of-way and for public access to existing building.
- C. Protect non-owned vehicular traffic, stored materials, site, and structures from damage.

1.06 VEHICULAR ACCESS AND PARKING - SEE SECTION 01 5500

- A. Coordinate access and haul routes with governing authorities and Owner.
- B. Provide and maintain access to fire hydrants, free of obstructions.
- C. Provide means of removing mud from vehicle wheels before entering streets.
- D. Provide temporary parking areas to accommodate construction personnel. When site space is not adequate, provide additional off-site parking.

1.07 WASTE REMOVAL

- A. Provide waste removal facilities and services as required to maintain the site in clean and orderly condition.
- B. Provide containers with lids. Remove trash from site periodically.
- C. If materials to be recycled or re-used on the project must be stored on-site, provide suitable non-combustible containers; locate containers holding flammable material outside the structure unless otherwise approved by the authorities having jurisdiction.
- D. Open free-fall chutes are not permitted. Terminate closed chutes into appropriate containers with lids.

1.08 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

- A. Remove temporary utilities, equipment, facilities, materials, prior to Substantial Completion inspection.
- B. Remove underground installations to a minimum depth of 2 feet. Grade site as indicated.
- C. Clean and repair damage caused by installation or use of temporary work.

PART 2 PRODUCTS - NOT USED
PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 01 5713
TEMPORARY EROSION AND SEDIMENT CONTROL

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Prevention of erosion due to construction activities.
- B. Prevention of sedimentation of waterways, open drainage ways, and storm and sanitary sewers due to construction activities.
- C. Restoration of areas eroded due to insufficient preventive measures.
- D. Compensation of Owner for fines levied by authorities having jurisdiction due to non-compliance by Contractor.

1.02 REFERENCE STANDARDS

- A. ASTM D4355 - Standard Test Method for Deterioration of Geotextiles by Exposure to Light, Moisture, and Heat in a Xenon Arc Type Apparatus; 2007.
- B. ASTM D4491 - Standard Test Methods for Water Permeability of Geotextiles by Permittivity; 1999a (Reapproved 2014).
- C. ASTM D4533 - Standard Test Method for Trapezoid Tearing Strength of Geotextiles; 2011.
- D. ASTM D4632 - Standard Test Method for Grab Breaking Load and Elongation of Geotextiles; 2008.
- E. ASTM D4751 - Standard Test Method for Determining Apparent Opening Size of a Geotextile; 2012.
- F. ASTM D4873 - Standard Guide for Identification, Storage, and Handling of Geosynthetic Rolls and Samples; 2002 (Reapproved 2009).
- G. FHWA FLP-94-005 - Best Management Practices for Erosion and Sediment Control; Federal Highway Administration; 1995.

1.03 PERFORMANCE REQUIREMENTS

- A. Develop and follow an Erosion and Sedimentation Prevention Plan and submit periodic inspection reports.
- B. Do not begin clearing, grading, or other work involving disturbance of ground surface cover until applicable permits have been obtained; furnish all documentation required to obtain applicable permits.
- C. Timing: Put preventive measures in place as soon as possible after disturbance of surface cover and before precipitation occurs.
- D. Storm Water Runoff: Control increased storm water runoff due to disturbance of surface cover due to construction activities for this project.
 - 1. Prevent runoff into storm and sanitary sewer systems, including open drainage channels, in excess of actual capacity or amount allowed by authorities having jurisdiction, whichever is less.
 - 2. Anticipate runoff volume due to the most extreme short term and 24-hour rainfall events that might occur in 25 years.
- E. Erosion On Site: Minimize wind, water, and vehicular erosion of soil on project site due to construction activities for this project.
 - 1. Control movement of sediment and soil from temporary stockpiles of soil.
 - 2. Prevent development of ruts due to equipment and vehicular traffic.
 - 3. If erosion occurs due to non-compliance with these requirements, restore eroded areas at no cost to Owner.
- F. Erosion Off Site: Prevent erosion of soil and deposition of sediment on other properties caused by water leaving the project site due to construction activities for this project.
 - 1. Prevent windblown soil from leaving the project site.

2. Prevent tracking of mud onto public roads outside site.
 3. Prevent mud and sediment from flowing onto sidewalks and pavements.
 4. If erosion occurs due to non-compliance with these requirements, restore eroded areas at no cost to Owner.
- G. Sedimentation of Waterways On Site: Prevent sedimentation of waterways on the project site, including rivers, streams, lakes, ponds, open drainage ways, storm sewers, and sanitary sewers.
1. If sedimentation occurs, install or correct preventive measures immediately at no cost to Owner; remove deposited sediments; comply with requirements of authorities having jurisdiction.
 2. If sediment basins are used as temporary preventive measures, pump dry and remove deposited sediment after each storm.
- H. Sedimentation of Waterways Off Site: Prevent sedimentation of waterways off the project site, including rivers, streams, lakes, ponds, open drainage ways, storm sewers, and sanitary sewers.
1. If sedimentation occurs, install or correct preventive measures immediately at no cost to Owner; remove deposited sediments; comply with requirements of authorities having jurisdiction.
- I. Open Water: Prevent standing water that could become stagnant.
- J. Maintenance: Maintain temporary preventive measures until permanent measures have been established.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Erosion and Sedimentation Control Plan:
1. Include:
 - a. Site plan identifying soils and vegetation, existing erosion problems, and areas vulnerable to erosion due to topography, soils, vegetation, or drainage.
 - b. Site plan showing grading; new improvements; temporary roads, traffic accesses, and other temporary construction; and proposed preventive measures.
 - c. Where extensive areas of soil will be disturbed, include storm water flow and volume calculations, soil loss predictions, and proposed preventive measures.
 - d. Schedule of temporary preventive measures, in relation to ground disturbing activities.
 - e. Other information required by law.
 - f. Format required by law is acceptable, provided any additional information specified is also included.
 2. Obtain the approval of the Plan by authorities having jurisdiction.
 3. Obtain the approval of the Plan by Owner.
- C. Certificate: Mill certificate for silt fence fabric attesting that fabric and factory seams comply with specified requirements, signed by legally authorized official of manufacturer; indicate actual minimum average roll values; identify fabric by roll identification numbers.
- D. Inspection Reports: Submit report of each inspection; identify each preventive measure, indicate condition, and specify maintenance or repair required and accomplished.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Mulch: Use one of the following:
1. Straw or hay.
- B. Grass Seed For Temporary Cover: Select a species appropriate to climate, planting season, and intended purpose. If same area will later be planted with permanent vegetation, do not use species known to be excessively competitive or prone to volunteer in subsequent seasons.

- C. Silt Fence Fabric: Polypropylene geotextile resistant to common soil chemicals, mildew, and insects; non-biodegradable; in longest lengths possible; fabric including seams with the following minimum average roll lengths:
 - 1. Average Opening Size: 30 U.S. Std. Sieve, maximum, when tested in accordance with ASTM D4751.
 - 2. Permittivity: 0.05 sec^{-1} , minimum, when tested in accordance with ASTM D4491.
 - 3. Ultraviolet Resistance: Retaining at least 70 percent of tensile strength, when tested in accordance with ASTM D4355 after 500 hours exposure.
 - 4. Tensile Strength: 100 lb-f, minimum, in cross-machine direction; 124 lb-f, minimum, in machine direction; when tested in accordance with ASTM D4632.
 - 5. Elongation: 15 to 30 percent, when tested in accordance with ASTM D4632.
 - 6. Tear Strength: 55 lb-f, minimum, when tested in accordance with ASTM D4533.
 - 7. Color: Manufacturer's standard, with embedment and fastener lines preprinted.
- D. Silt Fence Posts: One of the following, minimum 5 feet long:
 - 1. Steel U- or T-section, with minimum mass of 1.33 lb per linear foot.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine site and identify existing features that contribute to erosion resistance; maintain such existing features to greatest extent possible.

3.02 PREPARATION

- A. Schedule work so that soil surfaces are left exposed for the minimum amount of time.

3.03 SCOPE OF PREVENTIVE MEASURES

- A. In all cases, if permanent erosion resistant measures have been installed temporary preventive measures are not required.
- B. Linear Sediment Barriers: Made of silt fences.
 - 1. Provide linear sediment barriers:
 - a. Along downhill perimeter edge of disturbed areas, including soil stockpiles.
 - 2. Space sediment barriers with the following maximum slope length upslope from barrier:
 - a. Slope of Less Than 2 Percent: 100 feet..
 - b. Slope Between 2 and 5 Percent: 75 feet.
 - c. Slope Between 5 and 10 Percent: 50 feet.
 - d. Slope Between 10 and 20 Percent: 25 feet.
 - e. Slope Over 20 Percent: 15 feet.
- C. Storm Drain Curb Inlet Sediment Trap: Protect each curb inlet using one of the following measures:
 - 1. Filter fabric wrapped around hollow concrete blocks blocking entire inlet face area; use one piece of fabric wrapped at least 1-1/2 times around concrete blocks and secured to prevent dislodging; orient cores of blocks so runoff passes into inlet.
 - 2. Straw bale row blocking entire inlet face area; anchor into pavement.
- D. Storm Drain Drop Inlet Sediment Traps: As detailed on drawings.
- E. Temporary Splash Pads: Stone aggregate over filter fabric; size to suit application; provide at downspout outlets and storm water outlets.
- F. Soil Stockpiles: Protect using one of the following measures:
 - 1. Cover with polyethylene film, secured by placing soil on outer edges.
 - 2. Cover with mulch at least 4 inches thickness of pine needles, sawdust, bark, wood chips, or shredded leaves, or 6 inches of straw or hay.
- G. Mulching: Use only for areas that may be subjected to erosion for less than 6 months.
- H. Temporary Seeding: Use where temporary vegetated cover is required.

3.04 INSTALLATION

- A. Silt Fences:
 - 1. Store and handle fabric in accordance with ASTM D4873.
 - 2. Where slope gradient is less than 3:1 or barriers will be in place less than 6 months, use nominal 16 inch high barriers with minimum 36 inch long posts spaced at 6 feet maximum, with fabric embedded at least 4 inches in ground.
 - 3. Where slope gradient is steeper than 3:1 or barriers will be in place over 6 months, use nominal 28 inch high barriers, minimum 48 inch long posts spaced at 6 feet maximum, with fabric embedded at least 6 inches in ground.
 - 4. Where slope gradient is steeper than 3:1 and vertical height of slope between barriers is more than 20 feet, use nominal 32 inch high barriers with woven wire reinforcement and steel posts spaced at 4 feet maximum, with fabric embedded at least 6 inches in ground.
 - 5. Install with top of fabric at nominal height and embedment as specified.
 - 6. Do not splice fabric width; minimize splices in fabric length; splice at post only, overlapping at least 18 inches, with extra post.
 - 7. Fasten fabric to steel posts using wire, nylon cord, or integral pockets.
 - 8. Wherever runoff will flow around end of barrier or over the top, provide temporary splash pad or other outlet protection; at such outlets in the run of the barrier, make barrier not more than 12 inches high with post spacing not more than 4 feet.
- B. Mulching Over Small and Medium Areas:
 - 1. Dry Straw and Hay: Apply 4 to 6 inches depth.
- C. Temporary Seeding:
 - 1. When hydraulic seeder is used, seedbed preparation is not required.
 - 2. When surface soil has been sealed by rainfall or consists of smooth undisturbed cut slopes, and conventional or manual seeding is to be used, prepare seedbed by scarifying sufficiently to allow seed to lodge and germinate.
 - 3. If temporary mulching was used on planting area but not removed, apply nitrogen fertilizer at 1 pound per 1000 sq ft.
 - 4. On soils of very low fertility, apply 10-10-10 fertilizer at rate of 12 to 16 pounds per 1000 sq ft.
 - 5. Incorporate fertilizer into soil before seeding.
 - 6. Apply seed uniformly; if using drill or cultipacker seeders place seed 1/2 to 1 inch deep.
 - 7. Irrigate as required to thoroughly wet soil to depth that will ensure germination, without causing runoff or erosion.
 - 8. Repeat irrigation as required until grass is established.

3.05 MAINTENANCE

- A. Inspect preventive measures weekly, within 24 hours after the end of any storm that produces 0.5 inches or more rainfall at the project site, and daily during prolonged rainfall.
- B. Repair deficiencies immediately.
- C. Silt Fences:
 - 1. Promptly replace fabric that deteriorates unless need for fence has passed.
 - 2. Remove silt deposits that exceed one-third of the height of the fence.
 - 3. Repair fences that are undercut by runoff or otherwise damaged, whether by runoff or other causes.
- D. Clean out temporary sediment control structures weekly and relocate soil on site.
- E. Place sediment in appropriate locations on site; do not remove from site.

3.06 CLEAN UP

- A. Remove temporary measures after permanent measures have been installed, unless permitted to remain by Architect.
- B. Clean out temporary sediment control structures that are to remain as permanent measures.

- C. Where removal of temporary measures would leave exposed soil, shape surface to an acceptable grade and finish to match adjacent ground surfaces.

END OF SECTION

SECTION 01 6000
PRODUCT REQUIREMENTS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. General product requirements.
- B. Transportation, handling, storage and protection.
- C. Product option requirements.
- D. Substitution limitations and procedures.
- E. Maintenance materials, including extra materials, spare parts, tools, and software.

1.02 RELATED REQUIREMENTS

- A. Section 01 1000 - Summary: Lists of products to be removed from existing building.
- B. Section 01 4000 - Quality Requirements: Product quality monitoring.

1.03 REFERENCE STANDARDS

- A. 16 CFR 260.13 - Guides for the Use of Environmental Marketing Claims; Federal Trade Commission; Recycled Content; current edition.
- B. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.04 SUBMITTALS

- A. Product Data Submittals: Submit manufacturer's standard published data. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturers' standard data to provide information specific to this Project.
- B. Shop Drawing Submittals: Prepared specifically for this Project; indicate utility and electrical characteristics, utility connection requirements, and location of utility outlets for service for functional equipment and appliances.
- C. Sample Submittals: Illustrate functional and aesthetic characteristics of the product, with integral parts and attachment devices. Coordinate sample submittals for interfacing work.
 - 1. For selection from standard finishes, submit samples of the full range of the manufacturer's standard colors, textures, and patterns.

PART 2 PRODUCTS**2.01 NEW PRODUCTS**

- A. Provide new products unless specifically required or permitted by the Contract Documents.
- B. DO NOT USE products having any of the following characteristics:
 - 1. Made of wood from newly cut old growth timber.
 - 2. Containing lead, cadmium, asbestos.
- C. Where all other criteria are met, Contractor shall give preference to products that:
 - 1. Result in less construction waste.
 - 2. Are made of recycled materials.
 - 3. If made of wood, are made of sustainably harvested wood, wood chips, or wood fiber.
 - 4. Have a published GreenScreen Chemical Hazard Analysis.

2.02 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Use any product meeting those standards or description.
- B. Products Specified by Naming One or More Manufacturers: Use a product of one of the manufacturers named and meeting specifications, no options or substitutions allowed.

- C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.

2.03 MAINTENANCE MATERIALS

- A. Furnish extra materials, spare parts, tools, and software of types and in quantities specified in individual specification sections.
- B. Deliver to Project site; obtain receipt prior to final payment.

PART 3 EXECUTION

3.01 SUBSTITUTION PROCEDURES

- A. Document each request with complete data substantiating compliance of proposed substitution with Contract Documents.
- B. A request for substitution constitutes a representation that the submitter:
 - 1. Has investigated proposed product and determined that it meets or exceeds the quality level of the specified product.
 - 2. Agrees to provide the same warranty for the substitution as for the specified product.
 - 3. Agrees to coordinate installation and make changes to other Work that may be required for the Work to be complete with no additional cost to Owner.
 - 4. Waives claims for additional costs or time extension that may subsequently become apparent.

3.02 TRANSPORTATION AND HANDLING

- A. Package products for shipment in manner to prevent damage; for equipment, package to avoid loss of factory calibration.
- B. If special precautions are required, attach instructions prominently and legibly on outside of packaging.
- C. Coordinate schedule of product delivery to designated prepared areas in order to minimize site storage time and potential damage to stored materials.
- D. Transport and handle products in accordance with manufacturer's instructions.
- E. Transport materials in covered trucks to prevent contamination of product and littering of surrounding areas.
- F. Promptly inspect shipments to ensure that products comply with requirements, quantities are correct, and products are undamaged.
- G. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage, and to minimize handling.
- H. Arrange for the return of packing materials, such as wood pallets, where economically feasible.

3.03 STORAGE AND PROTECTION

- A. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication.
- B. Store and protect products in accordance with manufacturers' instructions.
- C. Store with seals and labels intact and legible.
- D. Store sensitive products in weather tight, climate controlled, enclosures in an environment favorable to product.
- E. For exterior storage of fabricated products, place on sloped supports above ground.
- F. Protect products from damage or deterioration due to construction operations, weather, precipitation, humidity, temperature, sunlight and ultraviolet light, dirt, dust, and other contaminants.
- G. Comply with manufacturer's warranty conditions, if any.

- H. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- I. Prevent contact with material that may cause corrosion, discoloration, or staining.
- J. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- K. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

END OF SECTION

SECTION 01 7000
EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Examination, preparation, and general installation procedures.
- B. Requirements for alterations work, including selective demolition, except removal, disposal, and/or remediation of hazardous materials and toxic substances.
- C. Cutting and patching.
- D. Surveying for laying out the work.
- E. Cleaning and protection.
- F. Starting of systems and equipment.
- G. Demonstration and instruction of Owner personnel.
- H. Closeout procedures, including Contractor's Correction Punch List, except payment procedures.
- I. General requirements for maintenance service.

1.02 RELATED REQUIREMENTS

- A. Section 01 1000 - Summary: Limitations on working in existing building; continued occupancy; work sequence; identification of salvaged and relocated materials.
- B. Section 01 3000 - Administrative Requirements: Submittals procedures, Electronic document submittal service.
- C. Section 01 4000 - Quality Requirements: Testing and inspection procedures.
- D. Section 01 5000 - Temporary Facilities and Controls: Temporary exterior enclosures.
- E. Section 01 5713 - Temporary Erosion and Sediment Control: Additional erosion and sedimentation control requirements.
- F. Section 01 7800 - Closeout Submittals: Project record documents, operation and maintenance data, warranties and bonds.

1.03 REFERENCE STANDARDS

- A. NFPA 241 - Standard for Safeguarding Construction, Alteration, and Demolition Operations; 2013.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Cutting and Patching: Submit written request in advance of cutting or alteration that affects:
 - 1. Structural integrity of any element of Project.
 - 2. Integrity of weather exposed or moisture resistant element.
 - 3. Efficiency, maintenance, or safety of any operational element.
 - 4. Visual qualities of sight exposed elements.
 - 5. Work of Owner or separate Contractor.

1.05 PROJECT CONDITIONS

- A. Grade site to drain. Maintain excavations free of water. Provide, operate, and maintain pumping equipment.
- B. Protect site from puddling or running water. Provide water barriers as required to protect site from soil erosion.
- C. Ventilate enclosed areas to assist cure of materials, to dissipate humidity, and to prevent accumulation of dust, fumes, vapors, or gases.
- D. Dust Control: Execute work by methods to minimize raising dust from construction operations. Provide positive means to prevent air-borne dust from dispersing into atmosphere and over adjacent property.

1. Provide dust-proof enclosures to prevent entry of dust generated outdoors.
 2. Provide dust-proof barriers between construction areas and areas continuing to be occupied by Owner.
- E. Erosion and Sediment Control: Plan and execute work by methods to control surface drainage from cuts and fills, from borrow and waste disposal areas. Prevent erosion and sedimentation.
1. Minimize amount of bare soil exposed at one time.
 2. Provide temporary measures such as berms, dikes, and drains, to prevent water flow.
- F. Pollution Control: Provide methods, means, and facilities to prevent contamination of soil, water, and atmosphere from discharge of noxious, toxic substances, and pollutants produced by construction operations. Comply with federal, state, and local regulations.

1.06 COORDINATION

- A. Coordinate scheduling, submittals, and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements, with provisions for accommodating items installed later.
- B. Notify affected utility companies and comply with their requirements.
- C. Verify that utility requirements and characteristics of new operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent responsibilities for installing, connecting to, and placing in service, such equipment.
- D. Coordinate space requirements, supports, and installation of mechanical and electrical work that are indicated diagrammatically on Drawings. Follow routing shown for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
- E. In finished areas except as otherwise indicated, conceal pipes, ducts, and wiring within the construction. Coordinate locations of fixtures and outlets with finish elements.
- F. Coordinate completion and clean-up of work of separate sections.
- G. After Owner occupancy of premises, coordinate access to site for correction of defective work and work not in accordance with Contract Documents, to minimize disruption of Owner's activities.

PART 2 PRODUCTS

2.01 PATCHING MATERIALS

- A. New Materials: As specified in product sections; match existing products and work for patching and extending work.
- B. Type and Quality of Existing Products: Determine by inspecting and testing products where necessary, referring to existing work as a standard.
- C. Product Substitution: For any proposed change in materials, submit request for substitution described in Section 01 6000 - Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent work. Start of work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Take field measurements before confirming product orders or beginning fabrication, to minimize waste due to over-ordering or misfabrication.
- E. Verify that utility services are available, of the correct characteristics, and in the correct locations.

- F. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work, assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions.

3.02 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

3.03 LAYING OUT THE WORK

- A. Verify locations of survey control points prior to starting work.
- B. Promptly notify Architect of any discrepancies discovered.
- C. Protect survey control points prior to starting site work; preserve permanent reference points during construction.
- D. Promptly report to Architect the loss or destruction of any reference point or relocation required because of changes in grades or other reasons.
- E. Replace dislocated survey control points based on original survey control. Make no changes without prior written notice to Architect.
- F. Utilize recognized engineering survey practices.
- G. Establish elevations, lines and levels. Locate and lay out by instrumentation and similar appropriate means:
 - 1. Site improvements including pavements; stakes for grading, fill and topsoil placement; utility locations, slopes, and invert elevations.
 - 2. Grid or axis for structures.
 - 3. Building foundation, column locations, ground floor elevations.
- H. Periodically verify layouts by same means.
- I. Maintain a complete and accurate log of control and survey work as it progresses.

3.04 GENERAL INSTALLATION REQUIREMENTS

- A. Install products as specified in individual sections, in accordance with manufacturer's instructions and recommendations, and so as to avoid waste due to necessity for replacement.
- B. Make vertical elements plumb and horizontal elements level, unless otherwise indicated.
- C. Install equipment and fittings plumb and level, neatly aligned with adjacent vertical and horizontal lines, unless otherwise indicated.
- D. Make consistent texture on surfaces, with seamless transitions, unless otherwise indicated.
- E. Make neat transitions between different surfaces, maintaining texture and appearance.

3.05 ALTERATIONS

- A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
 - 1. Verify that construction and utility arrangements are as shown.
 - 2. Report discrepancies to Architect before disturbing existing installation.
 - 3. Beginning of alterations work constitutes acceptance of existing conditions.
- B. Remove existing work as indicated and as required to accomplish new work.
 - 1. Remove items indicated on drawings.
 - 2. Relocate items indicated on drawings.
 - 3. Where new surface finishes are to be applied to existing work, perform removals, patch, and prepare existing surfaces as required to receive new finish; remove existing finish if necessary for successful application of new finish.

4. Where new surface finishes are not specified or indicated, patch holes and damaged surfaces to match adjacent finished surfaces as closely as possible.
- C. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, Telecommunications, and _____): Remove, relocate, and extend existing systems to accommodate new construction.
 1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components; if necessary, modify installation to allow access or provide access panel.
 2. Where existing systems or equipment are not active and Contract Documents require reactivation, put back into operational condition; repair supply, distribution, and equipment as required.
 3. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
 - a. Disable existing systems only to make switchovers and connections; minimize duration of outages.
 - b. Provide temporary connections as required to maintain existing systems in service.
 4. Verify that abandoned services serve only abandoned facilities.
 5. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification; patch holes left by removal using materials specified for new construction.
- D. Protect existing work to remain.
 1. Prevent movement of structure; provide shoring and bracing if necessary.
 2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
 3. Repair adjacent construction and finishes damaged during removal work.
- E. Adapt existing work to fit new work: Make as neat and smooth transition as possible.
- F. Patching: Where the existing surface is not indicated to be refinished, patch to match the surface finish that existed prior to cutting. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.
- G. Refinish existing surfaces as indicated:
 1. Where rooms or spaces are indicated to be refinished, refinish all visible existing surfaces to remain to the specified condition for each material, with a neat transition to adjacent finishes.
 2. If mechanical or electrical work is exposed accidentally during the work, re-cover and refinish to match.
- H. Clean existing systems and equipment.
- I. Remove demolition debris and abandoned items from alterations areas and dispose of off-site; do not burn or bury.
- J. Do not begin new construction in alterations areas before demolition is complete.
- K. Comply with all other applicable requirements of this section.

3.06 CUTTING AND PATCHING

- A. Whenever possible, execute the work by methods that avoid cutting or patching.
- B. See Alterations article above for additional requirements.
- C. Perform whatever cutting and patching is necessary to:
 1. Complete the work.
 2. Fit products together to integrate with other work.
 3. Provide openings for penetration of mechanical, electrical, and other services.
 4. Match work that has been cut to adjacent work.
 5. Repair areas adjacent to cuts to required condition.
 6. Repair new work damaged by subsequent work.

- 7. Remove samples of installed work for testing when requested.
- 8. Remove and replace defective and non-conforming work.
- D. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to original condition.
- E. Employ original installer to perform cutting for weather exposed and moisture resistant elements, and sight exposed surfaces.
- F. Cut rigid materials using masonry saw or core drill. Pneumatic tools not allowed without prior approval.
- G. Restore work with new products in accordance with requirements of Contract Documents.
- H. Fit work air tight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- I. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material in accordance with Section 07 8400, to full thickness of the penetrated element.
- J. Patching:
 - 1. Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
 - 2. Match color, texture, and appearance.
 - 3. Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

3.07 PROGRESS CLEANING

- A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.
- B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces, and other closed or remote spaces, prior to enclosing the space.
- C. Broom and vacuum clean interior areas prior to start of surface finishing, and continue cleaning to eliminate dust.
- D. Collect and remove waste materials, debris, and trash/rubbish from site periodically and dispose off-site; do not burn or bury.

3.08 PROTECTION OF INSTALLED WORK

- A. Protect installed work from damage by construction operations.
- B. Provide special protection where specified in individual specification sections.
- C. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.
- D. Provide protective coverings at walls, projections, jambs, sills, and soffits of openings.
- E. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage, or movement of heavy objects, by protecting with durable sheet materials.
- F. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- G. Remove protective coverings when no longer needed; reuse or recycle plastic coverings if possible.

3.09 SYSTEM STARTUP

- A. Coordinate schedule for start-up of various equipment and systems.
- B. Verify that each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, and for conditions that may cause damage.

- C. Verify tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer.
- D. Verify that wiring and support components for equipment are complete and tested.
- E. Execute start-up under supervision of applicable Contractor personnel and manufacturer's representative in accordance with manufacturers' instructions.
- F. Submit a written report that equipment or system has been properly installed and is functioning correctly.

3.10 DEMONSTRATION AND INSTRUCTION

- A. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at scheduled time, at equipment location.
- B. For equipment or systems requiring seasonal operation, perform demonstration for other season within six months.
- C. Provide a qualified person who is knowledgeable about the Project to perform demonstration and instruction of owner personnel.

3.11 ADJUSTING

- A. Adjust operating products and equipment to ensure smooth and unhindered operation.

3.12 FINAL CLEANING

- A. Use cleaning materials that are nonhazardous.
- B. Clean interior and exterior glass, surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.
- C. Remove all labels that are not permanent. Do not paint or otherwise cover fire test labels or nameplates on mechanical and electrical equipment.
- D. Clean equipment and fixtures to a sanitary condition with cleaning materials appropriate to the surface and material being cleaned.
- E. Clean filters of operating equipment.
- F. Clean debris from roofs, gutters, downspouts, scuppers, overflow drains, area drains, drainage systems, and _____.
- G. Clean site; sweep paved areas, rake clean landscaped surfaces.
- H. Remove waste, surplus materials, trash/rubbish, and construction facilities from the site; dispose of in legal manner; do not burn or bury.

3.13 CLOSEOUT PROCEDURES

- A. Make submittals that are required by governing or other authorities.
- B. Accompany Project Coordinator on preliminary inspection to determine items to be listed for completion or correction in the Contractor's Correction Punch List for Contractor's Notice of Substantial Completion.
- C. Notify Architect when work is considered ready for Architect's Substantial Completion inspection.
- D. Submit written certification containing Contractor's Correction Punch List, that Contract Documents have been reviewed, work has been inspected, and that work is complete in accordance with Contract Documents and ready for Architect's Substantial Completion inspection.
- E. Conduct Substantial Completion inspection and create Final Correction Punch List containing Architect's and Contractor's comprehensive list of items identified to be completed or corrected and submit to Architect.
- F. Correct items of work listed in Final Correction Punch List and comply with requirements for access to Owner-occupied areas.

- G. Notify Architect when work is considered finally complete and ready for Architect's Substantial Completion final inspection.
- H. Complete items of work determined by Architect listed in executed Certificate of Substantial Completion.

3.14 MAINTENANCE

- A. Provide service and maintenance of components indicated in specification sections.
- B. Maintenance Period: As indicated in specification sections or, if not indicated, not less than one year from the Date of Substantial Completion or the length of the specified warranty, whichever is longer.
- C. Examine system components at a frequency consistent with reliable operation. Clean, adjust, and lubricate as required.
- D. Include systematic examination, adjustment, and lubrication of components. Repair or replace parts whenever required. Use parts produced by the manufacturer of the original component.
- E. Maintenance service shall not be assigned or transferred to any agent or subcontractor without prior written consent of the Owner.

END OF SECTION

**SECTION 01 7800
CLOSEOUT SUBMITTALS**

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Project Record Documents.
- B. Operation and Maintenance Data.
- C. Warranties and bonds.

1.02 RELATED REQUIREMENTS

- A. Section 01 3000 - Administrative Requirements: Submittals procedures, shop drawings, product data, and samples.
- B. Section 01 7000 - Execution and Closeout Requirements: Contract closeout procedures.

1.03 SUBMITTALS

- A. Project Record Documents: Submit documents to Architect with claim for final Application for Payment.
- B. Operation and Maintenance Data:
 - 1. Submit two copies of preliminary draft or proposed formats and outlines of contents before start of Work. Architect will review draft and return one copy with comments.
 - 2. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit completed documents within ten days after acceptance.
 - 3. Submit one copy of completed documents 15 days prior to final inspection. This copy will be reviewed and returned after final inspection, with Architect comments. Revise content of all document sets as required prior to final submission.
 - 4. Submit two sets of revised final documents in final form within 10 days after final inspection.
- C. Warranties and Bonds:
 - 1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within 10 days after acceptance.
 - 2. Make other submittals within 10 days after Date of Substantial Completion, prior to final Application for Payment.
 - 3. For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within 10 days after acceptance, listing the date of acceptance as the beginning of the warranty period.

PART 2 PRODUCTS - NOT USED**PART 3 EXECUTION****3.01 PROJECT RECORD DOCUMENTS**

- A. Maintain on site one set of the following record documents; record actual revisions to the Work:
 - 1. Drawings.
 - 2. Specifications.
 - 3. Addenda.
 - 4. Change Orders and other modifications to the Contract.
 - 5. Reviewed shop drawings, product data, and samples.
 - 6. Manufacturer's instruction for assembly, installation, and adjusting.
- B. Ensure entries are complete and accurate, enabling future reference by Owner.
- C. Store record documents separate from documents used for construction.
- D. Record information concurrent with construction progress.
- E. Specifications: Legibly mark and record at each product section description of actual products installed, including the following:
 - 1. Manufacturer's name and product model and number.

2. Product substitutions or alternates utilized.
 3. Changes made by Addenda and modifications.
- F. Record Drawings and Shop Drawings: Legibly mark each item to record actual construction including:
1. Measured depths of foundations in relation to finish first floor datum.
 2. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 3. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
 4. Field changes of dimension and detail.
 5. Details not on original Contract drawings.

3.02 OPERATION AND MAINTENANCE DATA

- A. Source Data: For each product or system, list names, addresses and telephone numbers of Subcontractors and suppliers, including local source of supplies and replacement parts.
- B. Product Data: Mark each sheet to clearly identify specific products and component parts, and data applicable to installation. Delete inapplicable information.
- C. Drawings: Supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams. Do not use Project Record Documents as maintenance drawings.
- D. Typed Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.

3.03 OPERATION AND MAINTENANCE DATA FOR MATERIALS AND FINISHES

- A. For Each Product, Applied Material, and Finish:
 1. Product data, with catalog number, size, composition, and color and texture designations.
 2. Information for re-ordering custom manufactured products.
- B. Instructions for Care and Maintenance: Manufacturer's recommendations for cleaning agents and methods, precautions against detrimental cleaning agents and methods, and recommended schedule for cleaning and maintenance.
- C. Moisture protection and weather-exposed products: Include product data listing applicable reference standards, chemical composition, and details of installation. Provide recommendations for inspections, maintenance, and repair.
- D. Additional information as specified in individual product specification sections.
- E. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.
- F. Provide a listing in Table of Contents for design data, with tabbed fly sheet and space for insertion of data.

3.04 OPERATION AND MAINTENANCE DATA FOR EQUIPMENT AND SYSTEMS

- A. For Each Item of Equipment and Each System:
 1. Description of unit or system, and component parts.
 2. Identify function, normal operating characteristics, and limiting conditions.
 3. Include performance curves, with engineering data and tests.
 4. Complete nomenclature and model number of replaceable parts.
- B. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.
- C. Panelboard Circuit Directories: Provide electrical service characteristics, controls, and communications; typed.
- D. Include color coded wiring diagrams as installed.

- E. Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
- F. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and trouble shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- G. Provide servicing and lubrication schedule, and list of lubricants required.
- H. Include manufacturer's printed operation and maintenance instructions.
- I. Include sequence of operation by controls manufacturer.
- J. Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- K. Provide control diagrams by controls manufacturer as installed.
- L. Provide Contractor's coordination drawings, with color coded piping diagrams as installed.
- M. Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- N. Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- O. Include test and balancing reports.
- P. Additional Requirements: As specified in individual product specification sections.

3.05 ASSEMBLY OF OPERATION AND MAINTENANCE MANUALS

- A. Assemble operation and maintenance data into durable manuals for Owner's personnel use, with data arranged in the same sequence as, and identified by, the specification sections.
- B. Where systems involve more than one specification section, provide separate tabbed divider for each system.
- C. Prepare instructions and data by personnel experienced in maintenance and operation of described products.
- D. Prepare data in the form of an instructional manual.
- E. Binders: Commercial quality, 8-1/2 by 11 inch three D side ring binders with durable plastic covers; 2 inch maximum ring size. When multiple binders are used, correlate data into related consistent groupings.
- F. Cover: Identify each binder with typed or printed title OPERATION AND MAINTENANCE INSTRUCTIONS; identify title of Project; identify subject matter of contents.
- G. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Architect, Consultants, Contractor and subcontractors, with names of responsible parties.
- H. Tables of Contents: List every item separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.
- I. Dividers: Provide tabbed dividers for each separate product and system; identify the contents on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.
- J. Text: Manufacturer's printed data, or typewritten data on 24 pound paper.
- K. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.
- L. Provide a listing in Table of Contents for design data, with tabbed dividers and space for insertion of data.

- M. Table of Contents: Provide title of Project; names, addresses, and telephone numbers of Architect, Consultants, and Contractor with name of responsible parties; schedule of products and systems, indexed to content of the volume.

3.06 WARRANTIES AND BONDS

- A. Obtain warranties and bonds, executed in duplicate by responsible Subcontractors, suppliers, and manufacturers, within 10 days after completion of the applicable item of work. Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial completion is determined.
- B. Verify that documents are in proper form, contain full information, and are notarized.
- C. Co-execute submittals when required.
- D. Retain warranties and bonds until time specified for submittal.
- E. Manual: Bind in commercial quality 8-1/2 by 11 inch three D side ring binders with durable plastic covers.
- F. Cover: Identify each binder with typed or printed title WARRANTIES AND BONDS, with title of Project; name, address and telephone number of Contractor and equipment supplier; and name of responsible company principal.
- G. Table of Contents: Neatly typed, in the sequence of the Table of Contents of the Project Manual, with each item identified with the number and title of the specification section in which specified, and the name of product or work item.
- H. Separate each warranty or bond with index tab sheets keyed to the Table of Contents listing. Provide full information, using separate typed sheets as necessary. List Subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.

END OF SECTION

**SECTION 07 9005
JOINT SEALERS**

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Sealants and joint backing.

1.02 REFERENCE STANDARDS

- A. ASTM C834 - Standard Specification for Latex Sealants; 2014.
- B. ASTM C919 - Standard Practice for Use of Sealants in Acoustical Applications; 2012.
- C. ASTM C920 - Standard Specification for Elastomeric Joint Sealants; 2014.
- D. ASTM C1193 - Standard Guide for Use of Joint Sealants; 2013.
- E. ASTM D1667 - Standard Specification for Flexible Cellular Materials--Poly(Vinyl Chloride) Foam (Closed-Cell); 2005 (Reapproved 2011).
- F. SCAQMD 1168 - South Coast Air Quality Management District Rule No.1168; current edition; www.aqmd.gov.

1.03 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate the work with other sections referencing this section.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data indicating sealant chemical characteristics, performance criteria, substrate preparation, limitations, and color availability.
- C. Manufacturer's Installation Instructions: Indicate surface preparation and perimeter conditions requiring special attention.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- B. Applicator Qualifications: Company specializing in performing the work of this section with minimum three years experience.

1.06 FIELD CONDITIONS

- A. Maintain temperature and humidity recommended by the sealant manufacturer during and after installation.

1.07 WARRANTY

- A. See Section 01 7800 - Closeout Submittals, for additional warranty requirements.
- B. Correct defective work within a five year period after Date of Substantial Completion.
- C. Warranty: Include coverage for installed sealants and accessories which fail to achieve airtight seal, exhibit loss of adhesion or cohesion, or do not cure.

PART 2 PRODUCTS**2.01 MANUFACTURERS**

- A. Gunnable and Pourable Sealants:
 - 1. Adhesives Technology Corporation: www.atc.ws.
 - 2. BASF Construction Chemicals-Building Systems: www.buildingsystems.basf.com.
 - 3. Bostik Inc: www.bostik-us.com.
 - 4. Dow Corning Corporation: www.dowcorning.com.
 - 5. Hilti, Inc: www.us.hilti.com.
 - 6. Tremco Global Sealants: www.tremcosealants.com.
 - 7. W.R. Meadows, Inc: www.wrmeadows.com.

8. Substitutions: See Section 01 6000 - Product Requirements.

2.02 SEALANTS

- A. Sealants and Primers - General: Provide only products having lower volatile organic compound (VOC) content than required by South Coast Air Quality Management District Rule No.1168.
- B. Type 1 - General Purpose Exterior Sealant: Polyurethane; ASTM C920, Grade NS, Class 25 minimum; Uses M, G, and A; single component.
 - 1. Color: Standard colors matching finished surfaces.
 - 2. Applications: Use for:
 - a. Joints between concrete and other materials.
 - b. Joints between metal frames and other materials.
 - c. Other exterior joints for which no other sealant is indicated.
- C. Type 3 - General Purpose Interior Sealant: Acrylic emulsion latex; ASTM C834, Type OP, Grade NF single component, paintable.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that substrate surfaces are ready to receive work.
- B. Verify that joint backing and release tapes are compatible with sealant.

3.02 PREPARATION

- A. Remove loose materials and foreign matter that could impair adhesion of sealant.
- B. Clean and prime joints in accordance with manufacturer's instructions.
- C. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.
- D. Protect elements surrounding the work of this section from damage or disfigurement.

3.03 INSTALLATION

- A. Perform work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.
- B. Perform installation in accordance with ASTM C1193.
- C. Perform acoustical sealant application work in accordance with ASTM C919.
- D. Measure joint dimensions and size joint backers to achieve width-to-depth ratio, neck dimension, and surface bond area as recommended by manufacturer.
- E. Install bond breaker where joint backing is not used.
- F. Install sealant free of air pockets, foreign embedded matter, ridges, and sags.
- G. Apply sealant within recommended application temperature ranges. Consult manufacturer when sealant cannot be applied within these temperature ranges.
- H. Tool joints concave.

3.04 CLEANING

- A. Clean adjacent soiled surfaces.

3.05 PROTECTION

- A. Protect sealants until cured.

3.06 SCHEDULE

- A. Exterior Joints for Which No Other Sealant Type is Indicated: Type 1 .
- B. Interior Joints for Which No Other Sealant is Indicated: Type 3..
- C. Joints Between Pipe or Conduit penetrations at Walls and Floors.: Type 1.

END OF SECTION

SECTION 26 0501
MINOR ELECTRICAL DEMOLITION

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Electrical demolition.
- B. Extension of existing electrical systems.
- C. Maintaining Electrical Systems services.
- D. Electrical Systems switchover.

1.02 RELATED REQUIREMENTS

- A. Section 01 7000 - Execution and Closeout Requirements: Additional requirements for alterations work.

1.03 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

PART 2 PRODUCTS**2.01 MATERIALS AND EQUIPMENT**

- A. Materials and equipment for patching and extending work: As specified in individual sections.

PART 3 EXECUTION**3.01 EXAMINATION**

- A. Verify field measurements and circuiting arrangements are as shown on Drawings.
- B. Verify that abandoned wiring and equipment serve only abandoned facilities.
- C. Demolition drawings are based on casual field observation and existing record documents.
- D. Report discrepancies to Architect before disturbing existing installation.
- E. Beginning of demolition means installer accepts existing conditions.

3.02 PREPARATION

- A. Disconnect electrical systems in walls, floors, and ceilings to be removed only after new electrical system has been installed, tested, and approved.
- B. Coordinate utility service outages with utility company and Owner.
- C. Provide temporary wiring and connections to maintain existing systems in service during construction when work is not complete at the end of authorized work windows. When work must be performed on energized equipment or circuits, use personnel experienced in such operations.
- D. Existing Electrical Service:
 - 1. Obtain permission from Iowa Department of Transportation at least 72 hours before partially or completely disabling system. Owner reserves the right to deny permission for outages based on ongoing operations and conditions. Verify shutdown with Owner 24 hours prior to scheduled shutdown to ensure changing weather conditions have not affected shutdown decisions.
 - 2. Ensure Owner's personnel have prepared existing generator for operation during main distribution panel replacement.
 - 3. Schedule outage detailing shutdown, disconnections/disassembly, installation/re-installation/reconnections, and start-up. Minimize outage durations.
 - 4. Replace branch panelboards one at a time. Reconnect existing circuits to new circuit breakers.
 - 5. Coordinate construction activities with utility company activities on-site.

3.03 DEMOLITION AND EXTENSION OF EXISTING ELECTRICAL WORK

- A. Perform work for removal and disposal of equipment and materials containing toxic substances regulated under the Federal Toxic Substances Control Act (TSCA) in accordance with applicable federal, state, and local regulations. Applicable equipment and materials include, but are not limited to:
 - 1. PCB-containing electrical equipment, including transformers, capacitors, and switches.
 - 2. PCB- and DEHP-containing lighting ballasts.
 - 3. Mercury-containing lamps and tubes, including fluorescent lamps, high intensity discharge (HID), arc lamps, ultra-violet, high pressure sodium, mercury vapor, ignitron tubes, neon, and incandescent.
- B. Remove, relocate, and extend existing installations to accommodate new construction.
- C. Remove abandoned wiring to source of supply.
- D. Remove exposed abandoned conduit, including abandoned conduit above accessible ceiling finishes. Cut conduit flush with walls and floors, and patch surfaces.
- E. Disconnect abandoned outlets and remove devices. Remove abandoned outlets if conduit servicing them is abandoned and removed. Provide blank cover for abandoned outlets that are not removed.
- F. Disconnect and remove abandoned panelboards and distribution equipment.
- G. Disconnect and remove electrical devices and equipment serving utilization equipment that has been removed.
- H. Disconnect and remove abandoned luminaires. Remove brackets, stems, hangers, and other accessories.
- I. Repair adjacent construction and finishes damaged during demolition and extension work.
- J. Maintain access to existing electrical installations that remain active. Modify installation or provide access panel as appropriate.
- K. Extend existing installations using materials and methods compatible with existing electrical installations, or as specified.

3.04 CLEANING AND REPAIR

- A. Clean and repair existing materials and equipment that remain or that are to be reused.
- B. Panelboards: Clean exposed surfaces and check tightness of electrical connections. Replace damaged circuit breakers and provide closure plates for vacant positions. Provide typed circuit directory showing revised circuiting arrangement.

END OF SECTION

SECTION 26 0526
GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Grounding and bonding requirements.
- B. Conductors for grounding and bonding.
- C. Connectors for grounding and bonding.
- D. Ground rod electrodes.

1.02 RELATED REQUIREMENTS

- A. Section 26 0519 - Low-Voltage Electrical Power Conductors and Cables: Additional requirements for conductors for grounding and bonding, including conductor color coding.
- B. Section 03 3000 - Cast-in-Place Concrete.

1.03 REFERENCE STANDARDS

- A. IEEE 81 - Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System; Institute of Electrical and Electronic Engineers; 2012.
- B. NECA 1 - Standard for Good Workmanship in Electrical Construction; National Electrical Contractors Association; 2010.
- C. NEMA GR 1 - Grounding Rod Electrodes and Grounding Rod Electrode Couplings; National Electrical Manufacturers Association; 2007.
- D. NETA STD ATS - Acceptance Testing Specifications for Electrical Power Distribution Equipment and Systems; International Electrical Testing Association; 2007.
- E. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- F. UL 467 - Grounding and Bonding Equipment; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.
- B. Sequencing:
 - 1. Do not install ground rod electrodes until final backfill and compaction is complete.

1.05 PERFORMANCE REQUIREMENTS

- A. Grounding System Resistance: 5 ohms.

1.06 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements for submittals procedures.
- B. Product Data: Provide for grounding electrodes and connections.
- C. Test Reports: Indicate overall resistance to ground and resistance of each electrode.

1.07 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.

PART 2 PRODUCTS**2.01 GROUNDING AND BONDING REQUIREMENTS**

- A. Existing Work: Where existing grounding and bonding system components are indicated to be reused, they may be reused only where they are free from corrosion, integrity and continuity are verified, and where acceptable to the authority having jurisdiction.
- B. Do not use products for applications other than as permitted by NFPA 70 and product listing.

- C. Unless specifically indicated to be excluded, provide all required components, conductors, connectors, conduit, boxes, fittings, supports, accessories, etc. as necessary for a complete grounding and bonding system.
- D. Where conductor size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
- E. Grounding System Resistance:
 - 1. Achieve specified grounding system resistance under normally dry conditions unless otherwise approved by Architect. Precipitation within the previous 48 hours does not constitute normally dry conditions.
 - 2. Grounding Electrode System: Not greater than 5 ohms to ground, when tested according to IEEE 81 using "fall-of-potential" method.
- F. Grounding Electrode System:
 - 1. Provide connection to required and supplemental grounding electrodes indicated to form grounding electrode system.
 - a. Provide continuous grounding electrode conductors without splice or joint.
 - b. Install grounding electrode conductors in raceway where exposed to physical damage. Bond grounding electrode conductor to metallic raceways at each end with bonding jumper.
 - 2. Ground Rod Electrode(s):
 - a. Provide single electrode unless otherwise indicated or required.
 - b. Space electrodes not less than 10 feet from each other and any other ground electrode.
 - c. Where location is not indicated, locate electrode(s) at least 5 feet outside building perimeter foundation as near as possible to electrical service entrance; where possible, locate in softscape (uncovered) area.
 - 3. Provide additional ground electrode(s) as required to achieve specified grounding electrode system resistance.
- G. Service-Supplied System Grounding:
 - 1. For each service disconnect, provide grounding electrode conductor to connect neutral (grounded) service conductor to grounding electrode system. Unless otherwise indicated, make connection at neutral (grounded) bus in service disconnect enclosure.
- H. Grounding for Separate Building or Structure Supplied by Feeder(s) or Branch Circuits:
 - 1. Provide grounding electrode system for each separate building or structure.
 - 2. Provide equipment grounding conductor routed with supply conductors.
 - 3. For each disconnecting means, provide grounding electrode conductor to connect equipment ground bus to grounding electrode system.
 - 4. Do not make any connections and remove any factory-installed jumpers between neutral (grounded) conductors and ground.

2.02 GROUNDING AND BONDING COMPONENTS

- A. General Requirements:
 - 1. Provide products listed, classified, and labeled as suitable for the purpose intended.
 - 2. Provide products listed and labeled as complying with UL 467 where applicable.
- B. Conductors for Grounding and Bonding, in Addition to Requirements of Section 26 0526:
 - 1. Use insulated copper conductors unless otherwise indicated.
 - a. Exceptions:
 - 1) Use bare copper conductors where installed underground in direct contact with earth.
 - 2) Use bare copper conductors where directly encased in concrete (not in raceway).
- C. Connectors for Grounding and Bonding:
 - 1. Description: Connectors appropriate for the application and suitable for the conductors and items to be connected; listed and labeled as complying with UL 467.

2. Unless otherwise indicated, use exothermic welded connections for underground, concealed and other inaccessible connections.
 3. Unless otherwise indicated, use mechanical connectors, compression connectors, or exothermic welded connections for accessible connections.
- D. Ground Rod Electrodes:
1. Comply with NEMA GR 1.
 2. Material: Copper-bonded (copper-clad) steel.
 3. Size: 3/4 inch diameter by 10 feet length, unless otherwise indicated.

2.03 MANUFACTURERS

- A. Cooper Power Systems, a division of Cooper Industries: www.cooperindustries.com.
- B. Framatome Connectors International: www.fciconnect.com.
- C. Lightning Master Corporation: www.lightningmaster.com.
- D. Substitutions: See Section 01 6000 - Product Requirements.
1. Cooper Power Systems, a division of Cooper Industries: www.cooperindustries.com.
 2. Framatome Connectors International: www.fciconnect.com.
 3. Lightning Master Corporation: www.lightningmaster.com.
 4. Substitutions: See Section 01 6000 - Product Requirements.
- E. Rod Electrodes: Copper.
1. Diameter: 3/4 inch.
 2. Length: 10 feet.

2.04 CONNECTORS AND ACCESSORIES

- A. Mechanical Connectors: Bronze.
- B. Wire: Stranded copper.
- C. Grounding Electrode Conductor: Size to meet NFPA 70 requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that work likely to damage grounding and bonding system components has been completed.
- B. Verify that field measurements are as shown on the drawings.
- C. Verify that conditions are satisfactory for installation prior to starting work.
- D. Verify existing conditions prior to beginning work.
- E. Verify that final backfill and compaction has been completed before driving rod electrodes.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install grounding and bonding system components in a neat and workmanlike manner in accordance with NECA 1.
- C. Ground Rod Electrodes: Unless otherwise indicated, install ground rod electrodes vertically. Where encountered rock prohibits vertical installation, install at 45 degree angle or bury horizontally in trench at least 30 inches (750 mm) deep in accordance with NFPA 70 or provide ground plates.
- D. Make grounding and bonding connections using specified connectors.
1. Remove appropriate amount of conductor insulation for making connections without cutting, nicking or damaging conductors. Do not remove conductor strands to facilitate insertion into connector.
 2. Remove nonconductive paint, enamel, or similar coating at threads, contact points, and contact surfaces.

3. Exothermic Welds: Make connections using molds and weld material suitable for the items to be connected in accordance with manufacturer's recommendations.
4. Mechanical Connectors: Secure connections according to manufacturer's recommended torque settings.
5. Compression Connectors: Secure connections using manufacturer's recommended tools and dies.

3.03 FIELD QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for additional requirements.
- B. Perform inspection in accordance with Section 01 4000.
- C. Inspect and test in accordance with NETA ATS except Section 4.
- D. Perform inspections and tests listed in NETA ATS, Section 7.13.
- E. Perform ground electrode resistance tests under normally dry conditions. Precipitation within the previous 48 hours does not constitute normally dry conditions.
- F. Investigate and correct deficiencies where measured ground resistances do not comply with specified requirements.

END OF SECTION

SECTION 26 0534**CONDUIT****PART 1 GENERAL****1.01 SECTION INCLUDES**

- A. Rigid polyvinyl chloride (PVC) conduit.
- B. Conduit fittings.
- C. Accessories.
- D. Conduit, fittings and conduit bodies.

1.02 RELATED REQUIREMENTS

- A. Section 26 0526 - Grounding and Bonding for Electrical Systems.
- B. Section 26 0553 - Identification for Electrical Systems.
- C. Section 26 0537 - Boxes.
- D. Section 31 2316.13 - Trenching: Excavating, bedding, and backfilling.

1.03 REFERENCE STANDARDS

- A. ANSI C80.6 - American National Standard for Electrical Intermediate Metal Conduit (EIMC); 2005.
- B. NECA 1 - Standard for Good Workmanship in Electrical Construction; National Electrical Contractors Association; 2010.
- C. NEMA FB 1 - Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable; National Electrical Manufacturers Association; 2012 (ANSI/NEMA FB 1).
- D. NEMA TC 2 - Electrical Polyvinyl Chloride (PVC) Conduit; National Electrical Manufacturers Association; 2013.
- E. NEMA TC 3 - Polyvinyl Chloride (PVC) Fittings for Use with Rigid PVC Conduit and Tubing; National Electrical Manufacturers Association; 2015.
- F. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. UL 651 - Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate minimum sizes of conduits with the actual conductors to be installed, including adjustments for conductor sizes increased for voltage drop.
 - 2. Coordinate the arrangement of conduits with structural members, ductwork, piping, equipment and other potential conflicts installed under other sections or by others.
 - 3. Verify exact conduit termination locations required for boxes, enclosures, and equipment installed under other sections or by others.
 - 4. Coordinate the work with other trades to provide roof penetrations that preserve the integrity of the roofing system and do not void the roof warranty.
 - 5. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.
- B. Sequencing:
 - 1. Do not begin installation of conductors and cables until installation of conduit is complete between outlet, junction and splicing points.

1.05 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements for submittals procedures.

- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for conduits and fittings.

1.06 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.
- B. Products: Listed and classified by Underwriters Laboratories Inc. as suitable for purpose specified and shown.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store conduit and fittings in accordance with manufacturer's instructions.
- B. Protect conduit from corrosion and entrance of debris by storing above grade. Provide appropriate covering.
- C. Protect PVC conduit from sunlight.

PART 2 PRODUCTS

2.01 CONDUIT APPLICATIONS

- A. Do not use conduit and associated fittings for applications other than as permitted by NFPA 70 and product listing.
- B. Unless otherwise indicated and where not otherwise restricted, use the conduit types indicated for the specified applications. Where more than one listed application applies, comply with the most restrictive requirements. Where conduit type for a particular application is not specified, use galvanized steel rigid metal conduit.
- C. Underground:
 - 1. Under Slab on Grade: Use rigid PVC conduit.
 - 2. Exterior, Direct-Buried: Use PVC-coated galvanized steel rigid metal conduit or rigid PVC conduit.
 - 3. Where rigid polyvinyl (PVC) conduit larger than 2 inch (53 mm) trade size is provided, use PVC-coated galvanized steel rigid metal conduit elbows for bends.
- D. Exposed within Brine Building Interior: Use Rigid PVC conduit.
- E. Exposed, Exterior: Use rigid PVC conduit.
- F. Corrosive Locations Above Ground: Use Schedule 40 PVC.
 - 1. Corrosive locations include, but are not limited to:
 - a. Brine Building.

2.02 CONDUIT REQUIREMENTS

- A. Provide all conduit, fittings, supports, and accessories required for a complete raceway system.
- B. Provide products listed, classified, and labeled as suitable for the purpose intended.
- C. Where conduit size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.

2.03 RIGID POLYVINYL CHLORIDE (PVC) CONDUIT

- A. Manufacturers:
 - 1. AFC Cable Systems, Inc: www.afcweb.com.
 - 2. Electri-Flex Company: www.electriflex.com.
 - 3. International Metal Hose: www.metalhose.com.
 - 4. Substitutions: See Section 01 6000 - Product Requirements.
- B. Description: NFPA 70, Type PVC rigid polyvinyl chloride conduit complying with NEMA TC 2 and listed and labeled as complying with UL 651; Schedule 40 unless otherwise noted; Schedule 80 where noted as "rigid PVC conduit" or where conduits are subject to physical damage; rated for use with conductors rated 90 degrees C.
- C. Fittings:

1. Manufacturer: Same as manufacturer of conduit to be connected.
2. Description: Fittings complying with NEMA TC 3 and listed and labeled as complying with UL 651; material to match conduit.

2.04 ACCESSORIES

- A. Conduit Joint Compound: Corrosion-resistant, electrically conductive; suitable for use with the conduit to be installed.
- B. Solvent Cement for PVC Conduit and Fittings: As recommended by manufacturer of conduit and fittings to be installed.
- C. Pull Strings: Use nylon cord with average breaking strength of not less than 200 pound-force.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on drawings.
- B. Verify that mounting surfaces are ready to receive conduits.
- C. Verify that conditions are satisfactory for installation prior to starting work.
- D. Verify routing and termination locations of conduit prior to rough-in.
- E. Conduit routing is shown on drawings in approximate locations unless dimensioned. Route as required to complete wiring system.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install conduit in a neat and workmanlike manner in accordance with NECA 1.
- C. Install galvanized steel rigid metal conduit (RMC) in accordance with NECA 101.
- D. Install intermediate metal conduit (IMC) in accordance with NECA 101.
- E. Install rigid polyvinyl chloride (PVC) conduit in accordance with NECA 111.
- F. Conduit Routing:
 1. Unless dimensioned, conduit routing indicated is diagrammatic.
 2. When conduit destination is indicated and routing is not shown, determine exact routing required.
 3. Conduits installed underground or embedded in concrete may be routed in the shortest possible manner unless otherwise indicated. Route all other conduits parallel or perpendicular to building structure and surfaces, following surface contours where practical.
 4. Arrange conduit to maintain adequate headroom, clearances, and access.
 5. Arrange conduit to provide no more than the equivalent of four 90 degree bends between pull points.
 6. Arrange conduit to provide no more than 150 feet between pull points for interior locations and 300 feet for exterior (underground) locations.
 7. Route conduits above water and drain piping where possible.
 8. Maintain minimum clearance of 6 inches between conduits and piping for other systems.
 9. Maintain minimum clearance of 12 inches between conduits and hot surfaces. This includes, but is not limited to:
 - a. Heaters.
 - b. Flues.
 10. Group parallel conduits in the same area together on a common rack.
 11. Coordinate conduit installation so as not to interfere with the operation of overhead doors and other equipment.
- G. Conduit Support:
 1. Secure and support conduits in accordance with NFPA 70 and Section 26 0529 using suitable supports and methods approved by the authority having jurisdiction.

2. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.
 3. Use conduit clamp to support single conduit from beam clamp or threaded rod.
 4. Use of wire for support of conduits is not permitted.
- H. Connections and Terminations:
1. Use suitable adapters where required to transition from one type of conduit to another.
 2. Provide insulating bushings or insulated throats at all conduit terminations to protect conductors.
 3. Secure joints and connections to provide maximum mechanical strength and electrical continuity.
- I. Penetrations:
1. Do not penetrate or otherwise notch or cut structural members, including footings and grade beams, without approval of Structural Engineer.
 2. Make penetrations perpendicular to surfaces unless otherwise indicated.
 3. Provide sleeves for penetrations as indicated or as required to facilitate installation. Set sleeves flush with exposed surfaces unless otherwise indicated or required.
 4. Conceal bends for conduit risers emerging above ground.
 5. Seal interior of conduits entering the building from underground at first accessible point to prevent entry of moisture and gases.
 6. Where conduits penetrate waterproof membrane, seal as required to maintain integrity of membrane.
- J. Conduit Movement Provisions: Where conduits are subject to movement, provide expansion and expansion/deflection fittings to prevent damage to enclosed conductors or connected equipment. This includes, but is not limited to:
1. Where conduits cross structural joints intended for expansion, contraction, or deflection.
 2. Where conduits are subject to earth movement by settlement or frost.
- K. Condensation Prevention: Where conduits cross barriers between areas of potential substantial temperature differential, provide sealing fitting or approved sealing compound at an accessible point near the penetration to prevent condensation. This includes, but is not limited to:
1. Where conduits pass from outdoors into conditioned interior spaces.
 2. Where conduits pass from unconditioned interior spaces into conditioned interior spaces.
- L. Provide grounding and bonding in accordance with Section 26 0526.

3.03 CLEANING

- A. Clean interior of conduits to remove moisture and foreign matter.

3.04 PROTECTION

- A. Immediately after installation of conduit, use suitable manufactured plugs to provide protection from entry of moisture and foreign material and do not remove until ready for installation of conductors.
- B. Install conduit securely, in a neat and workmanlike manner, as specified in NECA 1.

3.05 CLEANING

- A. Section 01 7000 - Execution Requirements: Final cleaning.
- B. Clean interior of boxes to remove dust, debris, and other material.
- C. Clean exposed surfaces and restore finish.

END OF SECTION

SECTION 26 0537
BOXES

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Outlet and device boxes up to 100 cubic inches, including those used as junction and pull boxes.
- B. Cabinets and enclosures, including junction and pull boxes larger than 100 cubic inches.
- C. Underground boxes/enclosures.
- D. Wall and ceiling outlet boxes.
- E. Pull and junction boxes.

1.02 RELATED REQUIREMENTS

- A. Section 26 0534 - Conduit:
 - 1. Conduit bodies and other fittings.
- B. Section 26 0553 - Identification for Electrical Systems: Identification products and requirements.
- C. Section 26 2726 - Wiring Devices:
 - 1. Wall plates.

1.03 REFERENCE STANDARDS

- A. NECA 1 - Standard for Good Workmanship in Electrical Construction; National Electrical Contractors Association; 2010.
- B. NECA 130 - Standard for Installing and Maintaining Wiring Devices; National Electrical Contractors Association; 2010.
- C. NEMA OS 1 - Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports; National Electrical Manufacturers Association; 2013 (ANSI/NEMA OS 1).
- D. NEMA OS 2 - Nonmetallic Outlet Boxes, Device Boxes, Covers and Box Supports; National Electrical Manufacturers Association; 2013 (ANSI/NEMA OS 2).
- E. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); National Electrical Manufacturers Association; 2014.
- F. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. SCTE 77 - Specification for Underground Enclosure Integrity; Society of Cable Telecommunications Engineers; 2013 (ANSI/SCTE 77).
- H. UL 50 - Enclosures for Electrical Equipment, Non-Environmental Considerations; Current Edition, Including All Revisions.
- I. UL 50E - Enclosures for Electrical Equipment, Environmental Considerations; Current Edition, Including All Revisions.
- J. UL 508A - Industrial Control Panels; Current Edition, Including All Revisions.
- K. UL 514A - Metallic Outlet Boxes; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for outlet and device boxes and cabinets and enclosures.
- C. Project Record Documents: Record actual locations and mounting heights of outlet, pull, and junction boxes on project record documents.

1.05 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.

PART 2 PRODUCTS

2.01 BOXES

- A. General Requirements:
 - 1. Do not use boxes and associated accessories for applications other than as permitted by NFPA 70 and product listing.
 - 2. Provide all boxes, fittings, supports, and accessories required for a complete raceway system and to accommodate devices and equipment to be installed.
 - 3. Provide products listed, classified, and labeled as suitable for the purpose intended.
 - 4. Where box size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
 - 5. Provide grounding terminals within boxes where equipment grounding conductors terminate.
- B. Outlet and Device Boxes Up to 100 cubic inches, Including Those Used as Junction and Pull Boxes:
 - 1. Use sheet-steel boxes for dry locations unless otherwise indicated or required.
 - 2. Use cast iron boxes or cast aluminum boxes for damp or wet locations and locations identified as waterproof unless otherwise indicated or required; furnish with compatible weatherproof gasketed covers.
 - 3. Use suitable concrete type boxes where flush-mounted in concrete.
 - 4. Use raised covers suitable for the type of wall construction and device configuration where required.
 - 5. Use shallow boxes where required by the type of wall construction.
 - 6. Do not use "through-wall" boxes designed for access from both sides of wall.
 - 7. Sheet-Steel Boxes: Comply with NEMA OS 1, and list and label as complying with UL 514A.
 - 8. Cast Metal Boxes: Comply with NEMA FB 1, and list and label as complying with UL 514A; furnish with threaded hubs.
 - 9. Boxes for Supporting Luminaires and Ceiling Fans: Listed as suitable for the type and weight of load to be supported; furnished with fixture stud to accommodate mounting of luminaire where required.
 - 10. Boxes for Ganged Devices: Use multigang boxes of single-piece construction. Do not use field-connected gangable boxes.
 - 11. Provide plastic, gasketed, NEMA 4X boxes at Reclamation Building.
 - 12. Wall Plates: Comply with Section 26 2726.
 - 13. Manufacturers:
 - a. Cooper Crouse-Hinds, a division of Eaton Corporation: www.cooperindustries.com.
 - b. Hubbell Incorporated; Bell Products: www.hubbell-rtb.com.
 - c. Thomas & Betts Corporation: www.tnb.com.
 - d. Substitutions: See Section 01 6000 - Product Requirements.
- C. Cabinets and Enclosures, Including Junction and Pull Boxes Larger Than 100 cubic inches:
 - 1. Comply with NEMA 250, and list and label as complying with UL 50 and UL 50E, or UL 508A.
 - 2. NEMA 250 Environment Type, Unless Otherwise Indicated:
 - a. Indoor Clean, Dry Locations: Type 1, painted steel.
 - b. Outdoor Locations: Type 3R, painted steel.
 - c. Reclamation Building and other indicated: Type 4X:
 - 1) Panelboards and Disconnects: Stainless Steel
 - 2) Other power and data junction boxes: Plastic, gasketed.
 - 3. Junction and Pull Boxes Larger Than 100 cubic inches:
 - a. Provide screw-cover or hinged-cover enclosures unless otherwise indicated.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on drawings.
- B. Verify that mounting surfaces are ready to receive boxes.
- C. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Perform work in a neat and workmanlike manner in accordance with NECA 1 and, where applicable, NECA 130, including mounting heights specified in those standards where mounting heights are not indicated.
- C. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.
- D. Box Supports:
 - 1. Secure and support boxes in accordance with NFPA 70 and Section 26 0529 using suitable supports and methods approved by the authority having jurisdiction.
 - 2. Provide independent support from building structure except for cast metal boxes (other than boxes used for fixture support) supported by threaded conduit connections in accordance with NFPA 70. Do not provide support from piping, ductwork, or other systems.
- E. Install boxes plumb and level.
- F. Flush-Mounted Boxes:
 - 1. Install boxes in noncombustible materials such as concrete, tile, gypsum, plaster, etc. so that front edge of box or associated raised cover is not set back from finished surface more than 1/4 inch or does not project beyond finished surface.
 - 2. Install boxes in combustible materials such as wood so that front edge of box or associated raised cover is flush with finished surface.
 - 3. Repair rough openings around boxes in noncombustible materials such as concrete, tile, gypsum, plaster, etc. so that there are no gaps or open spaces greater than 1/8 inch at the edge of the box.
- G. Install boxes as required to preserve insulation integrity.
- H. Close unused box openings.
- I. Install blank wall plates on junction boxes and on outlet boxes with no devices or equipment installed or designated for future use.
- J. Provide grounding and bonding in accordance with Section 26 0526.
- K. Install boxes securely, in a neat and workmanlike manner, as specified in NECA 1.
- L. Install in locations as shown on Drawings, and as required for splices, taps, wire pulling, equipment connections, and as required by NFPA 70.
- M. Electrical boxes are shown on Drawings in approximate locations unless dimensioned.
 - 1. Adjust box locations up to 10 feet if required to accommodate intended purpose.
- N. Maintain headroom and present neat mechanical appearance.
- O. Install pull boxes and junction boxes above accessible ceilings and in unfinished areas only.
- P. Align adjacent wall mounted outlet boxes for switches, thermostats, and similar devices.
- Q. Support boxes independently of conduit, except cast box that is connected to two rigid metal conduits both supported within 12 inches of box.
- R. Large Pull Boxes: Use hinged enclosure in interior dry locations, surface-mounted cast metal box in other locations.

3.03 ADJUSTING

- A. Adjust flush-mounting outlets to make front flush with finished wall material.
- B. Install knockout closures in unused box openings.

3.04 CLEANING

- A. Clean interior of boxes to remove dirt, debris, plaster and other foreign material.

3.05 PROTECTION

- A. Immediately after installation, protect boxes from entry of moisture and foreign material until ready for installation of conductors.
- B. Clean exposed surfaces and restore finish.

END OF SECTION

SECTION 26 0553
IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Electrical identification requirements.
- B. Identification nameplates and labels.
- C. Voltage markers.
- D. Underground warning tape.
- E. Warning signs and labels.

1.02 RELATED REQUIREMENTS

- A. Section 26 0519 - Low-Voltage Electrical Power Conductors and Cables: Color coding for power conductors and cables 600 V and less; vinyl color coding electrical tape.

1.03 REFERENCE STANDARDS

- A. ANSI Z535.2 - American National Standard for Environmental and Facility Safety Signs; 2011.
- B. ANSI Z535.4 - American National Standard for Product Safety Signs and Labels; 2011.
- C. ASTM D 709 - Standard Specification for Laminated Thermosetting Materials; 2001 (Reapproved 2007).
- D. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- E. UL 969 - Marking and Labeling Systems; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements for submittals procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for nameplates, labels, and markers.
- C. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation and installation of product.

1.05 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.

PART 2 PRODUCTS**2.01 IDENTIFICATION REQUIREMENTS**

- A. Identification for Equipment:
 - 1. Use identification nameplate to identify each piece of electrical distribution and control equipment and associated sections, compartments, and components.
 - a. Switchboards:
 - 1) Identify voltage and phase.
 - 2) Identify power source and circuit number. Include location when not within sight of equipment.
 - 3) Use identification nameplate to identify main overcurrent protective device.
 - 4) Use identification nameplate to identify load(s) served for each branch device. Do not identify spares and spaces.
 - b. Panelboards:
 - 1) Identify power source and circuit number. Include location when not within sight of equipment.

- 2) Identify main overcurrent protective device. Use identification label for panelboards with a door. For power distribution panelboards without a door, use identification nameplate.
- 3) Use typewritten circuit directory to identify load(s) served for panelboards with a door. Identify spares and spaces using pencil.
- c. Enclosed switches, circuit breakers, and motor controllers:
 - 1) Identify load(s) served. Include location when not within sight of equipment.
- d. Transfer Switches:
 - 1) Identify voltage and phase.
 - 2) Identify power source and circuit number for both normal power source and standby power source. Include location when not within sight of equipment.
- B. Identification for Conductors and Cables:
 - 1. Color Coding for Power Conductors 600 V and Less: Comply with Section 26 0519.

2.02 IDENTIFICATION NAMEPLATES AND LABELS

- A. Identification Labels:
 - 1. Materials: Use self-adhesive laminated plastic labels; UV, chemical, water, heat, and abrasion resistant.
 - 2. Text: Use factory pre-printed or machine-printed text. Do not use handwritten text unless otherwise indicated.
- B. Format for Equipment Identification:
 - 1. Minimum Size: 1 inch by 2.5 inches.
 - 2. Legend:
 - a. Equipment designation or other approved description.
 - 3. Text: All capitalized unless otherwise indicated.
 - 4. Minimum Text Height:
 - a. System Designation: 1 inch.
 - b. Equipment Designation: 1/2 inch.
 - c. Other Information: 1/4 inch.

2.03 UNDERGROUND WARNING TAPE

- A. Materials: Use non-detectable type polyethylene tape suitable for direct burial, unless otherwise indicated.
- B. Non-detectable Type Tape: 6 inches wide, with minimum thickness of 4 mil.
- C. Legend: Type of service, continuously repeated over full length of tape.
- D. Color:
 - 1. Tape for Buried Power Lines: Black text on red background.
 - 2. Tape for Buried Communication, Alarm, and Signal Lines: Black text on orange background.

2.04 WARNING SIGNS AND LABELS

- A. Comply with ANSI Z535.2 or ANSI Z535.4 as applicable.
- B. Warning Signs:
 - 1. Minimum Size: 7 by 10 inches unless otherwise indicated.
- C. Warning Labels:
 - 1. Materials: Use factory pre-printed or machine-printed self-adhesive polyester or self-adhesive vinyl labels; UV, chemical, water, heat, and abrasion resistant; produced using materials recognized to UL 969.
 - 2. Machine-Printed Labels: Use thermal transfer process printing machines and accessories recommended by label manufacturer.
 - 3. Minimum Size: 2 by 4 inches unless otherwise indicated.

PART 3 EXECUTION

3.01 PREPARATION

- A. Clean surfaces to receive adhesive products according to manufacturer's instructions.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install identification products to be plainly visible for examination, adjustment, servicing, and maintenance. Unless otherwise indicated, locate products as follows:
 - 1. Surface-Mounted Equipment: Enclosure front.
 - 2. Flush-Mounted Equipment: Inside of equipment door.
 - 3. Free-Standing Equipment: Enclosure front; also enclosure rear for equipment with rear access.
 - 4. Elevated Equipment: Legible from the floor or working platform.
 - 5. Branch Devices: Adjacent to device.
 - 6. Interior Components: Legible from the point of access.
 - 7. Conductors and Cables: Legible from the point of access.
- C. Install identification products centered, level, and parallel with lines of item being identified.
- D. Install self-adhesive labels and markers to achieve maximum adhesion, with no bubbles or wrinkles and edges properly sealed.
- E. For conduits installed in trenches, install underground warning tape above buried lines with one tape per trench at 3 inches below finished grade.

END OF SECTION

SECTION 26 2416
PANELBOARDS

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Power distribution panelboards.
- B. Lighting and appliance panelboards.
- C. Overcurrent protective devices for panelboards.

1.02 RELATED REQUIREMENTS

- A. Section 26 0526 - Grounding and Bonding for Electrical Systems.
- B. Section 26 0553 - Identification for Electrical Systems: Identification products and requirements.

1.03 REFERENCE STANDARDS

- A. FS W-C-375 - Circuit Breakers, Molded Case; Branch Circuit and Service; Federal Specification; Revision E, 2013.
- B. NECA 1 - Standard for Good Workmanship in Electrical Construction; National Electrical Contractors Association; 2010.
- C. NECA 407 - Standard for Installing and Maintaining Panelboards; National Electrical Contractors Association; 2009.
- D. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.
- E. NEMA PB 1 - Panelboards; National Electrical Manufacturers Association; 2011.
- F. NEMA PB 1.1 - General Instructions for Proper Installation, Operation and Maintenance of Panelboards Rated 600 Volts or Less; National Electrical Manufacturers Association; 2013 (ANSI/NEMA PB 1.1).
- G. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- H. UL 50 - Enclosures for Electrical Equipment, Non-Environmental Considerations; Current Edition, Including All Revisions.
- I. UL 50E - Enclosures for Electrical Equipment, Environmental Considerations; Current Edition, Including All Revisions.
- J. UL 67 - Panelboards; Current Edition, Including All Revisions.
- K. UL 489 - Molded-Case Circuit Breakers, Molded-Case Switches and Circuit Breaker Enclosures; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for panelboards, enclosures, overcurrent protective devices, and other installed components and accessories.
- C. Shop Drawings: Indicate outline and support point dimensions, voltage, main bus ampacity, overcurrent protective device arrangement and sizes, short circuit current ratings, conduit entry locations, conductor terminal information, and installed features and accessories.
- D. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
- E. Project Record Documents: Record actual installed locations of panelboards and actual installed circuiting arrangements.

- F. Maintenance Data: Include information on replacement parts and recommended maintenance procedures and intervals.
- G. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 01 6000 - Product Requirements, for additional provisions.
 - 2. Panelboard Keys: Two of each different key.

1.05 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store panelboards in accordance with manufacturer's instructions and NECA 407.
- B. Store in a clean, dry space. Maintain factory wrapping or provide an additional heavy canvas or heavy plastic cover to protect units from dirt, water, construction debris, and traffic.
- C. Handle carefully in accordance with manufacturer's written instructions to avoid damage to panelboard internal components, enclosure, and finish.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Siemens Industry, Inc: www.usa.siemens.com.
- B. Eaton Corporation: www.eaton.com.
- C. General Electric Company: www.geindustrial.com.
- D. Schneider Electric; Square D Products: www.schneider-electric.us.
- E. Substitutions: See Section 01 6000 - Product Requirements.
- F. Source Limitations: Furnish panelboards and associated components produced by the same manufacturer as the other electrical distribution equipment used for this project and obtained from a single supplier.

2.02 PANELBOARDS - GENERAL REQUIREMENTS

- A. Provide products listed, classified, and labeled as suitable for the purpose intended.
- B. Short Circuit Current Rating: 10,000 amps rms symmetrical minimum unless otherwise indicated.
- C. Mains: Configure for top or bottom incoming feed as indicated or as required for the installation.
- D. Branch Overcurrent Protective Devices: Replaceable without disturbing adjacent devices.
- E. Bussing: Sized in accordance with UL 67 temperature rise requirements.
 - 1. Provide solidly bonded equipment ground bus in each panelboard, with a suitable lug for each feeder and branch circuit equipment grounding conductor.
- F. Conductor Terminations: Suitable for use with the conductors to be installed.
- G. Enclosures: Comply with NEMA 250, and list and label as complying with UL 50 and UL 50E.
 - 1. Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
 - a. Indoor Clean, Dry Locations: Type 1.
 - b. Outdoor Locations: Type 4X, stainless steel.
 - 2. Boxes: Galvanized steel unless otherwise indicated.
 - a. Provide wiring gutters sized to accommodate the conductors to be installed.
 - 3. Fronts:
 - a. Fronts for Surface-Mounted Enclosures: Same dimensions as boxes.
 - b. Fronts for Flush-Mounted Enclosures: Overlap boxes on all sides to conceal rough opening.
 - c. Finish for Painted Steel Fronts: Manufacturer's standard grey unless otherwise indicated.

4. Lockable Doors: All locks keyed alike unless otherwise indicated.
- H. Future Provisions: Prepare all unused spaces for future installation of devices including bussing, connectors, mounting hardware and all other required provisions.

2.03 POWER DISTRIBUTION PANELBOARDS

- A. Description: Panelboards complying with NEMA PB 1, power and feeder distribution type, circuit breaker type, and listed and labeled as complying with UL 67; ratings, configurations and features as indicated on the drawings.
- B. Conductor Terminations:
 1. Main and Neutral Lug Material: Copper, suitable for terminating copper conductors only.
 2. Main and Neutral Lug Type: Mechanical.
- C. Bussing:
 1. Phase and Neutral Bus Material: Copper.
 2. Ground Bus Material: Copper.
- D. Circuit Breakers:
 1. Provide bolt-on type compatible with existing breakers.
 2. Provide thermal magnetic circuit breakers for circuit breaker frame sizes less than 400 amperes.
- E. Enclosures:
 1. Provide surface-mounted enclosures unless otherwise indicated.
- F. Description: NEMA PB 1, circuit breaker type.
- G. Panelboard Bus: Copper, ratings as indicated. Provide copper ground bus in each panelboard.
- H. Molded Case Circuit Breakers: With integral thermal and instantaneous magnetic trip in each pole; UL listed. For air conditioning equipment branch circuits provide circuit breakers UL listed as Type HACR.

2.04 LIGHTING AND APPLIANCE PANELBOARDS

- A. Description: Panelboards complying with NEMA PB 1, lighting and appliance branch circuit type, circuit breaker type, and listed and labeled as complying with UL 67; ratings, configurations and features as indicated on the drawings.
- B. Conductor Terminations:
 1. Main and Neutral Lug Material: Copper, suitable for terminating copper conductors only.
 2. Main and Neutral Lug Type: Mechanical.
- C. Bussing:
 1. Phase Bus Connections: Arranged for sequential phasing of overcurrent protective devices.
 2. Phase and Neutral Bus Material: Copper.
 3. Ground Bus Material: Copper.
- D. Circuit Breakers: Thermal magnetic bolt-on type unless otherwise indicated.
 1. Class A Ground Fault Interrupter protected thermal magnetic bolt-on type where circuits are identified with 'GF' on the panelboard schedule.
- E. Enclosures:
 1. Provide surface-mounted or flush-mounted enclosures as indicated.
 2. Provide clear plastic circuit directory holder mounted on inside of door.

2.05 OVERCURRENT PROTECTIVE DEVICES

- A. Molded Case Circuit Breakers:
 1. Description: Quick-make, quick-break, over center toggle, trip-free, trip-indicating circuit breakers listed and labeled as complying with UL 489, and complying with FS W-C-375 where applicable; ratings, configurations, and features as indicated on the drawings.
 2. Interrupting Capacity:

- a. Provide circuit breakers with interrupting capacity as required to provide the short circuit current rating indicated, but not less than:
 - 1) 10,000 rms symmetrical amperes at 240 VAC or 208 VAC.
- b. Fully Rated Systems: Provide circuit breakers with interrupting capacity not less than the short circuit current rating indicated.
- 3. Conductor Terminations:
 - a. Lug Material: Copper, suitable for terminating copper conductors only.
- 4. Thermal Magnetic Circuit Breakers: For each pole, furnish thermal inverse time tripping element for overload protection and magnetic instantaneous tripping element for short circuit protection.
 - a. Provide field-adjustable magnetic instantaneous trip setting for circuit breaker frame sizes 200 amperes and larger.
- 5. Electronic Trip Circuit Breakers: Furnish solid state, microprocessor-based, true rms sensing trip units.
 - a. Provide the following field-adjustable trip response settings:
 - 1) Long time pickup, adjustable by setting dial.
 - 2) Long time delay.
 - 3) Short time pickup and delay.
 - 4) Instantaneous pickup.
- 6. Multi-Pole Circuit Breakers: Furnish with common trip for all poles.
- 7. Do not use tandem circuit breakers.
- 8. Do not use handle ties in lieu of multi-pole circuit breakers.
- 9. Provide multi-pole circuit breakers for multi-wire branch circuits as required by NFPA 70.

2.06 SOURCE QUALITY CONTROL

- A. Factory test panelboards according to NEMA PB 1.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on the drawings.
- B. Verify that the ratings and configurations of the panelboards and associated components are consistent with the indicated requirements.
- C. Verify that mounting surfaces are ready to receive panelboards.
- D. Verify that conditions are satisfactory for installation prior to starting work.
- E. Verify that panel is suitable for installation of existing circuit breakers.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install panelboards securely, in a neat and workmanlike manner in accordance with NECA 1 (general workmanship), NECA 407 (panelboards), and NEMA PB 1.1.
- C. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.
- D. Provide required supports in accordance with Section 26 0529.
- E. Install panelboards plumb.
- F. Install flush-mounted panelboards so that trims fit completely flush to wall with no gaps and rough opening completely covered.
- G. Mount panelboards such that the highest position of any operating handle for circuit breakers or switches does not exceed 79 inches above the floor or working platform.
- H. Provide grounding and bonding in accordance with Section 26 0526.
- I. Install all field-installed branch devices, components, and accessories.
- J. Install panelboards in accordance with NEMA PB 1.1 and NECA 1.

- K. Install panelboards plumb. Install recessed panelboards flush with wall finishes.
- L. Provide filler plates to cover unused spaces in panelboards.
- M. Ground and bond panelboard enclosure according to Section 26 0526.

3.03 FIELD QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for additional requirements.
- B. Perform inspection, testing, and adjusting in accordance with Section 01 4000.
- C. Perform field inspection and testing in accordance with Section 01 4000
- D. Correct deficiencies and replace damaged or defective panelboards or associated components.

3.04 ADJUSTING

- A. Adjust tightness of mechanical and electrical connections to manufacturer's recommended torque settings.
- B. Adjust alignment of panelboard fronts.

3.05 CLEANING

- A. Clean dirt and debris from panelboard enclosures and components according to manufacturer's instructions.
- B. Repair scratched or marred exterior surfaces to match original factory finish.

END OF SECTION

SECTION 26 2717
EQUIPMENT WIRING

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Electrical connections to equipment.

1.02 RELATED REQUIREMENTS

- A. Section 26 0534 - Conduit.
- B. Section 26 0537 - Boxes.
- C. Section 26 2726 - Wiring Devices.

1.03 REFERENCE STANDARDS

- A. NEMA WD 1 - General Color Requirements for Wiring Devices; National Electrical Manufacturers Association; 1999 (R 2010).
- B. NEMA WD 6 - Wiring Devices - Dimensional Requirements; National Electrical Manufacturers Association; 2012.
- C. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Obtain and review shop drawings, product data, manufacturer's wiring diagrams, and manufacturer's instructions for equipment furnished under other sections.
 - 2. Determine connection locations and requirements.
- B. Sequencing:
 - 1. Install rough-in of electrical connections before installation of equipment is required.
 - 2. Make electrical connections before required start-up of equipment.

1.05 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide wiring device manufacturer's catalog information showing dimensions, configurations, and construction.
- C. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

1.06 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.
- B. Products: Listed, classified, and labeled as suitable for the purpose intended.

1.07 COORDINATION

- A. Obtain and review shop drawings, product data, manufacturer's wiring diagrams, and manufacturer's instructions for equipment furnished under other sections.
- B. Determine connection locations and requirements.
- C. Sequence rough-in of electrical connections to coordinate with installation of equipment.
- D. Sequence electrical connections to coordinate with start-up of equipment.

PART 2 PRODUCTS**2.01 MATERIALS**

- A. Cords and Caps: NEMA WD 6; match receptacle configuration at outlet provided for equipment.

1. Colors: Conform to NEMA WD 1.
 2. Cord Construction: NFPA 70, Type SO, multiconductor flexible cord with identified equipment grounding conductor, suitable for use in damp locations.
 3. Size: Suitable for connected load of equipment, length of cord, and rating of branch circuit overcurrent protection.
- B. Wiring Devices: As specified in Section 26 2726.
- C. Boxes: As specified in Section 26 0537.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that equipment is ready for electrical connection, wiring, and energization.

3.02 ELECTRICAL CONNECTIONS

- A. Make electrical connections in accordance with equipment manufacturer's instructions.
- B. Make conduit connections to equipment using flexible conduit. Use liquidtight flexible conduit with watertight connectors in damp or wet locations.
- C. Connect heat producing equipment using wire and cable with insulation suitable for temperatures encountered.
- D. Provide receptacle outlet to accommodate connection with attachment plug.
- E. Provide cord and cap where field-supplied attachment plug is required.
- F. Install suitable strain-relief clamps and fittings for cord connections at outlet boxes and equipment connection boxes.
- G. Install disconnect switches, controllers, control stations, and control devices to complete equipment wiring requirements.
- H. Install terminal block jumpers to complete equipment wiring requirements.
- I. Install interconnecting conduit and wiring between devices and equipment to complete equipment wiring requirements.

END OF SECTION

**SECTION 26 2726
WIRING DEVICES****PART 1 GENERAL****1.01 SECTION INCLUDES**

- A. Wall switches.
- B. Receptacles.
- C. Wall Plates.

1.02 RELATED REQUIREMENTS

- A. Section 23 3423 - Power Ventilators: Motor Starters and Disconnects
- B. Section 26 0526 - Grounding and Bonding.
- C. Section 26 0535 - Surface Raceways:
- D. Section 26 0537 - Boxes.
- E. Section 26 0537 - Boxes.
- F. Section 26 0553 - Identification for Electrical Systems: Identification products and requirements.
- G. Section 26 0923 - Lighting Control Devices: Devices for automatic control of lighting, including occupancy sensors, in-wall time switches, and in-wall interval timers.
- H. Section 26 2717 - Equipment Wiring: Cords and plugs for equipment.

1.03 REFERENCE STANDARDS

- A. FS W-C-596 - Connector, Electrical, Power, General Specification for; Federal Specification; Revision G, 2001.
- B. FS W-S-896 - Switches, Toggle (Toggle and Lock), Flush-mounted (General Specification); Federal Specification; Revision F, 1999.
- C. NECA 1 - Standard for Good Workmanship in Electrical Construction; National Electrical Contractors Association; 2010.
- D. NEMA WD 1 - General Color Requirements for Wiring Devices; National Electrical Manufacturers Association; 1999 (R 2010).
- E. NEMA WD 6 - Wiring Device -- Dimensional Specifications; National Electrical Manufacturers Association; 2012.
- F. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. UL 20 - General-Use Snap Switches; Current Edition, Including All Revisions.
- H. UL 498 - Attachment Plugs and Receptacles; Current Edition, Including All Revisions.
- I. UL 514D - Cover Plates for Flush-Mounted Wiring Devices; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's catalog information showing dimensions, colors, and configurations.
- C. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Hubbell Incorporated: www.hubbell-wiring.com.
- B. Leviton Manufacturing Company, Inc: www.leviton.com.
- C. Pass & Seymour, a brand of Legrand North America, Inc: www.legrand.us
- D. Cooper Wiring Devices: www.cooperwiringdevices.com.
- E. GE Industrial: www.geindustrial.com.
- F. Leviton Manufacturing, Inc: www.leviton.com.
- G. Substitutions: See Section 01 6000 - Product Requirements.

2.02 ALL WIRING DEVICES

- A. Provide products listed and classified by Underwriters Laboratories Inc. as suitable for the purpose specified and indicated.

2.03 WALL SWITCHES

- A. Wall Switches - General Requirements: AC only, quiet operating, general-use snap switches with silver alloy contacts, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 20 and where applicable, FS W-S-896; types as indicated on the drawings.
 - 1. Wiring Provisions: Terminal screws for side wiring and screw actuated binding clamp for back wiring with separate ground terminal screw.
- B. Standard Wall Switches: Industrial specification grade, 20 A, 120/277 V with standard toggle type switch actuator and maintained contacts; single pole single throw, three way, or four way as indicated on the drawings.

2.04 RECEPTACLES

- A. Receptacles - General Requirements: Self-grounding, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 498, and where applicable, FS W-C-596; types as indicated on the drawings.
 - 1. Wiring Provisions: Terminal screws for side wiring or screw actuated binding clamp for back wiring with separate ground terminal screw.
 - 2. NEMA configurations specified are according to NEMA WD 6.
- B. Convenience Receptacles:
 - 1. Standard Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R; single or duplex as indicated on the drawings.
 - 2. Weather Resistant Convenience Receptacles: Industrial specification grade, 20A, 125V, NEMA 5-20R, listed and labeled as weather resistant type complying with UL 498 Supplement SE suitable for installation in damp or wet locations; single or duplex as indicated on the drawings.
- C. Locking Receptacles: Industrial specification grade, configuration as indicated on the drawings.

2.05 WALL PLATES

- A. Wall Plates: Comply with UL 514D.
 - 1. Configuration: One piece cover as required for quantity and types of corresponding wiring devices.
 - 2. Size: Standard; .
 - 3. Screws: Metal with slotted heads finished to match wall plate finish.
- B. Stainless Steel Wall Plates: Brushed satin finish, Type 302 stainless steel.
- C. General Purpose Weatherproof Covers for Wet Locations and all locations within the Reclamation Building: Gasketed, thermoplastic, with hinged lockable cover and corrosion-resistant screws; listed as suitable for use in wet locations while in use with attachment plugs connected.

- D. Special Purpose Weatherproof Covers for Wet Locations: Gasketed, cast aluminum, with spring-loaded, hinged cover and corrosion-resistant screws; listed as suitable for use in wet locations while in use with attachment plugs connected.
- E. Switch Covers for Wet Locations: Gasketed, thermoplastic, with non-metallic toggle switch for use in exposed applications. Corrosion resistant and non-conductive. Entirely enclosed, for use with standard wall switch. Similar and equal to Carlon E98TSN-CAR.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on the drawings.
- B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate devices and conductors in accordance with NFPA 70.
- C. Verify that wall openings are neatly cut and will be completely covered by wall plates.
- D. Verify that final surface finishes are complete, including painting.
- E. Verify that branch circuit wiring installation is completed, tested, and ready for connection to wiring devices.
- F. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Perform work in a neat and workmanlike manner in accordance with NECA 1 and, where applicable, NECA 130, including mounting heights specified in those standards unless otherwise indicated.
- B. Coordinate locations of outlet boxes provided under Section 26 0537 as required for installation of wiring devices provided under this section.
- C. Install wiring devices in accordance with manufacturer's instructions.
- D. Where required, connect wiring devices using pigtails not less than 6 inches long. Do not connect more than one conductor to wiring device terminals.
- E. Connect wiring devices by wrapping conductor clockwise 3/4 turn around screw terminal and tightening to proper torque specified by the manufacturer. Where present, do not use push-in pressure terminals that do not rely on screw-actuated binding.
- F. Unless otherwise indicated, connect wiring device grounding terminal to branch circuit equipment grounding conductor and to outlet box with bonding jumper.
- G. Install wiring devices plumb and level with mounting yoke held rigidly in place.
- H. Install wall switches with OFF position down.
- I. Install vertically mounted receptacles with grounding pole on bottom and horizontally mounted receptacles with grounding pole on left.
- J. Install interior, non-weatherproof wall plates to fit completely flush to wall with no gaps and rough opening completely covered without strain on wall plate. Repair or reinstall improperly installed outlet boxes or improperly sized rough openings. Do not use oversized wall plates in lieu of meeting this requirement.
- K. Install blank wall plates on junction boxes and on outlet boxes with no wiring devices installed or designated for future use.

3.03 ADJUSTING

- A. Adjust devices and wall plates to be flush and level.

3.04 CLEANING

- A. Clean exposed surfaces to remove dirt, paint, or other foreign material and restore to match original factory finish.

END OF SECTION

SECTION 26 5100
INTERIOR LIGHTING

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Interior luminaires.
- B. Exit signs.
- C. Ballasts and drivers.
- D. Lamps.

1.02 REFERENCE STANDARDS

- A. IES LM-79 - Approved Method: Electrical and Photometric Measurements of Solid-State Lighting Products; Illuminating Engineering Society; 2008.
- B. IES LM-80 - Approved Method: Measuring Lumen Maintenance of LED Light Sources; Illuminating Engineering Society; 2008.
- C. NECA 1 - Standard for Good Workmanship in Electrical Construction; National Electrical Contractors Association; 2010.
- D. NECA/IESNA 500 - Standard for Installing Indoor Commercial Lighting Systems; National Electrical Contractors Association; 2006.
- E. NECA/IESNA 502 - Standard for Installing Industrial Lighting Systems; National Electrical Contractors Association; 2006.
- F. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. UL 924 - Emergency Lighting and Power Equipment; Current Edition, Including All Revisions.
- H. UL 1598 - Luminaires; Current Edition, Including All Revisions.
- I. UL 8750 - Light Emitting Diode (LED) Equipment for Use in Lighting Products; Current Edition, Including All Revisions.

1.03 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate the installation of luminaires with mounting surfaces installed under other sections or by others. Coordinate the work with placement of supports, anchors, etc. required for mounting. Coordinate compatibility of luminaires and associated trims with mounting surfaces at installed locations.
 - 2. Coordinate the placement of luminaires with structural members, ductwork, piping, equipment, diffusers, fire suppression system components, and other potential conflicts installed under other sections or by others.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, installed accessories, and ceiling compatibility; include model number nomenclature clearly marked with all proposed features.
 - 1. LED Luminaires:
 - a. Include estimated useful life, calculated based on IES LM-80 test data.
 - 2. Provide electronic files of photometric data certified by a National Voluntary Laboratory Accreditation Program (NVLAP) lab or independent testing agency in IESNA LM-63 standard format upon request.
 - 3. Ballasts: Include wiring diagrams and list of compatible lamp configurations.

4. Lamps: Include rated life, color temperature, color rendering index (CRI), and initial and mean lumen output.
- C. Operation and Maintenance Data: Instructions for each product including information on replacement parts.

1.05 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.
- B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

1.06 DELIVERY, STORAGE, AND PROTECTION

- A. Receive, handle, and store products according to NECA/IESNA 500 (commercial lighting), NECA/IESNA 502 (industrial lighting), and manufacturer's written instructions.
- B. Keep products in original manufacturer's packaging and protect from damage until ready for installation.

1.07 FIELD CONDITIONS

- A. Maintain field conditions within manufacturer's required service conditions during and after installation.

1.08 WARRANTY

- A. See Section 01 7800 - Closeout Submittals, for additional warranty requirements.

PART 2 PRODUCTS

2.01 LUMINAIRE TYPES

- A. Furnish products as indicated in luminaire schedule attached to this section.
- B. Substitutions: See Section 01 6000 - Product Requirements.

2.02 LUMINAIRES

- A. Provide products that comply with requirements of NFPA 70.
- B. Provide products that are listed and labeled as complying with UL 1598, where applicable.
- C. Provide products listed, classified, and labeled as suitable for the purpose intended.
- D. Unless otherwise indicated, provide complete luminaires including lamp(s) and all sockets, ballasts, reflectors, lenses, housings and other components required to position, energize and protect the lamp and distribute the light.
- E. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, hardware, supports, trims, accessories, etc. as necessary for a complete operating system.
- F. Provide products suitable to withstand normal handling, installation, and service without any damage, distortion, corrosion, fading, discoloring, etc.
- G. LED Luminaires:
 1. Components: UL 8750 recognized or listed as applicable.
 2. Tested in accordance with IES LM-79 and IES LM-80.
 3. LED Estimated Useful Life: Minimum of 50,000 hours at 70 percent lumen maintenance, calculated based on IES LM-80 test data.

2.03 EXIT SIGNS

- A. Description: Exit signs and similar signs for special purpose applications such as area of refuge/rescue assistance.
- B. Description: Internally illuminated exit signs with LEDs unless otherwise indicated; complying with NFPA 101 and all applicable state and local codes, and listed and labeled as complying with UL 924.
 1. Number of Faces: Single or double as indicated or as required for the installed location.
 2. Directional Arrows: As indicated or as required for the installed location.

- C. Self-Powered Exit Signs:
 - 1. Operation: Upon interruption of normal power source or brownout condition exceeding 20 percent voltage drop from nominal, solid-state control automatically switches connected lamps to integral battery power for minimum of 90 minutes of rated emergency illumination, and automatically recharges battery upon restoration of normal power source.
 - 2. Battery: Sealed maintenance-free nickel cadmium unless otherwise indicated.
 - 3. Diagnostics: Provide power status indicator light and accessible integral test switch to manually activate emergency operation.
 - 4. Provide low-voltage disconnect to prevent battery damage from deep discharge.
 - 5. Self-Diagnostics: Provide units that self-monitor functionality and automatically perform testing required by NFPA 101 where indicated; provide indicator light(s) to report test and diagnostic status.

2.04 BALLASTS AND DRIVERS

- A. Dimmable LED Drivers:
 - 1. Dimming Range: Continuous dimming from 100 percent to five percent relative light output unless dimming capability to lower level is indicated, without flicker.
 - 2. Control Compatibility: Fully compatible with the dimming controls to be installed.
 - 3. Product(s):
 - a. Lutron Hi-Lume A-Series (LTE-Series): Forward phase (neutral wire required); one percent dimming.

2.05 LAMPS

- A. Lamps - General Requirements:
 - 1. Unless explicitly excluded, provide new, compatible, operable lamps in each luminaire.
 - 2. Verify compatibility of specified lamps with luminaires to be installed. Where lamps are not specified, provide lamps per luminaire manufacturer's recommendations.
 - 3. Minimum Efficiency: Provide lamps complying with all current applicable federal and state lamp efficiency standards.
 - 4. Color Temperature Consistency: Unless otherwise indicated, for each type of lamp furnish products which are consistent in perceived color temperature. Replace lamps that are determined by the Architect to be inconsistent in perceived color temperature.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on the drawings.
- B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate conductors in accordance with NFPA 70.
- C. Verify that suitable support frames are installed where required.
- D. Verify that branch circuit wiring installation is completed, tested, and ready for connection to luminaires.
- E. Verify that conditions are satisfactory for installation prior to starting work.

3.02 PREPARATION

- A. Provide extension rings to bring outlet boxes flush with finished surface.
- B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

3.03 INSTALLATION

- A. Coordinate locations of outlet boxes provided under Section 26 0537 as required for installation of luminaires provided under this section.
- B. Install products according to manufacturer's instructions.
- C. Install luminaires securely, in a neat and workmanlike manner, as specified in NECA 1 (general workmanship), NECA 500 (commercial lighting), and NECA 502 (industrial lighting).
- D. Install luminaires plumb and square and aligned with building lines and with adjacent luminaires.

- E. Suspended Luminaires:
 1. Install using suspension method indicated, with support lengths and accessories as required for specified mounting height
 2. Provide minimum of two supports for each luminaire equal to or exceeding 4 feet in length, with no more than 4 feet between supports.
 3. Secure pendant-mounted luminaires to building structure.
- F. Install accessories furnished with each luminaire.
- G. Bond products and metal accessories to branch circuit equipment grounding conductor.
- H. Exit Signs:
 1. Unless otherwise indicated, connect unit to unswitched power from same circuit feeding normal lighting in same room or area. Bypass local switches, contactors, or other lighting controls.
- I. Install lamps in each luminaire.

3.04 FIELD QUALITY CONTROL

- A. Inspect each product for damage and defects.
- B. Operate each luminaire after installation and connection to verify proper operation.
- C. Test self-powered exit signs, emergency lighting units, and fluorescent emergency power supply units to verify proper operation upon loss of normal power supply.
- D. Correct wiring deficiencies and repair or replace damaged or defective products. Repair or replace excessively noisy ballasts as determined by Architect.

3.05 ADJUSTING

- A. Aim and position adjustable luminaires to achieve desired illumination as indicated or as directed by Architect. Secure locking fittings in place.
- B. Exit Signs with Field-Selectable Directional Arrows: Set as indicated or as required to properly designate egress path as directed by Architect or authority having jurisdiction.

3.06 CLEANING

- A. Clean surfaces according to NECA 500 (commercial lighting), NECA 502 (industrial lighting), and manufacturer's instructions to remove dirt, fingerprints, paint, or other foreign material and restore finishes to match original factory finish.

3.07 CLOSEOUT ACTIVITIES

- A. Demonstration: Demonstrate proper operation of luminaires to Architect, and correct deficiencies or make adjustments as directed.
- B. Just prior to Substantial Completion, replace all lamps that have failed .

3.08 PROTECTION

- A. Protect installed luminaires from subsequent construction operations.

3.09 ATTACHMENTS

- A. Luminaire schedule.

3.10 SCHEDULE

- A. Type F-3 LED Thermoplastic Fixture (Brine Building:
 1. Manufacturer: RAZZ Rig-A-Lite, FPF14L-8-U-SS (Basis of Design)
 2. Size: 100"L x 6.75" Dia.
 3. Water Proof: High Pressure Hose Down Rated
 4. Mounting: Pendant
 5. Driver: Electronic
 6. Lamp: 4000K, 4000 LM
 7. Other Manufacturers: Precision Paragone SNL Series
- B. Type X-2 LEF Red Exit Sign for wet areas (Egress Doors in Brine Building)

1. Manufacturer: Dual-Lite LN4XRW (Basis of Design)Lithonia LQM P W 1 R 120/277
2. Description: Construct of High-Impact Resistant, glass-filled polycarbonate with a clear polycarbonated cover sealed by an oil-resistant gasket for water and dust-tight seal. NEMA 4X Rated. Snap in directional chevrons. Conforms to UL 924/NFPA 70/NFPA 101 Standards
3. Size: 12 3/8"H x 16 5/8"W x 5 1/4"D
4. Lamp: RED LEDS
5. Other Manufacturers: Light Alarms XV Series; Emergi-Lite SVX Series; Evenlite NEX Series; Lithonia LV Series

END OF SECTION

SECTION 26 5600
EXTERIOR LIGHTING

PART 1 GENERAL**1.01 SECTION INCLUDES**

- A. Exterior luminaires.

1.02 RELATED REQUIREMENTS

- A. Section 26 0526 - Grounding and Bonding for Electrical Systems.
- B. Section 26 0537 - Boxes.
- C. Section 26 2726 - Wiring Devices 26 2726
- D. Section 26 5100 - Interior Lighting.

1.03 REFERENCE STANDARDS

- A. ANSI C82.1 - American National Standard for Lamp Ballast - Line Frequency Fluorescent Lamp Ballast; 2004.
- B. ANSI C82.4 - American National Standard for Ballasts for High-Intensity-Discharge and Low Pressure Sodium Lamps (Multiple-Supply Type); 2002.
- C. ANSI O5.1 - American National Standard for Wood Poles -- Specifications and Dimensions; 2008.
- D. IES LM-79 - Approved Method: Electrical and Photometric Measurements of Solid-State Lighting Products; Illuminating Engineering Society; 2008.
- E. IES LM-80 - Approved Method: Measuring Lumen Maintenance of LED Light Sources; Illuminating Engineering Society; 2008.
- F. NECA 1 - Standard for Good Workmanship in Electrical Construction; National Electrical Contractors Association; 2010.
- G. NECA/IESNA 501 - Recommended Practice for Installing Exterior Lighting Systems; National Electrical Contractors Association; 2006.
- H. NFPA 70 - National Electrical Code; National Fire Protection Association; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- I. UL 8750 - Light Emitting Diode (LED) Equipment for Use in Lighting Products; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate dimensions and components for each luminaire that is not a standard product of the manufacturer.
- C. Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, weight, effective projected area (EPA), and installed accessories; include model number nomenclature clearly marked with all proposed features.
 - 1. LED Luminaires:
 - a. Include estimated useful life, calculated based on IES LM-80 test data.
 - 2. Lamps: Include rated life and initial and mean lumen output.
- D. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, installation, and starting of product.

1.05 QUALITY ASSURANCE

- A. Conform to requirements of NFPA 70.

- B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- C. Electrical Components: Listed and classified by Underwriters Laboratories Inc. as suitable for the purpose specified and indicated.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Receive, handle, and store products according to NECA/IESNA 501 and manufacturer's written instructions.
- B. Keep products in original manufacturer's packaging and protect from damage until ready for installation.

1.07 WARRANTY

- A. See Section 01 7800 - Closeout Submittals, for additional warranty requirements.
- B. Provide three year manufacturer warranty for all LED luminaires, including drivers.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Lithonia: www.lithonia.com
- B. Substitutions: See Section 01 6000 - Product Requirements.

2.02 LUMINAIRE TYPES

- A. Furnish products as indicated in luminaire schedule included on the drawings.
- B. Substitutions: See Section 01 6000 - Product Requirements.

2.03 LUMINAIRES

- A. Provide products that comply with requirements of NFPA 70.
- B. Provide products that are listed and labeled as complying with UL 1598, where applicable.
- C. Provide products listed, classified, and labeled as suitable for the purpose intended.
- D. Unless otherwise indicated, provide complete luminaires including lamp(s) and all sockets, ballasts, reflectors, lenses, housings and other components required to position, energize and protect the lamp and distribute the light.
- E. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, hardware, poles, foundations, supports, trims, accessories, etc. as necessary for a complete operating system.
- F. Provide products suitable to withstand normal handling, installation, and service without any damage, distortion, corrosion, fading, discoloring, etc.
- G. LED Luminaires:
 - 1. Components: UL 8750 recognized or listed as applicable.
 - 2. Tested in accordance with IES LM-79 and IES LM-80.
 - 3. LED Estimated Useful Life: Minimum of 50,000 hours at 70 percent lumen maintenance, calculated based on IES LM-80 test data.
- H. Luminaire :
 - 1. Product Description: Complete exterior luminaire assemblies, with features, options, and accessories as scheduled.
 - 2. Substitutions: See Section 01 6000 - Product Requirements.

2.04 BALLASTS

- A. All Ballasts:
 - 1. Provide ballasts containing no polychlorinated biphenyls (PCBs).
 - 2. Minimum Efficiency/Efficacy: Provide ballasts complying with all current applicable federal and state ballast efficiency/efficacy standards.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Coordinate locations of outlet boxes provided under Section 26 0537 as required for installation of luminaires provided under this section.
- B. Install products according to manufacturer's instructions.
- C. Install luminaires securely, in a neat and workmanlike manner, as specified in NECA 1 (general workmanship) and NECA/IESNA 501 (exterior lighting).
- D. Install luminaires plumb and square and aligned with building lines and with adjacent luminaires.
- E. Wall-Mounted Luminaires: Unless otherwise indicated, specified mounting heights are to center of luminaire.
- F. Install accessories furnished with each luminaire.
- G. Bond products and metal accessories to branch circuit equipment grounding conductor.
- H. Provide concrete bases for lighting poles at locations indicated, in accordance with Section 03 3000.
- I. Install lamps in each luminaire.
- J. Bond luminaires, metal accessories, and metal poles to branch circuit equipment grounding conductor. Provide supplementary grounding electrode at each pole.

3.02 FIELD QUALITY CONTROL

- A. Inspect each product for damage and defects.
- B. Operate each luminaire after installation and connection to verify proper operation.

3.03 ADJUSTING

- A. Aim and position adjustable luminaires to achieve desired illumination as indicated or as directed by Architect. Secure locking fittings in place.
- B. Aim and adjust luminaires to provide illumination levels and distribution indicated on Drawings.

3.04 CLEANING

- A. Clean photometric control surfaces as recommended by manufacturer.
- B. Clean finishes and touch up damage.

3.05 SCHEDULE

- A. Type F-7 LED Exterior Wall Mounted Fixture
 1. Manufacturer: Lithonia, WST LED-2-10A700/40K-SR2-MVOLT-PE-DBLXD (Basis of Design)
 2. Size: 9 1/8"W x 14 1/4"L x 11 3/8"D
 3. Housing: die-cast aluminum housing and hinged, gasketed door frame with clear, tempered glass lens and full, cut-off anodized aluminum reflector. Housing finished with electrostatically applied and baked black polyester powder coat. Integral button type photocell 100,000 hr projected L70. 5 year manufacturer warranty
 4. Driver: Electronic
 5. Lamp: 4000K, 4000 LM
 6. Other Manufacturers: Philips Gardco 101 Series; Spaulding TRP Series

END OF SECTION

SECTION 31 2316.13**TRENCHING****PART 1 GENERAL****1.01 SECTION INCLUDES**

- A. Trenching and backfilling and compacting utilities.
- B. Conduit and pipe installation.

1.02 REFERENCES

- A. AASHTO T 180 - Standard Specification for Moisture-Density Relations of Soils Using a 4.54 kg (10-lb) Rammer and a 457 mm (18 in.) Drop; American Association of State Highway and Transportation Officials; 2010
- B. ASTM D698 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³)); 2012.
- C. ASTM D1557 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN m/m³)); 2012.

1.03 SUBMITTALS

- A. Compaction Density Test Reports.
- B. Submittals at Project Closeout:
 - 1. Maintain documents at site during construction and submit at Contract Closeout.
 - 2. Record/verify locations of all located utilities and record depths of exposed utilities.
 - 3. Record location and depth of all borings and transcribe on record drawings.

PART 2 PRODUCTS**2.01 FILL MATERIALS**

- A. General Fill: Subsoil excavated on-site. All materials not classified as rock or rubble including loam, silt, gumbo, peat, clay, soft shale, sand, gravel, and fragmentary rock or boulders which can be handled by normal earth moving equipment.
 - 1. Graded.
 - 2. Free of lumps larger than 3 inches, rocks larger than 2 inches, and debris.
- B. Concrete for Fill: As specified in Section 03 3000; compressive strength of 3000 psi.
- C. Sand: Natural river or bank sand; washed; free of silt, clay, loam, friable or soluble materials, and organic matter.
- D. Topsoil: Topsoil excavated on-site. Organic well draining soil free from clay lumps, rocks, stones, concrete, toxic minerals, roots over 1/4" in diameter or other material which will not provide good turf growth.

2.02 ACCESSORIES

- A. Geotextile Fabric: Non-biodegradable, woven, conforming to Iowa DOT 4196.

PART 3 EXECUTION**3.01 INSTALLATION**

- A. Prepare trenches and bore-pits to accommodate minimum conduit or pipe installation depths, or depths as indicated on Drawings.
 - 1. Water Piping: 60"
 - 2. Power (600 Volt and below): 36"
 - 3. Communications Cables: 36"
- B. Ensure conduit depth accommodates minimum separation between conduits containing different services. Minimum separations:
 - 1. Power (600 Volt and below) to Communications: 4"
- C. Install conduits and pipes in trenches on a minimum 4" bed of compacted granular fill.

- D. Install Warning tape directly above trench installed conduits. Warning tape installation depths:
 - 1. Power (600 Volt and below) Warning Tape: 12" (303 mm).
 - 2. Commuincaitons Warning Tape" 12" (303 mm).

3.02 TRENCHING

- A. Notify Architect of unexpected subsurface conditions and discontinue affected Work in area until notified to resume work.
- B. Slope banks of excavations deeper than 4 feet to angle of repose or less until shored.
- C. Do not interfere with 45 degree bearing splay of foundations.
- D. Cut trenches wide enough to allow inspection of installed utilities.
- E. Hand trim excavations. Remove loose matter.
- F. Remove excavated material that is unsuitable for re-use from site.
- G. Stockpile excavated material to be re-used in area designated on site.
- H. Remove excess excavated material from site.

3.03 PREPARATION FOR UTILITY PLACEMENT

- A. Cut out soft areas of subgrade not capable of compaction in place. Backfill with general fill.
- B. Compact subgrade to density equal to or greater than requirements for subsequent fill material.
- C. Until ready to backfill, maintain excavations and prevent loose soil from falling into excavation.

3.04 BACKFILLING

- A. Backfill to contours and elevations indicated using unfrozen materials.
- B. Employ a placement method that does not disturb or damage other work.
- C. Systematically fill to allow maximum time for natural settlement. Do not fill over porous, wet, frozen or spongy subgrade surfaces.
- D. Maintain optimum moisture content of fill materials to attain required compaction density.
- E. Granular Fill: Place and compact materials in equal continuous layers not exceeding 6 inches compacted depth.
- F. Soil Fill: Place and compact material in equal continuous layers not exceeding 8 inches compacted depth.
- G. Slope grade away from building minimum 2 inches in 10 ft, unless noted otherwise. Make gradual grade changes. Blend slope into level areas.
- H. Correct areas that are over-excavated.
 - 1. Other areas: Use general fill, flush to required elevation, compacted to minimum 97 percent of maximum dry density.
- I. Compaction Density Unless Otherwise Specified or Indicated:
 - 1. At other locations: 95 percent of maximum dry density.
- J. Reshape and re-compact fills subjected to vehicular traffic.
- K. Backfill to a minimum 6" above conduits.

3.05 BEDDING AND FILL AT SPECIFIC LOCATIONS

- A. Use general fill unless otherwise specified or indicated.
- B. Utility Piping, Conduits, and Duct Bank :
 - 1. Bedding: Use general fill.
 - 2. Cover with general fill.
 - 3. Fill up to subgrade elevation.
 - 4. Compact in maximum 8 inch lifts to 95 percent of maximum dry density.

3.06 FIELD QUALITY CONTROL

- A. Evaluate results in relation to compaction curve determined by testing uncompacted material in accordance with ASTM D698 ("standard Proctor"), ASTM D1557 ("modified Proctor"), or AASHTO T 180.
- B. If tests indicate work does not meet specified requirements, remove work, replace and retest.
- C. Frequency of Tests: Provide one test per each 2 vertical feet of consolidated fill for each 200 horizontal feet of trench.

END OF SECTION



Bidders Request for Alternatives or Exceptions (BRAE)

Letting Date: January 7, 2016

Proposal No.: 15602

BRAE form due on or before: December 31, 2015

Item: Electrical upgrade for Centerville Maintenance Garage Brine Building Spec. No.: _____

Request: _____

Bidder Proposes to furnish in lieu of above: _____

NOTE: The determination of acceptance of this BRAE request is only valid for the bid for which it was submitted. BRAE approvals received for this bid do not determine or set a precedent for what is acceptable in any other bid posted by the State of Iowa.

Email/Fax to:

Iowa Department of Transportation
Purchasing Section
Attention: Laura Linduski
Email:laura.linduski@dot.iowa.gov

Fax No.: 515-239-1538

Submitted By _____

Company _____

Address _____

City State Zip

Phone No. _____

Fax No. _____

=====

DOT USE ONLY

Approved _____

Disapproved _____

Reason _____

Signature: _____

Date: _____