



www.iowadot.gov

**Date: March 8, 2016**

**ADDENDUM NO. 1  
to the  
Iowa Department of Transportation  
Proposal No. 16119  
For Lighting installation for 6 Iowa DOT Maintenance Facilities in Various Locations  
throughout the state  
Letting Date: 03/16/2016**

**Notice To Bidders:**

This Addendum is issued to incorporate the following additions, deletions, corrections, and/or clarifications to the terms or specifications and shall hereby be considered a part of the final contract documents. This Addendum shall supersede, modify and/or change all statements to the contrary in the bid proposal and shall take precedence over previous terms or specifications.

**CHANGE: The following language in section 3.1.1 has changed**

**Albia** IA DOT furnished lights (33) high bay, (6) wet location high bay  
Contractor furnished (5) workbench ~~LED~~ and replace with Lithonia PV Series PV 2 32 MVOLT GEB 10PS, (3) combination exit/emergency

**Bloomfield** -Contractor to provide as per plans (Base Bid) supply materials, demolition and labor for the following fixtures (33) high bay ~~LED~~, (6) wet locations high bay ~~LED~~, (5) workbench ~~LED~~ and replace with Lithonia PV Series PV 2 32 MVOLT GEB 10PS, (3) combination exit/ emergency, this includes miscellaneous install and materials for circuit new fixtures.

**Bloomfield Alt1**-Contractor to provide alternate (1) as per plans LED fixtures as scheduled on the Drawings. With the exception of the work bench light it is to be replaced with Lithonia PV Series PV 2 32 MVOLT GEB 10PS  
All other aspects of the work remain the same.

**Council Bluffs** IA DOT furnished lights (43) high bay, (9) wet locations high bay.  
Contractor furnished (8) work bench ~~LED~~ and replace with Lithonia PV Series PV 2 32 MVOLT GEB 10PS, (3) combination exit/ emergency

**Mount Pleasant** IA DOT furnished (42) high bay, (9) wet locations high bay.  
Contractor to furnish (8) workbench ~~LED~~ and replace with Lithonia PV Series PV 2 32 MVOLT GEB 10PS, (3) Combination exit/ emergency

**Urbana** IA DOT to furnished (60) high bay,  
Contractor to furnish (18) wet location high bay.  
(10) workbench ~~LED~~ and replace with Lithonia PV Series PV 2 32 MVOLT GEB 10PS, (4) Combination exit/ emergency

**Washington** IA DOT furnished (61) high bay, (6) wet location high bay. Contractor to furnish (12) work bench ~~LED~~ and replace with Lithonia PV Series PV 2 32 MVOLT GEB 10PS, (3) Combination exit/ Emergency.

**Changes continued:**

**Plan language**

Electrical Keyed Notes for all locations

#4 Demolish and replace the existing fluorescent light fixtures over the work benches with fluorescent fixture Lithonia PV Series, PV 2 32 MVOT GEB 10PS ~~new LED light fixtures~~ in the same location.

**Urbana plan**

#5 Urbana, now has contractor supplying the 18 Type F2 wet location high bay fixtures, but plan fixture schedule on plan page E1 for Urbana still shows the F2 as being supplied by Owner. **F2 is to be supplied by the contractor.**

The Schedule of prices form has been updated to reflect the changes from section 3.1.1

**ADDITIONS:**

All Bidders must sign and return this Addendum for the bid opportunity referenced above. Failure to do so may subject the Bidder to disqualification. If a bid response has already been submitted, this Addendum shall be signed and emailed or faxed to the Purchasing Section prior to the scheduled Letting Date.

\_\_\_\_\_  
Company Name *(please print)*

\_\_\_\_\_  
Date

\_\_\_\_\_  
Signature

Sincerely,

Jody McNaughton, Purchasing Agent (title)  
Phone No. 515-239-1298 Fax No. 515-239-1538  
Jody.mcnaughton@dot.iowa.gov

## Schedule of Prices

### Project Description: Lighting Installation at 6 Various Garage Locations Albia, Bloomfield, Council Bluffs, Mount Pleasant, Urbana, Washington

Locations are not tied.

Item No.	Description	Quantity	Unit/Price	Total Bid Amount
1	<p>Albia Garage 501 South C Street Albia, IA 52531</p> <p>Contractor to provide materials, demolition and labor to install IA DOT furnished lights as indicated in the plans and specifications 33 high bay, 6 wet location high bay. Contractor to furnish 5 workbench fluorescent lights Lithonia PV Series, PV 2 32 MVOLT GEB 10PS ,3 combination exit/emergency</p>	1	Lump/Sum	\$ _____
2	<p>Bloomfield Garage 20836 HWY 2, Bloomfield, IA 52537</p> <p>Contractor to provide as per plans (Base Bid for T8 fluorescents) supply materials, demolition and labor for the following fixtures 33 high bay, 6 wet locations high bay, 5 workbench fluorescent lights Lithonia PV Series, PV 2 32 MVOLT GEB 10PS, 3 combination exit/ emergency, this includes miscellaneous install and materials for circuit new fixtures.</p>	1	Lump/Sum	\$ _____
2A	<p>Alt1- E1 for Bloomfield</p> <p>Contractor to provide alternate (1) as per plans using LED fixtures opposed to the T8 Fluorescents as scheduled on the Drawings. With the exception of the work bench area this will be Lithonia PV Series, PV 2 32 MVOLT GEB 10PS</p> <p>All other aspects of the work remain the same.</p>	1	Lump/ Sum	\$ _____
3	<p>South Council Bluffs Garage 3540 South Express Way Council Bluffs, IA 51502</p> <p>Contractor to provide materials, demolition and labor to install IA DOT will furnish 43 high bay, 9 wet locations high bay. Contractor furnished 8 work bench fluorescent lights Lithonia PV Series, PV 2 32 MVOLT GEB 10PS 3 combination exit/ emergency</p>	1	Lump/Sum	\$ _____
4	<p>Mt Pleasant Garage 906 East Harvest Dr Mt Pleasant, IA 52641</p>	1	Lump/Sum	\$ _____

	Contractor to provide materials, demolition and labor to install, IA DOT furnished 42 high bay, 9 wet locations high bay. Contractor to furnish 8 workbench fluorescent lights Lithonia PV Series, PV 2 32 MVOLT GEB 10PS, 3 Combination exit/ emergency			
5	Urbana Garage 5397 31 <sup>st</sup> Street Urbana, IA 52345  Contractor to provide materials, demolition and labor to install IA DOT furnished 60 high bay, Contractor to provide 18 wet location high bay. 10 workbench fluorescent lights Lithonia PV Series, PV 2 32 MVOLT GEB 10PS, 4 Combination exit/ emergency	1	Lump/Sum	\$ _____
6	Washington Garage 1148 East 11 <sup>th</sup> Street Washington, IA 52323  Contractor to provide materials, demolition and labor to install IA DOT furnished lights as indicated in the plans and specifications. IA DOT furnished 61 high bay, 6 wet location high bay. Contractor to furnish 12 work bench fluorescent lights Lithonia PV Series, PV 2 32 MVOLT GEB 10PS, 3 Combination exit/ Emergency.	1	Lump/Sum	\$ _____

I hereby certify that this Bid Response meets or exceeds the minimum requirements including specifications and addendums.

Authorized  
Signature:

\_\_\_\_\_

Contact Person:

Company:

\_\_\_\_\_

\_\_\_\_\_  
(Print Name)

Address:

\_\_\_\_\_

\_\_\_\_\_  
(City) (State) (Zip Code)

Contractors  
Registration No \_\_\_\_\_

Phone No: \_\_\_\_\_

Email: \_\_\_\_\_

Fax No.: \_\_\_\_\_

I acknowledge receipt of addendums: \_\_\_\_\_