

Proposal 16167
Decorah Salt Shed Renovations
Questions and Responses Set 1

Q1) Are we just dealing with the North wall and re-sheathing the South wall and then siding both?

R1 Removing the sheathing on the North and South walls, repairing the North wall, enclosing the doors on the North wall, and sheathing and siding the whole building.

Q2 Are we actually removing and replacing the whole North wall or just filling in the overhead door openings?

R2) Just removing the sheathing on the North wall, repairing the wall where it has been pushed out, and enclosing the doors.

Q3) Are we framing out and sheathing the side walls?

R3) Yes.

Q4) Does the whole building get siding?

R4) Yes.

Q5) Any gutter and fascia work?

R5) No.

Q6) Is the ledger the 4-treated 2x12's shown on the inside?

R6) The ledger will go on the outside of the building around the bottom to keep any rodents from getting into the walls between the inside and outside sheathing.

Q7) Is any of the interior wall sheathing being replaced?

R7) No, just make sure to include enough sheathing to cover where the doors get enclosed on the inside.

Q8). Are any of the existing 6x8 posts being replaced?

R8) Possibly 2, we will not know that until the sheathing gets removed on the North end, there MAY be 2 broken posts.

Q9) Are all new wood materials treated?

R9) Any new posts would need to be treated, since everything else will be covered with siding treated lumber is not necessary.