

**Proposal 16941**  
**Remodeling of the Management Team Area at Ames DOT Complex**  
**Questions and Responses Set 1**

**Q1) Is there a basement and what is the ceiling like?**

**R1) Yes, There is a basement it has a partial open ceiling and also enclosed tile ceiling.**

**Q2 What kind of box are you using?**

**R2) A floor outlet will be chosen that can have a circular cut in floor, size of hole needed to be 10" – 12".**

**Q3) Remove cabinets and replace some in 117 the extra cabinets and counter top will be taken to the auction building.**

**R3) See addendum and drawing update.**

**Q4) Are we to remove all blinds in offices?**

**R4) Yes in office 101-105 exterior window blinds and put up new shades as per specs & drawings.**

**Q5) Floor covering, we can't cut into carpet without really destroying it with cuts and slurry from the drilling.**

**R5) Flooring will be replaced by others coordinated with work to be done on this contract.**

**Q6) Walls do they need painted? The hallway wall the textures will not match once the windows are replaced how do you want to handle that?**

**R6) Yes, The hallway wall will need to be skimmed over and orange peel texture paint color # SW 7037.**

**Q7) How do you want to handle the drilling noise and mess for the basement staff. The area will need to be bagged.**

**R7) DOT will move what the can and then contractor to bag the rest. DOT can arrange drilling work to be done after hours or weekends if needed and to move equipment.**

**Q8).Do the new cabinets have special grommets or openings?**

**R8) No**

**Q9)How are we handling the carpet issues once the cabinets are removed?**

**R9)Flooring will be replaced by others coordinated with work to be done on this contract.**