

**Proposal 17003  
Questions and Responses Set 1**

**Q1) Will the tower antenna be reinstalled?**

**R1) No, remove existing antenna tower and dispose of offsite. See addendum 2**

**Q2) Can downspouts drain into tiling around building?**

**R2) Yes, this is an option. Please bid the project as shown, with the drainage piping 4" per spec section 33 4600. If you would like to provide drainage of the North-side downspouts into the building subdrainage, please bid this as Alternate #1. Provide a closed connection with PVC downspout connectors to PVC risers, properly connected to 6" PVC subdrainage system as specified in 33 4600 – perforated with sock. Use Timewell Drainage Products or equal.**

**[www.timewellpipe.com](http://www.timewellpipe.com) see addendum 2**

**Q3) Can an alternate material be used to patch asphalt road where drainage excavation occurs?**

**R3) Yes. The road repair where the drainage crosses can be repaired with concrete of the same requirements as the rest of the project. Be sure the base is well compacted before installing concrete to ensure lasting results. Asphalt is also acceptable. See addendum 2**

**Q4) Will there be any interior masonry wall repair?**

**R5) Not at this time. This is strictly an exterior project. See addendum 2**