FIELD EVALUATION OF COLD IN-PLACE RECYCLING OF ASPHALT CONCRETE

FINAL REPORT Iowa Highway Research Board Project HR-303

DECEMBER 1993

Highway Division



Final Report for Iowa Highway Research Board Project HR-303

Field Evaluation of Cold In-Place Recycling of Asphalt Concrete

By Robert Gumbert, P.E. Tama County Engineer 515-484-3341

and

Gary Harris Secondary Road Research Coordinator 515-239-1382 Office of Materials Highway Division Iowa Department of Transportation Ames, Iowa 50010

December 1993

TECHNICAL REPORT TITLE PAGE

1.	REPORT NO.	2.	REPORT DATE
	HR-303		December 1993
3.	TITLE AND SUBTITLE	4.	TYPE OF REPORT & PERIOD COVERED
	Field Evaluation of Cold In-Place Recycling of Asphalt Concrete		Final Report, 6-89 to 12-93
5.	AUTHOR(S)	6.	PERFORMING ORGANIZATION ADDRESS
	Robert Gumbert Tama County Engineer		1002 E. 5th Street Tama, Iowa 52339-2216
	Gary Harris Secondary Road Research Coordinat	or	Iowa Department of Transportation Office of Materials 800 Lincoln Way Ames, Iowa 50010

7. ACKNOWLEDGEMENT OF COOPERATING ORGANIZATIONS

Asphalt Paving Association of Iowa Nady Engineering Service Koss Construction Cessford Construction Company

8. ABSTRACT

The average thickness of the existing asphalt cement concrete (ACC) along route E66 in Tama County was 156 mm (6.13 in.). The rehabilitation strategy called for widening the base using the top 75 mm (3 in.) of the existing ACC by a recycling process involving cold milling and mixing with additional emulsion/rejuvenator. The material was then placed into a widening trench and compacted to match the level of the milled surface.

The project had the following results:

- Cold recycled ACC pavement does provide adequate pavement structure for a low volume road.
- Premature cracking of the ACC in the widened pavement area was caused by compaction of the mix over a saturated subgrade.
- Considerably less transverse and longitudinal cracking with 75 mm (3 in.) of cold recycled ACC and a 50 mm (2 in.) hot mix ACC overlay than a conventional hot mix overlay with no cold recycling.

More research should be done on efficient construction procedures and incorporating longer test sections for proper evaluation.

9. KEY WORDS

10. NO. OF PAGES

Cold recycling Milling ACC Rehabilitation

TABLE OF CONTENTS

	Page
Introduction	1
Objective	2
Project Location and Description	2
Construction	4
Field Evaluation	7
Crack Survey	10
Conclusions and Recommendations	11
Acknowledgements	12
Appendices	
Appendix A - Contract Document Appendix B - Special Provisions & Cross Sections	13 22

Appendix C - Construction Photographs.....

30

DISCLAIMER

The contents of this report reflect the views of the author and do not necessarily reflect the official views of the Iowa Department of Transportation and Tama County. This report does not constitute any standard, specification or regulation.

INTRODUCTION

There still exists in Iowa substantial mileage of 1920's and 1930's portland cement concrete (PCC) pavement, 5.4 m (18 ft) wide with one, two or more asphalt cement concrete (ACC) overlays dating from the 1950's to more recent times. The first overlays were placed to fill the curb sections, to cover joints and to improve rideability. Successive overlays were placed to cover reflective cracks and to again improve the rideability.

To date, most of this mileage remains 5.4 m (18 ft) wide and has its original horizontal and vertical alignment. These roads, formerly a part of the State system, now mostly transferred to county jurisdiction, are increasingly more hazardous to drive (due to fewer and fewer motorists having significant driving experience on this type of road) and more difficult to maintain (especially along the edge of the pavement).

While there is agreement that these roads need to be improved, both from a safety and a maintenance perspective, there is no affordable, commonly accepted method available to accomplish the needed improvements. For example, Tama County has nearly 32 km (20 miles) of original (constructed in the 1920's) US 30. To do a reconstruction of this mileage (involving removal of existing pavement, corrective grading, and new paving) would use all of the county's Farm-to-Market money from now to well into the next century.

OBJECTIVE

The objective of this project was to search for an effective, affordable technique, based on cold in-place recycling of ACC pavement, to widen an existing road, 5.4 m (18 ft) in width, to 7.2 m (24 ft) and to have a finished surface capable of carrying traffic with little or no additional work.

Specific topics to be investigated were:

- Structural adequacy of the milled and cold recycled rehabilitated pavement.
- Density measurements to compare the density obtained in the several sections to the laboratory density of the recycled material.

PROJECT LOCATION AND DESCRIPTION

The proposed research was part of a project to improve a portion of Tama County Route E66 (formerly Iowa 212, formerly US 30) (see Figure 1) and involved:

 Basic treatment: cold in-place recycling of 75 mm (3 in.) of the existing ACC surfacing to provide material for a widening strip, 900 mm (3 ft) wide, to be placed along each side of the existing roadway.



2. Test sections applied to "Basic Treatment" sections:

- A. 120 m (400 ft) of aggregate seal coat only plus three different engineering fabrics placed over the longitudinal joint.
- B. 120 m (400 ft) of slurry seal coat only plus three different engineering fabrics placed over the longitudinal joint.
- C. 210 m (700 ft) of a 50 mm (2 in.) overlay of new hot mix ACC only plus three different engineering fabrics placed over the longitudinal joint.
- 3. A. As in 2A above.
 - B. As in 2B above.
 - C. Test section applied to 210 m (700 ft) where 75 mm (3 in.) of ACC were cold milled to provide material for the widening strip and an additional 75 mm (3 in.) of remaining ACC were cold in-place recycled (placed by an asphalt paver):

CONSTRUCTION

This research was part of a project to improve a 7.2 km (4.5 mile) portion of Tama County road E66 (formerly Iowa 212, formerly US 30). Approximately 75 mm (3 in.) of the

150 mm (6 in.) ACC resurfacing on this PCC pavement was milled off to provide a 900 mm (3 ft) widening strip on both sides of the existing roadway. Fog seal treatment, bituminous seals or slurry seals were used to provide the wearing surface.

The contractors began the milling and trenching operations on June 14, 1989 and the entire project was completed August 17, 1989.

The milling procedure began at station 2315+50 in the eastbound lane only. With the milling machine being 3.6 m (12 ft) wide and the road lane 2.7 m (9 ft) wide, the outside track of the machine broke off pieces of the ACC at the edge. The subcontractor began the trenching operation 900 mm (3 ft) wide and 230 mm (9 in) deep behind the milling machine and it soon proved inadequate in keeping pace with the milling operation. There was some discussion about obtaining another trencher. In the meantime, the trench was formed 760 mm (2.5 ft) wide and 100 mm (4 in.) deep with a motor grader.

Trenching on the following day began at station 2351+00 prior to milling to give the trenching machine a head start. The milling operation ran smoothly until the milling train ran out of asphalt emulsion. The train was again running smoothly with a new supply of CRS2 emulsion out of Des Moines, but ceased operating to allow the trencher to catch up.

Work proceeded eastward toward Chelsea and back westward with the milling operation now working mostly in the left, westbound lane toward the research sections of the project (station 2333+00 to 2365+00). The new "Ditch Witch D-100" trencher did a significantly better job of keeping pace with the milling machine and with only a few minor repairs. Compaction of the cold recycled material was initially done with a motor grader running the tires on the widening strip, but this proved ineffective. Later, a fully loaded tandem axle truck was used to achieve better results. However, cracks developed in the mat in a few trench areas caused by what appeared to be a saturated subgrade flexing under the compactive effort.

An AC-10 asphalt cement was used to place the engineering fabrics over the widening joint throughout the test sections. Trevira 1114 was placed from station 2345+00 to 2346+00, 1-Step Roadglas from station 2344+00 to 2345+00 and station 2351+00 to 2352+00, and Petromat from station 2343+00 to 2344+00. Three other similar test sections used identical lengths of fabric. There appeared to be no appreciable difference in performance between the various fabrics after three years in that they all allowed longitudinal reflective cracks at the widening strip to surface as early as one year after construction.

FIELD EVALUATION

Road Rater™ testing has been conducted annually on the entire project with the exception of 1990. The Road Rater is a dynamic deflection measuring device used to determine the structural adequacy of pavements. The difference in pavement structural ratings from year to year (Table 1) may be explained by the fact that annual testing is performed in the outside wheeltrack during the months of April and May when the roadway exhibits the greatest instability. Thus, the structural rating can vary from one year to the next depending upon the amount of moisture in the soil at the time of testing. For the most part, a high structural rating will correspond with a thicker overlay. The difference in these results are statistically insignificant.

Table 1. Deflection Testing							
	1989	1991	1992				
Structural Rating	2.10	1.68	2.02				
Soil K	86	86	90				

Field cores were taken in the spring after construction to correlate field densities to laboratory densities (Table 2). In every case, the field densities exceeded those obtained in the laboratory.

Table 2. Lab and Field Core Comparison									
Core		Core	Laboratory	y Core as	Core Unit Wt,				
Number	Location	Density	Density	% of Lab	pcf				
1	2384+60 Rt	2.242	2.161	103.7	139.9				
2	2414+08 Lt	2.199	2.186	100.6	137.2				
3	2447+24 Rt	2.216	2.067	107.2	138.3				
4	2478+40 Lt	2.197	2.121	103.6	137.1				
5	2509+56 Rt	2.234	2.073	107.8	139.4				
6	2532+47 Lt	2.189	2.119	103.3	136.6				
7	2594+81 Rt	2.239	2.147	104.3	139.7				
8	2641+61 Lt	2.206	2.153	102.5	137.7				
9	2687+35 Rt	2.193	2.152	101.9	136.8				
10	2743+38 Lt	2.187	2.135	102.4	136.5				
11	2785+17 Rt	2.196	2.128	103.2	137.0				
12	2806+40 Lt	2.158	2.111	101.8	134.7				

Field cores were also taken from the project one year after construction to evaluate densities of the cold recycled asphalt concrete used in the widening strip (Table 3). No statistical significance exists between these core densities. The mix

appeared to be a fine mix and had a relatively high percentage of asphalt cement (>7%). The aggregate gradation for both sample cores 1 and 6 is given in Table 4 and the gradation chart is in Figure 2.

Table 3.	Post Construction Core Data					
Core #	Location	Density				
1.	2366+94 EB	2.212				
2	2478+70 EB	2.181				
3	2529+03 EB	2.168				
4	2527+19 WB	2.131				
5	2488+90 WB	2.124				
6	2373+20 WB	2.106				

Core #1 Core #6

FORM 820925 8-75 GRADATION CHART ISED TO THE 0.45 POWER. "SIMPLIFIED PRA 100 100 90 90 60 80 70 70 PERCENT PASSING 60 1.1 1 2 14 174 SIEVE ANALYSIS % PASSING Identification Sample Sieve Size Specification 111 30 3/4" 3 /8" 20 #4 #8 #16 #30 10 450 #100 #200 0 50 100 40 50 5, 20, No 90 10 . 74 IN

IOWA DEPARTMENT OF TRANSPORTATION

Aggregate Gradation on a 0.45 Power Chart

Figure 2

Table 4 Combined Aggregate Gradation By Extraction								
	Percent	Passing						
Sieve Size	Core #1	Core #2						
19 mm (3/4 in)		100						
13.2 mm (1/2 in)	100	99						
9.5 mm (3/8 in)	98	93						
4.75 mm (#4)	82	71						
2.36 mm (#8)	64	55						
1.18 mm (#16)	51	44						
600 µm (#30)	40	33						
300 µm (#50)	25	19						
150 µm (#100)	19	14						
75 μm (#200)	16	12						

CRACK SURVEY

A detailed crack survey of the test sections has been conducted annually since the completion of the project in 1989. The purpose of the crack survey was to document occurrence of new or reflective cracking in the surface. The chip seal, slurry seal, and fog seal sections were only surface treatments that clearly exhibited the underlying pavement cracking due to the milling of the top surface. Therefore, only the 210 m (700 ft) hot mix ACC and cold recycled ACC test sections could reveal true reflective surface cracking since the completion of the project. The section that was milled and overlaid with hot mix ACC experienced more than ten times the length of total transverse cracking (Figure 3) and six times the length of total longitudinal cracking than the cold recycled ACC test section. The majority of the longitudinal cracking occurred at the widening joint between the old roadway and the widening trench.





CONCLUSIONS & RECOMMENDATIONS

This research resulted in the following conclusions:

- 1. Cold recycled ACC pavement does provide adequate pavement structure for a low volume road.
- 2. Blading out 100-125 mm (4"-5") of shoulder material prior to trenching should improve the speed of the trencher in keeping pace with the milling operation. A specially designed cutting edge fitted for a motor grader should work well.
- 3. The 75 mm (3 in) cold recycled section with a 50 mm (2 in) ACC overlay had considerably less cracking after three years than the section with a 2 inch ACC overlay and no cold recycling.

ACKNOWLEDGEMENTS

Research project HR-303 was sponsored by the Iowa Highway Research Board and Tama County. Funding for this project was from the Secondary Road Research Fund in the amount of \$100,000.

The Tama County Secondary Road Department wishes to extend their appreciation to the Tama County Board of Supervisors, the Iowa Department of Transportation, the Asphalt Paving Association of Iowa, Nady Engineering Service and the employees of Koss Construction Company of West Des Moines, Iowa and Cessford Construction Company of Le Grand, Iowa for the extra effort and cooperation that was put forth in the completion of this research project.

Appendix A Contract Document



¢

Iowa Department of Transportation

800 Lincoln Way, Ames, IA 50010 5

515/239-1414

MAY 31 1988

County Auditor:

We are enclosing one fully signed copy of the contract(s) awarded by your Board of Supervisors for the following project(s):

Tama County, SN-4875(1), ACC

Very truly yours,

Harrey A. Olson

Harvey H. Olson Contracts Engineer Highway Division

HHO:djw

Enclosure

cc: District 1 Engineer Reilly Constr. Co., Inc. Box 99 Ossian, IA 52161 Tama County Engineer

CONTRACT

NO. 28666

County TAMA	l III		Proi	ect No	- M2	4875	())-	-51-	86				
Type of Work	GRAD	E & .	ACC'PA	VEMEN	r			M	iles _	9.	9 200		
Cost Center	80100	ROA	D E-bb	ect Code	8L THE	<u>0</u> JUNC	TION	ØF	U • S	S• 30-			
SOUTHE	STERL	Y TO	APPRO	XIMATE	ELY D	•6 M	ILE	LES'	r of	THE	JUNCTI	ON	
OF IOW	1 51.												
This agreen C OUNTY	nent mad	e and	entered	by and b	etween	the _	B0	ARD	ØF	SUPE	RVISORS	ØF	TAMA
		······································								Cont	racting Au	thori	ty and
PETTY	TANT	RULT	TAN CO		• 0F	220	TAN-	TO	A			a cino ni	y, and

00037400Contractor.

81 1988

It is agreed that the notice and instructions to bidders, the proposal filed herein, the general specifications of the lowa Department of Transportation for 1984, together with supplemental specifications and special provisions, together with the general and detailed plans, if any, for said project

_, together with Contractor's performance bond, are made a part hereof and together with this instrument constitute the contract. This contract contains all of the terms and conditions agreed upon by the parties hereto. A true copy of said plans and specifications is now on file in the office of the Contracting Authority under date of ______

, payable as set forth in the Contractor, for and in consideration of \$... specifications constituting a part of this contract, agrees to construct various items of work and/or provide various materials or supplies in accordance with the plans and specifications therefor, and in the locations designated in the Notice to Bidders.

Contractor certifies by his signature on this contract, under pain of penalties for false certification, that he has complied with Iowa Code Section 324.17(8) (1985) as amended, if applicable.

In consideration of the foregoing, Contracting Authority hereby agrees to pay the Contractor promptly and according to the requirements of the specifications the amounts set forth, subject to the conditions as set forth in the specifications.

It is further understood and agreed that the above work shall be commenced or completed in the following schedule: START • DATE COMPL• DATE with the following schedule: 150 06/30/89

Time is the essence of this contract.

To accomplish the purpose herein expressed, Contracting Authority and Contractor have signed this and four other identical instruments as of the _____ day of ______

BOARD OF SUPERVISORS OF TAMA COUNTY, IOWA

Ву	Jer Contracting Authority		Approved:			
	REILLY CONSTRUCTION CO., INC.	0F	OSSIAN 2-1	en R	. Olar	MAY 8
D .,	Colley Bill		· Ce	ontracts Engin	eer	Date
БУ	Contractor		10	mana pari da	TRANSPOR	TATION

Proposal I.D. No. 880880

Contractor's Not 31 71 41 01 01

CONTRACT NO. 28666

County TAMA

Bid Order No. 157

Page No.]

Project No. SN-4875(1)--51-86

Type of Work GRADE & ACC PAVEMENT

			.	Unit Price		Amount	
Line No.	tom	110m (Units	Dollars XXXX,XXX	Cents XXXX	Dollars XX,XXX,XXX	Cents XX
0010	SURFACING, GRANULAR, CLASS A CRUSHED STONE - ON ROAD	60	TONS	J.5	-0000	9 00	•00
0200	APRONS, CONCRETE PRECAST, L. X J.	6	ONLY	1800	-0098	20-800	•00.
0030	APRONS, CONCRETE PRECAST, 7" X 3"	5	ONLY	7400	-0000	3-800	•00
0040	APRONS CONCRETE PRECAST 8 X 4	5	ONLY	2050	-0000	4,100	• 00
0050	APRONS, CONCRETE, 36 IN- DIA-	ţ,	ONLY	450	-0000	a-700	• 00
0060	APRONS. METAL, 21 IN. DIA.	٩	ONL Y	1.55	•0000	1-395	-00
0070	APRONS, METAL, 24 IN. DIA.	4	ONLY	165	•0000	660	•00
008C	APRONS. METAL. 36 IN. DIA.	5	ONLY	450	•0000	900	-00
0050	APRONS. METAL, 66 IN. DIA.	5	ONLY	7552	-0000	2,450	•00
0700	APRONS, METAL, 78 IN. DIA.	5	ONLY	1500	-0000	3-000	-00
0770	APRONS, METAL, ARCH, 28 IN• X 20 IN•	́ Ц	ONLY	150	-0000	480	+00
0750	APRONS, METAL, ARCH, 42 IN- X 29 IN-	Ь	ONLY	245	•0000	1-470	-00
0130	CLEARING & GRUBBING	l	ACRES	2005	•0000	. s.ooc	- 00
0140	CULVERT, CONCRETE ROADWAY PIPE, 36 IN. DIA.	245	LINEAR	FT 65	-0000	15-925	•00
01,50	CULVERT, CORRUGATED METAL ARCH ROADWAY PIPE, 28 IN. X 20 IN.	52	LINEAR	FT 42	•0003	1-134	•00
0720	CULVERT. CORRUGATED METAL ARCH ROADWAY PIPE. 42 IN. X 29 IN.	108	LINEAR	FT 47	- 5000	5.130) - 00
0170	CULVERT, CORRUGATED METAL ARCH ROADWAY PIPE, 49 IN. X 33 IN.	750	LINEAR	FT 60	.0000	7,200	•00
03.60	CULVERT, CORRUGATED METAL ROADWAY PIPE, 21 IN- DIA-	74	LINEAR	FT 43	8.0000	· 3 .1 88	2-03
01,90	CULVERT, CORRUGATED Metal Roadway Pipe, 24 IN. DIA.	11 9	LINEAR	FT 21	•0000	E-478	-00

1444 470 ••

Proposal I.D. No. 880880

Contractor's No L 31 71 41 01 0

.

Project No. SN-4875[1]--51-86

CONTRACT NO. 28666 County TAMA

Bid Order No. 157

Page No. 3

Type of Work GRADE & ACC PAVEMENT

				Unit Price	• {	Amount	
Line No.	item	item (and	Quentity Units	Dollars X,XXX,XXX	Centa XXXX	Dollars XX,XXX,XXX	Cents XX
0420	(CONTINUED) FLAGGERS	10	ZYAC	10(0000	1-00	0 .0 0
0430	APRONS, CONCRETE PRECAST, 12' X 5'	5	ONLÝ	50 \$()+0000	16-10	0+00
0440	APRONS, CONCRETE PRECAST, 8" X 4"	2	ONLY	2050	0000-0	4-10	0+00
0450	APRONS, CONCRETE, 48 IN. DIA.	1	ONLY	683	5.0000	68	5+00
0460	APRONS, METAL, 21 IN- DIA-	7	ONLY	15	5-0000	1.08	5-00
0470	APRONS, METAL, 30 IN. DIA.	٦	ONLY	25	0.000	25	i0 . 00
0480	APRONS, METAL, ARCH, 49 IN- X 33 IN-	2	ONLY	40	0.000	80	00-00
0490	APRONS, METAL, ARCH, 42 IN. X 29 IN.	5	ONLY	- 24	5.0000	tų ت	10 • 00
0500	CLEARING & GRUBBING	2	ACRES	200	0.0000	4.00	00+00
0510	CONCRETE STRUCTURAL	32- L	CUBIC	YDS 35	0-0000	11-43	0-00
0520	CULVERT, CONCRETE ROADWAY PIPE, 48 IN. DIA.	. 61	LINEAR	FT 8	s-0000	6.8	85.00
0530	CULVERT, CORRUGATED METAL ARCH ROADWAY PIPE, 49 IN, X 33 IN,	25	LINEAR	FT 6	0.0000	1.5	00-00
0540	CULVERT, CORRUGATED Metal Arch Roadway Pipe, 64 IN. X 43 IN.	40	LINEAR	EL 15	5-0000	5.0	00-00
0550	CULVERT. CORRUGATED METAL ENTRANCE PIPE. 18 IN. DIA.	165	LINEAR	FT 1	6.0000		40.00
0560	CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN- DIA-	28) LINEAR	FT a	2-0000		16-00
0570	CULVERT. CORRUGATED Metal Roadway Pipe. 21 IN. DIA.	11.	3 LINEAR	FT L	13+0000) 4 . 8	59.00
0580	CULVERT, CORRUGATED Metal Roadway Pipe, 66 IN- Dia-	33	3 LINEAR	FT 1a	25-0000) 4.1.	25-00
0590	CULVERT. CORRUGATED Metal Roadway Pipe, 30 IN. DIA.	4	3 LINEAR -	FT I	-2 -000 0	, , 5'F	66+00
0600	CULVERT, CORRUGATED Metal Roadway Pipe, 54 IN- DIA-	15	4 LINEAR	R FT	75-000() 9.3	00-00
						•.	

CONTRACT NO. 28666

County TAMA

Bid Order No. 3-57

Contractor's No.L 31 71 41 11 11

Proposal I.D. No. 880880

Project No. SN-4875 (1) -- 51-86

Type of Work GRADE & ACC PAVENENT

Page No. 2

						28		
		item (Quantity	Un	t Price	Amount		
Line No.		end	Units	Dollara X,XXX,XX	x	Cents XXXX	Dollars XX,XXX,XXX	Cent
02.00	CULVERT, CORRUGATED METAL ROADWAY PIPE, 35 IN- DIA-	24	LINEAR	FT	P5	•0000	1-46	8+00
0570	CULVERT, CORRUGATED Metal Roadway Pipe, 78 IN• DIA•	105	LINEAR	FT.	90	-0000	5.16	-00 -
0250	CULVERT, PRECAST CONCRETE BOX, 6' X 3'	Эь	LINEAR	FT	450	•0000	16.50	10-00
0230	CULVERT, PRECAST CONCRETE BOX, 7º X 3º	18	LINEAR	FT	520	-0000	1 <i>i</i>	80.00
0240	CULVERT PRECAST Concrete Box, 8" X 4"	25	LINEAR	FT	560	-0000	ь. ?а	20+00
0250	ELBOUS, CONCRETE PIPE, 35 IN. DIA.	7	ONLY		240	-0000	51	10.00
0520	ELBOWS, CORRUGATED METAL ARCH ROADWAY PIPE, 42 IN. X 29 IN.	ų	ONLY		590	•0000	1.10	20.00
0270	ELBOWS, CORRUGATED METAL ARCH ROADWAY PIPE, 49 IN• X 33 IN•	ų	ONLŸ		350	-0000	1-51	50+00
0850	ELBOWS, CORRUGATED METAL PIPE, 21 IN. DIA.	5	ONLY		160	-0000	ΪE	20+00
0290	ELBOWS, CORRUGATED METAL PIPE, 35 IN. DIA.	2	ONLY	ν.	085	•0000	51	-0-00
0300	EXCAVATION: CLASS 10. Roadway & Borrow	25752	CUBIC \	ZQI	5	- 9000	74-6	80+80
0310	EXCAVATION, CLASS 20	276	CUBIC Y	ZC	50	•0000	S + 5	20.00
0350	GRANULAR MATERIAL	35	TONS		50	•0000	្រំដូរ	10.00
0330	MOBILIZATION		LUMP SU	m		• .	44.0	00-00
0340	MORTAR. FLOWABLE	858	CUBIC	20S	70	•0000	15-46	00.00
0350	OVERHAUL	37 25P 7	STA- YI	•20	0	.0200	6-31	35-22
0360	REMOVAL OF EXISTING STRUCTURES		LUMP SU	J M			5-0	00-00
0370	REMOVAL OF PAVEMENT	2753	Se- YDS	S	Э	- 5000	9-63	35.50
0380	STABILIZING CROP - SEEDING AND FERTILIZING	57	ACRES		200	•0000	4-2	00+00
0990	SUBDRAIN, PLASTIC PIPE, 5 IN.	95	LINEAR	FT	-15	-0000	1.4	2 5-0 °
0400	TOPSOIL, STRIP, SALVAGE AND SPREADING	8470	CUBIC	ZC	З	• 5000	1 - 95	45-06
0410	TRAFFIC CONTROL		LUMP SU	M			2.0	00.00

Proposal I.D. No. 880880

Contractor's No.L. 31 71 41 11

CONTRACT PRICES

CONTRACT NO. 28466

Bid Order No. 1.57

Page No. 5

Amount

Project No. SN-4875 (1) -- 51-86

County TAMA Type of Work GRADE & ACC PAVEMENT

Unit Price

		item (Dunotity	Unit Price	' 	Amount	· · · · · · · · · · · · · · · · · · ·
Line No.	Item	and	Units	Doilars X,XXX,XXX	Cents XXXX	Dollars XX,XXX,XXX	Cents XX
0580	(CONTINUED) SUBDRAIN, TILE, 6 IN. DIA.	995	LINEAR	FT 7	•0000	£.96	5-00
0680	TOPSOIL, STRIP, SALVAGE AND SPREADING	4961	CUBIC Y	E 20	• 5000	17-36	3+50
0840	TRAFFIC CONTROL		LUMP SU	n		7.00	Ū-00
0850	FLAGGERS	10	DAYS	1 00	0000-0	1.00	0-00
0860	CULVERT, CORRUGATED METAL ROADWAY PIPE, 66 IN- DIA-	28	LINEAR	FT 100	0000+0000	2+80	0-00
0670	CULVERT, CORRUGATED METAL ROADWAY PIPE, 48 IN. DIA.	104	LINEAR	FT BI	5.0000	8-84	0-00
0880	ASPHALT PAVEMENT, IN-PLACE COLD RECYCLED	48880	SQ. YDS	• :	7700	86-51	7-60
0890	ASPHALT REJUVENATING AGENT	43991	GALLONS	: f	-85 00	37-39	12+35
0900	EXCAVATION, CLASS 13, FOR WIDENING	8095	CUBIC Y	DZ .	2 • 5980	2C+96	6+05
0910	SHOULDERS, GRANULAR, TYPE B	2972	TONS	i	3•9000	25+05	6 3-5 0
0920	BASE, TYPE B CLASS L ASPHALT CEMENT CONCRETE	-55 . 37	TONS	J .	7-4500	44.17	20+95
0930	ASPHALT CEMENT	136	TONS	<u>]</u> 4	4-1400	J FC	3+04
0940	PRIMER OR TACK-COAT BITUMEN	3727	GALLONS		0.8300	3.0°	
0950	SHOULDER CONSTRUCTION.	28	- ZATZ	15	5-0000	; 3 . 50	00+00
0960	ASPHALT EMULSION FOR FOG SEAL	1,5356	GALLONS	5	1.2400]01	41.44
0970	ASPHALT EMULSION FOR SLURRY SEAL	746	GALLONS		1-9500	1-39	57-72
0980	AGGREGATE FOR SLURRY SEAL	- 55	TONS	18	0+4000	4.6	10-40
0990	AGGREGATE, ROADWAY Cover, 3/8 IN.	56	TONS	. 2	6-5400	6	10.04
1000	BINDER BITUMEN, FURNISH & APPLY CRS-2S	. 640	GALLONS	2	4-2000	č -68	88.00
1010	FABRIC REINFORCEMENT	SBB	SQ+ YDS	S.	6.4100	3-43	16+53
70 50	ASPHALT PAVEMENT. IN-PLACE COLD RECYCLED	46905	SQ- YDS	Ŝ•	1-7700	* 83.0a	22-85
7030	ASPHALT REJUVENATING AGENT	42215	GALLONS	2	0.8500	35.88	92-75

Proposal I.D. No. 880880

Contractor's No.L 31 21 41 Di

Project No. SN-4875(1)--51-86

CONTRACT NO. 28666

County TAMA

Bid Order No. 157

Page No. 4

Type of Work GRADE & ACC PAVEMENT

		item Quantity and Units		Unit Price		Amount	
Line No.	item			Dollars X,XXX,XXX	Cents XXXX	Dollars Centr XX,XXX,XXX XX	
0630	(CONTINUED) CULVERT, CORRUGATED METAL ARCH ROADWAY PIPE, 42 IN. X 29 IN.	14	LINEAR	FT .47	.5000	665+00	
0650	CULVERT, PRECAST CONCRETE BOX, 12' X 5'	55	LINEAR	525 FT	.0000	13.650.00	
0630	CULVERT PRECAST CONCRETE BOX 8' X 4'	14	LINEAR	FT 560	•0000	7.840.00	
0640	ELBOWS, CONCRETE PIPE, 48 IN- DIA.	7	ONLY	355	•0000	325•00	
0650	ELBOWS, CORRUGATED METAL ARCH ROADWAY PIPE, 49 IN, X 33 IN,	5	ONLY	250	-0000	500 -0 0	
0660	ELBOWS, CORRUGATED METAL PIPE, 21 IN. DIA.	5	ONLY	110	•0000	00-05	
06 7 0	ELBOWS. CORRUGATED METAL PIPE, 30 IN. DIA.	5	ONLY	175	•0000	350+00	
0690	EXCAVATION, CLASS 10, CHANNEL	1358	CUBIC Y	4 ZQ	•0000	5,375-00	
0690	EXCAVATION CLASS 10. ROADWAY & BORROW	32572	CUBIC Y	5 ZQ	• 9000	705-753-20	
0700	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	185	CUBIC Y	DZ 50	•0000	3+700+00	
0710	SURFACING, GRANULAR, CLASS A CRUSHED STONE - ON ROAD	10	TONS	15	•0000	150-00	
0720	GUARDRAIL END ANCHORAGES BEAM RE-52	14	ONLY	400	•0000	5+600+00	
0730	GUARDRAIL, FORMED STEEL BEAM	1293-75	LINEAR	FT 10	•0000	12-937-50	
0740	GUARDRAIL, POSTS, BEAM	202	ONLY	50	• 0000	16-100-00	
0750	MOBILIZATION		LUMP SU	in .		44,000+00	
0760	OVERHAUL	PDP533	STA. YD	•2•	•0500	12-125-46	
0770	REMOVAL OF EXISTING STRUCTURES		LUMP SU	m		4.000.00	
0780	REMOVAL OF PAVEMENT	2300	SQ- YDS	а З	.5000	8.050.00	
D790	STABILIZING CROP - SEEDING AND FERTILIZING	JР	ACRES	005	•0000	3 . 200.00	
08C0	STEEL REINFORCING	5810	POUNDS	J	•0000	5-810-06	
0410	SUBDRAIN OUTLET. Corrugated metal pipe. 6 IN- DIA-	36	ONLY	100	•0000	3.600.00	

Form 65031 8-87 H-588

CONTRACT PRICES

Proposal I.D. No. 880880

Contractor's No 1 31 71 41 01 01

Project No. SN-4875(1)--51-86

CONTRACT NO. 28666

County TAMA

Bid Order No. 157

Page No. 占

Type of Work GRADE & ACC PAVEMENT

Line No.	ltem	item Quantity and Units		Unit Price		Amount	
				Dollars X,XXX,XXX	Cents XXXX	Dollars XX,XXX,XXX	Cents XX
1040	(CONTINUED) EXCAVATION, CLASS L3, FOR WIDENING	8638	CUBIC Y	5 ZQ	5900	22,37	2-42
1050	SHOULDERS, GRANULAR, TYPE B	3010	TONS	q	-3800	28 . 23	3•80
1060	BASE, TYPE B CLASS L ASPHALT CEMENT CONCRETE	1532	ZNOT	50	-3500	31-17	6.50
7050	ASPHALT CEMENT	5P	TONS	344	-1400	73456	88+0
1080	PRIMER OR TACK-COAT BITUMEN	1878	GALLONS	0	0068-	1-55	8-74
7040	SHOULDER CONSTRUCTION.	53	+ ZATZ	152	•0000	č•87	5.00
11CO	ASPHALT EMULSION FOR FOG Seal	18765	GALLONS	ľ	-2400	53-5F	4-88

TOTAL \$1.193.009.03

LAST PAGE

Appendix B Special Provisions & Cross Sections

Tama County SN 4875(1)--51-86 ACC Resurfacing Page 1 of 2

IOWA DEPARTMENT OF TRANSPORTATION

AMES, IOWA

SPECIAL PROVISION

FOR

COLD IN-PLACE ASPHALT RECYCLING

February 23, 1988

11 applicable provisions of the Iowa Department of Transportation's Standard pecifications for Highway and Bridge Construction, 1984, shall apply in addition to the following.

186.01 DESCRIPTION. This work shall consist of the in-place recycling of an existing pavement by pulverizing to the depth as shown on the plans, and by adding emulsified asphalt and water (if required) with the pulverized bituminous surfacing, then placing and compacting said mixture as shown on the plans and as provided herein unless otherwise directed by the Engineer.

> The contractor shall furnish all equipment, tools, labor and material (except the pulverized bituminous material), and any other appurtenances necessary to complete the work.

186.02 EQUIPMENT. Equipment used for the tilling or milling shall be subject to the approval of the engineer.

The Contractor shall furnish a self-propelled machine capable of cutting and removing the bituminous pavement, in one pass, to the depth shown on the plans. The cutting machine shall have automatic controls capable of maintaining a uniform grade and cross slope. The existing asphalt pavement shall be pulverized to 98-100% passing the 1 1/4" sieve.

Provisions shall be made for continuous weight measurement of the pulverized pavement material, interlocked with the additive metering device in order that the desired additive content will be maintained. Positive means shall be provided for calibrating the weight measurement device and the additive metering device.

The additive shall be applied in a mixing chamber which is capable of mixing the pulverized pavement material and additive to a homogeneous mixture. The additive pump shall automatically shut off when delivery of pulverized material to the mixing chamber is stopped. The additive system shall maintain the binder amount within plus or minus 0.2 percent of the desired rate. The mixture shall be placed in a windrow in such a manner that segregation does not occur.

1.) <u>Rollers - Shall comply with Sec. 2001.05 Standard</u> Specifications 1984.

Tama County SN 4875(1)--51-86 ACC Resurfacing Page 2 of 2

Iowa Department of Transportation Special Provision for Cold In-Place Asphalt Recycling

- 186.03 <u>Materials</u> The Asphalt Emulsion shall be a grade as specified by the Engineer and shall meet the the requirements of Sec. 4140 Standard Specifications 1984.
- 187.04 <u>GENERAL CONDITIONS AND SPECIFICATIONS</u>. Except in specific cases when permitted by the Engineer, the work shall be done only between May 1 and October 1. Bituminous materials shall be applied and bituminous mixtures shall be placed only when air temperature in the shade is above 60° F.
 - A. <u>Cleaning and Preparation</u>. Prior to initiating any recycling operation or other inherent work, the contractor shall clear, grub, and remove all vegetation and debris within the width of pavement to be recycled. Disposal of said vegetation and debris shall be as directed by the Engineer.
 - B. <u>Mixing</u>. If there is insufficient moisture for proper mixing or optimum moisture, water in the amount specified by the Engineer shall be added. A place for adding water shall be provided.
 - C. <u>Compaction</u>. After the mixture has been spread and it will bear the weight of the roller without excess laterial movement, as determined by the Engineer, it shall be rolled longitudinally. Initial rolling shall be performed with the pneumatic roller(s) and continue until no displacement is discerned or until the pneumatic rollers have "walked out." Final rolling to eliminate pneumatic tire marks and achieve density shall be done by steel wheel roller(s) either in static or vibratory mode, as required, to achieve required density.

Rollers shall not be started or stopped on uncompacted recycled material. Rolling shall be established so that starting and stopping will be on previously compacted recycled material or on existing asphalt mat.

- E. <u>Density</u>. The field density shall be a minimum of 92% of laboratory density based on the dry weight of compacted material. Five tests per days run will be required at locations as determined by the Engineer. A nuclear tester may be used to determine density.
- F. <u>Basis of Payment</u>. This work will be paid for at the Contract Unit Prices per gallon for Asphalt Rejuvenating Agent and square yards for Asphalt Pavement, in place Cold recycled which shall include all preparation, tilling or milling, mixing, shaping, and compaction.



TAMA COUNTY







ان العام اليونية (الما المنتخر بمنتخل العامي ال الما العام الماري الما العام الماري الماري الماري الماري الم





Appendix C Construction Photographs



Material From Milling Machine Train



Trencher



Slippage Crack Removed and Replaced .

Slippage Crack Replaced





Milled Surface



Trench After Cleaning



Lower Lift in Trench and Rolling With Patrol



Filling Top of Trench



Rolling Lower Lift



Subsidence in First Day's Run