

# **Asphalt Rubber Cement Concrete Webster County**

Final Report  
Iowa Department of Transportation  
Office of Materials  
Project HR-555

April 2003

Highway Division



**Iowa Department  
Of Transportation**

# **Asphalt Rubber Cement Concrete Webster County**

Final Report  
for  
Iowa Department of Transportation  
Project HR-555

by  
Edward J. Engle, P.E.  
Office of Materials  
Highway Division  
Iowa Department of Transportation  
Ames, Iowa 50010

April 2003

### **Disclaimer**

The contents of this report reflect the views of the author and do not necessarily reflect the official views of the Iowa Department of Transportation. This report does not constitute any standard, specification or regulation.

TECHNICAL REPORT TITLE PAGE

---

**1. REPORT NO.** **2. REPORT DATE**

HR-555

April 2003

---

**3. TITLE AND SUBTITLE** **4. TYPE OF REPORT & PERIOD COVERED**

Asphalt Rubber Cement Concrete  
Webster County

Final Report, 4-92 to 2-93

---

**5. AUTHOR(S)** **6. PERFORMING ORGANIZATION ADDRESS**

Edward Engle, P.E.  
Secondary Road Research Coordinator

Iowa Department of Transportation  
Office of Materials  
800 Lincoln Way  
Ames, IA 50010

---

**7. ACKNOWLEDGMENT OF COOPERATING ORGANIZATIONS/INDIVIDUALS**

---

**8. ABSTRACT**

Discarded tires have become a major disposal problem in the U.S. Different techniques of recycling these discarded tires have been tried. The state of Iowa has evaluated the use of discarded tires ground into crumb rubber and blending it with asphalt to make asphalt rubber cement (ARC). This was the sixth project using this process. The project is located on US 169 from the east junction of IA 175 west and north to US 20.

Only the binder course was placed during this research with the surface course to be let at a later date. There were four test sections, two sections with conventional mixtures and two with ARC mixtures.

There were no significant differences in placement or performance between the two mix types. The cost of the ARC mixture was significantly higher.

---

**9. KEY WORDS** **10. NO. OF PAGES**

Ground crumb rubber,  
Recycled tires,  
Asphalt rubber cement,  
Crumb rubber modifier,  
Asphalt concrete

20

## TABLE OF CONTENTS

Introduction .....	1
Objective .....	1
Contractors.....	1
Project Location .....	1
Preconstruction Survey .....	1
Materials.....	2
Mix Design .....	2
Plant Operation .....	2
Paving Operation .....	3
Construction Testing .....	3
Performance Monitoring.....	3
Cracking.....	3
Rutting.....	4
Structure.....	5
Cost Comparison .....	6
Conclusions.....	6
Appendices	
Appendix A – Project Location Map.....	7
Appendix B – Mix Designs.....	9
Appendix C – Lab Test Results .....	12

## INTRODUCTION

Recycling discarded tires into asphalt rubber cement (ARC) has been evaluated in several research projects by the Iowa DOT and others. The process used in this project involved blending the crumb rubber with AC-5 before mixing it with the aggregates (this is the so-called "wet process").

Only the binder (lower) course was completed as part of this research. There were areas of reconstruction and finally an overlay of the entire project at a later date. The project contained two test sections with ARC and two control sections with conventional asphalt cement concrete (ACC). The control sections were placed on August 13, 1992 and the test sections later on August 24, 1992.

## OBJECTIVE

The objective of this project was to compare the cost and performance of ARC to conventional ACC.

## CONTRACTORS

Mathy Construction Company of Onalaska, Wisconsin was the contractor on this project. Rouse Rubber Products of Vicksburg, Mississippi furnished the reactor and the crumb rubber for the project.

## PROJECT LOCATION

The project was located on US 169 from the east junction with IA 175 west and north to the junction with US 20. Test sections are shown in Table 1 below. A map is provided in Appendix A.

<u>Test Section</u>	<u>Stations (Mileposts)</u>	<u>Type</u>
1	221+00 (137.76) to 247+00 (138.25)	Conventional
2	303+50 (139.32) to 383+50 (140.84)	ARC binder
3	430+00 (141.72) to 510+00 (143.23)	ARC binder
4	565+00 (144.27) to 590+00 (144.75)	Conventional

## PRECONSTRUCTION SURVEY

The original road was a 24-foot wide by 7-inch thick Portland cement concrete (PCC) pavement built in 1930. It had been overlaid with three inches of ACC in 1960. The 1991 traffic volume was 2550 VPD with 12 percent trucks.

A preliminary crack and patch survey was conducted and the Road Rater was used to test the structural rating of the test sections prior to construction. Portions of the test sections had been milled. The road had a large number of reflective cracks and was showing signs of distress.

## **MATERIALS**

The ground tire rubber provided by Rouse Rubber Products was listed as GF-50 rubber. Course aggregate was furnished by Martin-Marietta, Fort Dodge Mine, Webster County, Iowa. The crushed limestone, manufactured sand was produced by Martin-Marietta, Hodges, Humboldt County, Iowa. Finally, the natural sand was produced by Northwest Limestone, Yates, Webster County. AC-5 and AC-10 were supplied by Bituminous Materials of Algona, Iowa.

## **MIX DESIGNS**

Low lab voids were a problem with both the conventional mixtures and the ARC mixtures. The mix design for the conventional sections was changed twice and a new mix design adopted for the last two days of production. The asphalt content was reduced from 5.1 to 4.9 percent. Even with the new mix design, including an aggregate interchange and reduced asphalt content, the lab voids remained below three percent.

The ARC mix had low lab voids (1.5 percent on the first day). The asphalt/rubber content was reduced from 6.5 to 6.1 percent. This did increase the lab voids to 3.6 percent.

The ARC mix contained 15 percent crumb rubber. This amounted to one percent of the ACC mixture. All of the mix designs are shown in Appendix B.

## **PLANT OPERATION**

This was the first time a drum plant was used for producing an ARC mixture in Iowa (usually a batch plant was used). It worked satisfactorily with approximately 250 tons per hour being produced. Normally this particular drum plant (Bituma Drum Plant) would be expected to produce 350 tons per hour with conventional mixtures.

Past production of ARC using a Rouse reactor resulted in 150 tons per hour. The lower production was due to difficulties in maintaining temperature in the reaction unit, resulting in longer reaction times. Between 1991 and 1992, Rouse Rubber added an auxiliary heater to the reactor which increased production.

## **PAVING OPERATION**

There were no construction problems with the conventional mix and segregation was minimal.

The ARC mix seemed to handle well, but the mix appeared rather dry. The appearance seemed to improve after the first 1500 feet. There was a minor problem with tearing of the mat when the finish roller was working. Mathy backed the finish roller off some behind the paving operation which helped reduce the problem. This same problem had occurred in previous ARC projects such as the one for HR-330 in Muscatine county. With both the Muscatine project and this one, the tearing was not apparent by the next day. The temperature of the mat behind the paver was between 275 °F and 300 °F with the conventional mixture and approximately 290 °F with the ARC.

Mathy used a Blaw-Knox PF-180H paver and a Dynapac vibratory roller with a steel finish roller on this project.

## **CONSTRUCTION TESTING**


A sample of the GF-50 rubber was tested for gradation. The rubber and AC-5 were tested for viscosity. Finally, samples of the mix were subjected to creep and resilient modulus testing. These laboratory results are provided in Appendix C.

## **PERFORMANCE MONITORING**

This road was evaluated approximately annually from just before the construction until 2001. The results of this testing are shown below.

## **CRACKING**


Crack surveys were performed six times over the course of this project. Figure 1 shows the results of these surveys.



The data in this graph have been normalized. That is to say that because almost all of the cracks in the overlay are reflective, the cracks in the underlying pavement have a strong effect on the number of cracks in the overlay. These data were normalized by dividing the cracks-per-hundred feet by the original (pre-construction) cracks-per-hundred feet. As can be seen from the figure, there are no significant differences apparent between the ARC sections and the control sections.

## RUTTING


Rutting measurements were made using a standard four-foot straight edge in each wheel track. Figure 2 shows the results of rut measurements between 1992 and 2001. The level of rutting was not significant within the accuracy of the measurements.



## STRUCTURE

The structural support of the road – a measure of its strength was measured using the Iowa DOT's Road Rater. This device non-destructively determines the thickness, and strength of pavement by measuring its stiffness. It accomplishes this by vibrating a large mass resonantly against the surface and measuring the deflection of the pavement in response. The values obtained are structural numbers (bigger is better) which can be correlated with equivalent thicknesses of various types of pavement.

Figure 3 shows the results of Road Rater testing for this project. Once again the data have been normalized. This is because the structural number is strongly affected by the strength and moisture content of the subgrade. Under certain conditions, such as a wet spring, the structural numbers are lower across the board. Because this research was mostly concerned with comparison between ARC and control sections, it was assumed that the subgrade values were similar for all of the projects. So the structural numbers were normalized to a fixed average. This makes the data inappropriate for absolute measures but useable for comparison purposes.



The data for the control sections straddle the data for the ARC sections. As a result, there is no indication of a significant difference between the two.

## COST COMPARISON


A major difference between conventional mixtures and the ARC mixtures was the cost. On this project, the asphalt cement was bid at \$84.00 per ton while the bid for ARC was \$190.00 per ton. The cost of the conventional ACC and ARC mix are shown in Table 2 below.

<u>Conventional Mix</u>		<u>ARC Mix</u>	
Aggregate	\$14.53	Aggregate	\$14.53
4.9 % AC-10	\$ 4.12	6.1% ARC	\$11.59
Total	\$18.65 per ton mix	Total	\$26.12 per ton mix

## CONCLUSIONS

1. The ARC mixture can be constructed with little or no difference from that of a conventional mixture.
2. The performance of the two mixes was very similar in terms of cracking, rutting and strength.
3. The cost of ARC mix was significantly higher than that of conventional mixes (this could change with improved technology and possible patent issues).
4. Under the conditions of this research project there is insufficient benefit of using ARC to outweigh the higher cost.

**APPENDIX A**  
Project Location Map



**APPENDIX B**  
Mix Designs

ABD2-0183  
BD

MIX DESIGN

IOWA DEPARTMENT OF TRANSPORTATION  
OFFICE OF MATERIALS  
TEST REPORT - ASPHALT MIX DESIGN  
LAB LOCATION - AMES

LAB NO....:ABD2-0183

MATERIAL.....:TYPE A ARC  
INTENDED USE....:BINDER  
PROJECT NO.....:NHS-169-6(43)--19-94  
COUNTY.....:WEBSTER  
SPEC NO.....:5040.00  
SAMPLED BY.....:

CONTRACTOR:MATHY  
SIZE.....:3/4  
SENDER NO.:

DATE SAMPLED: DATE RECEIVED: DATE REPORTED: 08/21/92  
PROJ. LOCATION: FROM E. JCT. IOWA 175 TO U.S. 20

AGG. SOURCES: CR. LST. & CHIPS - MARTIN MARIETTA, FORT  
ODDGE MINE, WEBSTER CO.; MAN. SAND - MARTIN MARIETTA,  
HODGES, HUMBOLDT CO.; SAND - NORTHWEST LST., YATES, WEBSTER  
CO./ 15% RUBBER ADDED TO AC.

JOB MIX FORMULA-COMB. GRADATION

1 1/2" 1" 3/4" 1/2" 3/8" NO.4 NO.8 NO.16 NO.30 NO.50 NO.100 NO.200  
100.0 92.0 79.0 56.0 45.0 33.0 22.0 11.0 5.3 4.0

TOLERANCE /100 :

98 7 7 7 5 4 2

MATERIAL MIX	A94002	A94002	A46006	A94502	
% AGGR. PROP.	52.50	12.50	10.00	25.00	0.00
% ASPHALT IN MIX		5.25	6.25	7.25	0.00
NUMBER OF MARSHALL BLOWS		50	50	50	0
MARSHALL STABILITY - LBS.		1933	1777	1600	0
FLOW - 0.01 IN.		9	12	13	0
SP GR BY DISPLACEMENT (LAB DENS)		2.332	2.338	2.354	0.000
BULK SP. GR. COMB. DRY AGG.		2.697	2.697	2.697	0.000
SP. GR. ASPH. @ 77 F.		1.022	1.022	1.022	0.000
CALC. SOLID SP. GR.		2.497	2.459	2.423	0.000
% VOIDS - CALC.		6.60	4.94	2.85	0.00
RICE SP.GR.		2.469	2.438	2.405	0.000
% VOIDS - RICE		5.55	4.10	2.12	0.00
% WATER ABSORPTION - AGGREGATE		0.47	0.47	0.47	0.00
% VOIDS IN MINERAL AGGREGATE		18.07	18.73	19.05	0.00
% V.H.A. FILLED WITH ASPHALT		63.47	73.65	85.04	0.00
CALC. ASPH. FILM THICK. MICRONS		10.41	12.48	14.56	0.00
FILLER/BIYUMEN RATIO		0.00	0.62	0.00	0.00

A CONTENT OF 6.5% BINDER IS RECOMMENDED TO START THE JOB.  
TARGET VOIDS 3.5%

COPIES TO:

CENTRAL LAB  
D. HEINS  
DIST. 1

R. MONROE  
MATHY  
JEFFERSON RES.

J. ADAM  
W. OPPELAL

DISPOSITION:

\*\*\*\*\*

SIGNED: ORRIS J. LANE, JR.  
TESTING ENGINEER

ABD2-0182  
00

MIX DESIGN

IOWA DEPARTMENT OF TRANSPORTATION  
OFFICE OF MATERIALS  
TEST REPORT - ASPHALT MIX DESIGN  
LAB LOCATION - AMES

LAB NO.....:ABD2-0182

MATERIAL.....:TYPE A  
INTENDED USE.....:BINDER  
PROJECT NO.....:NMS-169-6(43)--19-94  
COUNTY.....:WEBSTER  
SPEC NO.....:5040.00  
SAMPLED BY.....:  
DATE SAMPLED: DATE RECEIVED: DATE REPORTED: 08/20/92  
PROJ. LOCATION: FROM E. JCT. IOWA 175 TO U.S. 20  
CONTRACTOR:MATHY  
SIZE.....:3/4  
SENDER NO.:

AGG. SOURCES: CR. LST. & CHIPS - MARTIN MARIETTA, FORT DODGE  
MINE, WEBSTER CO.; MAN. SAND - MARTIN MARIETTA, HODGES,  
HUMBOLET CO.; SAND - NORTHWEST LST., YATES, WEBSTER CO.

JOB MIX FORMULA-COMB. GRADATION  
1 1/2" 1" 3/4" 1/2" 3/8" NO.4 NO.8 NO.16 NO.30 NO.50 NO.100 NO.200  
100.0 92.0 79.0 56.0 45.0 33.0 22.0 11.0 5.3 4.0

TOLERANCE /100 :  
98 7 7 7 5 4 2

MATERIAL MIX A94002 A94002 A46006 A94502  
% AGGR. PROP. 52.50 12.50 10.00 25.00 0.00

ASPHALT SOURCE AND ALGONA  
APPROXIMATE VISCOSITY POISES 0929  
% ASPHALT IN MIX 4.50 5.50 0.00 0.00  
NUMBER OF MARSHALL BLOWS 50 50 0 0  
MARSHALL STABILITY - LBS. 2482 2390 0 0  
FLOW - 0.01 IN. 6 8 0 0  
SP GR BY DISPLACEMENT (LAB DENS) 2.376 2.395 0.000 0.000  
BULK SP. GR. COMB. DRY AGG. 2.697 2.697 0.000 0.000  
SP. GR. ASPH. @ 77 F. 1.023 1.023 0.000 0.000  
CALC. SOLID SP. GR. 2.526 2.488 0.000 0.000  
% VOIDS - CALC. 5.94 3.73 0.00 0.00  
RICE SP. GR. 2.497 2.462 0.000 0.000  
% VOIDS - RICE 4.85 2.72 0.00 0.00  
% WATER ABSORPTION - AGGREGATE 0.47 0.47 0.00 0.00  
% VOIDS IN MINERAL AGGREGATE 15.87 16.08 0.00 0.00  
% V.M.A. FILLED WITH ASPHALT 62.59 76.84 0.00 0.00  
CALC. ASPH. FILM THICK. MICRONS 8.85 10.93 0.00 0.00  
FILLER/BITUMEN RATIO 0.00 0.78 0.00 0.00

A CONTENT OF 5.1% AC 10 IS RECOMMENDED TO START THE JOB.  
TARGET VOIDS 3.5%

COPIES TO:

CENTRAL LAB R. MONROE J. ADAM  
D. HEINS MATHY DIST. 1  
JEFFERSON RES.

DISPOSITION:

\*\*\*\*\*

SIGNED: ORRIS J. LANE, JR.  
TESTING ENGINEER

**APPENDIX C**  
Lab Test Results

TEST SECTION WORKSHEET

①

TEST SECTION WORKSHEET

DATE: 8/26/92 STATE:  Iowa  COUNTY:  Webster

PROJECT NUMBER: \_\_\_\_\_ HIGHWAY:  20-169

MARKER: \_\_\_\_\_ % RUBBER:  15%

TYPE RUBBER:  GFSDA  UNIT RPM:  20

TOTAL RUBBER USED/DAY:  48,375  ASPHALT TEMP:  352°F   
 21.5 SK. @ 2250R = 48,375

BROOKSFIELD DATA

TIME	TEMP	SPINDLE	B/F READING	FACTOR	OPS	VISCOSITY
8:30	350	3	20.5	200	1000	
11:30	350	3	6	200	1200	
1:30	350	3	5.5	200	1100	
5:00	350	3	7	200	1400	
made 2750 Tons Asphalt concrete etc						
8/27/92						
8:00	355	3	6	200	1200	
10:00	350	3	8	200	1600	
12:00	350	3	8.5	200	1700	
3:00	347	3	10.0	200	2000	
3:00	345	3	5.5	200	1100	

Rubber used:  21.5 SK @ 2250 48,375   
 Made 2750 TONS Asphalt concrete.

**Iowa Department of Transportation**  
**DAILY PLANT REPORT**  
 BITUMINOUS TREATED BASE, ASPHALT TREATED BASE, ASPHALT CONCRETE

County: Webster  
 Project: MHS-169-G (37) 17-24  
 Contract No.: 34399  
 Date: 8-24-92  
 Report No.: 11  
 Recd. By: Don DeBok

Plant Location: Smiles south Fort Dodge on Hwy 169  
 Plant Name: Bituma  
 Plant Operator: Don DeBok  
 Station: 34  
 Crew Chief: Macin  
 Recycle Source: Macin  
 Plant Operator: Macin  
 Plant Name: Macin  
 Plant Location: Macin  
 Plant Address: Macin  
 Plant Phone: Macin  
 Plant Fax: Macin  
 Plant E-mail: Macin  
 Plant Website: Macin

**SIEVE ANALYSIS OF COMBINED AGGREGATES**

Sieve No.	% Passing	
	Actual	Interpolated
75	100	100
150	93	93
300	84	84
60	46	46
120	35	35
240	14	14
480	7	7
960	3	3
1920	1	1
3840	0	0

**LAB. DEN. 2.37**

Station	Course	Lab. Den.	Comp. Ratio
502423	3 RT	2.37	0.82
49027	7 RT	2.37	0.82
47826	7 RT	2.37	0.82
45425	7 RT	2.37	0.82
44724	9 RT	2.37	0.82
41123	7 RT	2.37	0.82
38122	5 RT	2.37	0.82

**TEMPERATURE RECORD**

Time	7	8	9	10	11	12
Air	69	73	75	78	86	87
A.C.	303	320	335	355	330	330
Asph.	303	305	310	315	305	310
Mix	300	300	305	312	300	305
Mt	250	245	240	235	235	230

**PRODUCTION AND PLACEMENT RECORD**

From Station to Station	Yards Today	Tons To Date
51430 to 430124	1421.69	
51430 to 47450	604.61	
	2026.30	30867.86

Comments: Started rubber mix today

Accepted Price: 4.16 / 5.6 = 0.82

Comments: Delay, Breakdown, Corrective Action, etc.  
 \*Thick mix: (1) Actual, (2) Interpolated  
 Bituminous Treated Base: Binder % Moisture in % Veins Column

Inspector: Macin  
 Signed: Macin  
 Date: 8-24-92





**Iowa Department of Transportation**

**DAILY PLANT REPORT**  
 BITUMINOUS TREATED BASE, ASPHALT TREATED BASE, ASPHALT CONCRETE

County: Webster  
 Project: MH15-169-6 (3) 19-99  
 Contract No: 3-4378  
 Date: 8-27-92

Plant Name: Moby Constructive  
 Plant Location: 5 miles south Fort Dodge on Hwy 167  
 Plant Operator: B. Williams  
 Production Equipment: Stationary Grader  
 Closed Appr. Source: Hodges, Yates  
 Plant Capacity: 6:00 P.M. to 6:00 P.M.  
 Request Source: Do Boek

Report No.: 14  
 Resident Engineer: Do Boek  
 Request Source: Do Boek

**SIEVE ANALYSIS OF COMBINED AGGREGATES**

Sieve No.	% Passing	
	Actual	Intended
3/8"	100	100
No. 40	99	98
No. 60	94	94
No. 80	83	83
No. 100	61	61
No. 150	46	46
No. 200	23	23
No. 300	12	12
No. 425	6.5	6.5
No. 600	4.5	4.5
No. 840	3.1	3.1
No. 1060	2.1	2.1
No. 1320	1.6	1.6
No. 1680	1.1	1.1
No. 2100	0.8	0.8
No. 2700	0.6	0.6
No. 3360	0.5	0.5
No. 4200	0.4	0.4
No. 5250	0.3	0.3
No. 6480	0.2	0.2
No. 7980	0.1	0.1
No. 9750	0.1	0.1
No. 11820	0.1	0.1
No. 14280	0.1	0.1
No. 17160	0.1	0.1
No. 20460	0.1	0.1
No. 24180	0.1	0.1
No. 28320	0.1	0.1
No. 33900	0.1	0.1
No. 40920	0.1	0.1
No. 49440	0.1	0.1
No. 59520	0.1	0.1
No. 71220	0.1	0.1
No. 84660	0.1	0.1
No. 100800	0.1	0.1
No. 119880	0.1	0.1
No. 141840	0.1	0.1
No. 166800	0.1	0.1
No. 194940	0.1	0.1
No. 235920	0.1	0.1
No. 280920	0.1	0.1
No. 339960	0.1	0.1
No. 403920	0.1	0.1
No. 482880	0.1	0.1
No. 577440	0.1	0.1
No. 688640	0.1	0.1
No. 816480	0.1	0.1
No. 961920	0.1	0.1
No. 1124880	0.1	0.1
No. 1305360	0.1	0.1
No. 1503360	0.1	0.1
No. 1718880	0.1	0.1
No. 1951920	0.1	0.1
No. 2202480	0.1	0.1
No. 2570520	0.1	0.1
No. 2966040	0.1	0.1
No. 3489120	0.1	0.1
No. 4138680	0.1	0.1
No. 4914760	0.1	0.1
No. 5817360	0.1	0.1
No. 6847440	0.1	0.1
No. 8005080	0.1	0.1
No. 9290280	0.1	0.1
No. 10703040	0.1	0.1
No. 12342240	0.1	0.1
No. 14208960	0.1	0.1
No. 16303200	0.1	0.1
No. 18624960	0.1	0.1
No. 21173120	0.1	0.1
No. 23947680	0.1	0.1
No. 26948640	0.1	0.1
No. 30175040	0.1	0.1
No. 33626880	0.1	0.1
No. 37303200	0.1	0.1
No. 41204160	0.1	0.1
No. 45329600	0.1	0.1
No. 49679600	0.1	0.1
No. 54254000	0.1	0.1
No. 59052800	0.1	0.1
No. 64076000	0.1	0.1
No. 69323200	0.1	0.1
No. 74794400	0.1	0.1
No. 80489600	0.1	0.1
No. 86409600	0.1	0.1
No. 92554400	0.1	0.1
No. 98924800	0.1	0.1
No. 105520000	0.1	0.1
No. 112326400	0.1	0.1
No. 119343600	0.1	0.1
No. 126571600	0.1	0.1
No. 134010400	0.1	0.1
No. 141660000	0.1	0.1
No. 149520320	0.1	0.1
No. 157591360	0.1	0.1
No. 165873120	0.1	0.1
No. 174365600	0.1	0.1
No. 183069600	0.1	0.1
No. 191985120	0.1	0.1
No. 201112160	0.1	0.1
No. 210450720	0.1	0.1
No. 220000800	0.1	0.1
No. 229762400	0.1	0.1
No. 239735600	0.1	0.1
No. 249920320	0.1	0.1
No. 260317600	0.1	0.1
No. 270927520	0.1	0.1
No. 281750000	0.1	0.1
No. 292786080	0.1	0.1
No. 304035840	0.1	0.1
No. 315499200	0.1	0.1
No. 327176160	0.1	0.1
No. 339066720	0.1	0.1
No. 351170880	0.1	0.1
No. 363488640	0.1	0.1
No. 376019920	0.1	0.1
No. 388764640	0.1	0.1
No. 401722720	0.1	0.1
No. 414894240	0.1	0.1
No. 428279200	0.1	0.1
No. 441877600	0.1	0.1
No. 455689440	0.1	0.1
No. 469714720	0.1	0.1
No. 483953440	0.1	0.1
No. 498405600	0.1	0.1
No. 513071200	0.1	0.1
No. 527950240	0.1	0.1
No. 543042640	0.1	0.1
No. 558348400	0.1	0.1
No. 573867600	0.1	0.1
No. 589599200	0.1	0.1
No. 605543200	0.1	0.1
No. 621700640	0.1	0.1
No. 638071520	0.1	0.1
No. 654655840	0.1	0.1
No. 671453600	0.1	0.1
No. 688464800	0.1	0.1
No. 705689440	0.1	0.1
No. 723127520	0.1	0.1
No. 740779040	0.1	0.1
No. 758644000	0.1	0.1
No. 776722400	0.1	0.1
No. 795014240	0.1	0.1
No. 813519600	0.1	0.1
No. 832238560	0.1	0.1
No. 851170960	0.1	0.1
No. 870316800	0.1	0.1
No. 889676160	0.1	0.1
No. 909249040	0.1	0.1
No. 929035440	0.1	0.1
No. 949035360	0.1	0.1
No. 969249760	0.1	0.1
No. 989678640	0.1	0.1
No. 1010322000	0.1	0.1
No. 1031074800	0.1	0.1
No. 1051945040	0.1	0.1
No. 1072932720	0.1	0.1
No. 1094037960	0.1	0.1
No. 1115260760	0.1	0.1
No. 1136601120	0.1	0.1
No. 1158058040	0.1	0.1
No. 1179631520	0.1	0.1
No. 1201321560	0.1	0.1
No. 12231280640	0.1	0.1
No. 1245051120	0.1	0.1
No. 1267090720	0.1	0.1
No. 1289246880	0.1	0.1
No. 1311519600	0.1	0.1
No. 1333908960	0.1	0.1
No. 1356414960	0.1	0.1
No. 1379037520	0.1	0.1
No. 1401776640	0.1	0.1
No. 1424631360	0.1	0.1
No. 1447601760	0.1	0.1
No. 1470687840	0.1	0.1
No. 1493889600	0.1	0.1
No. 1517107040	0.1	0.1
No. 1540440160	0.1	0.1
No. 1563888960	0.1	0.1
No. 1587453440	0.1	0.1
No. 1611133600	0.1	0.1
No. 1634929440	0.1	0.1
No. 1658840800	0.1	0.1
No. 1682867840	0.1	0.1
No. 1707010400	0.1	0.1
No. 1731268560	0.1	0.1
No. 1755642240	0.1	0.1
No. 1780131440	0.1	0.1
No. 1804736160	0.1	0.1
No. 1829456400	0.1	0.1
No. 1854292320	0.1	0.1
No. 1879243840	0.1	0.1
No. 1904310960	0.1	0.1
No. 1929493600	0.1	0.1
No. 1954791840	0.1	0.1
No. 1980205600	0.1	0.1
No. 2005734960	0.1	0.1
No. 2031379840	0.1	0.1
No. 2057140320	0.1	0.1
No. 2083016400	0.1	0.1
No. 2109008160	0.1	0.1
No. 2135115520	0.1	0.1
No. 2161338560	0.1	0.1
No. 2187677280	0.1	0.1
No. 2214131600	0.1	0.1
No. 2240701520	0.1	0.1
No. 2267387040	0.1	0.1
No. 2294188160	0.1	0.1
No. 2321104800	0.1	0.1
No. 2348137040	0.1	0.1
No. 2375284800	0.1	0.1
No. 2402547200	0.1	0.1
No. 2429924160	0.1	0.1
No. 2457415600	0.1	0.1
No. 2485021600	0.1	0.1
No. 2512743040	0.1	0.1
No. 2540579920	0.1	0.1
No. 2568532320	0.1	0.1
No. 2596600240	0.1	0.1
No. 2624783680	0.1	0.1
No. 2653082720	0.1	0.1
No. 2681497360	0.1	0.1
No. 2710027520	0.1	0.1
No. 2738673200	0.1	0.1
No. 2767434400	0.1	0.1
No. 2796311200	0.1	0.1
No. 2825303520	0.1	0.1
No. 2854411360	0.1	0.1
No. 2883634720	0.1	0.1
No. 2912973600	0.1	0.1
No. 2942428000	0.1	0.1
No. 2971998000	0.1	0.1
No. 3001683600	0.1	0.1
No. 3031484800	0.1	0.1
No. 3061401600	0.1	0.1
No. 3091434000	0.1	0.1
No. 3121582000	0.1	0.1
No. 3151845600	0.1	0.1
No. 3182224800	0.1	0.1
No. 3212719600	0.1	0.1
No. 3243330000	0.1	0.1
No. 3274056000	0.1	0.1
No. 3304897600	0.1	0.1
No. 3335854800	0.1	0.1
No. 3366927600	0.1	0.1
No. 3398116000	0.1	0.1
No. 3429420000	0.1	0.1
No. 3460839600	0.1	0.1
No. 3492374800	0.1	0.1
No. 3524025600	0.1	0.1
No. 3555792000	0.1	0.1
No. 3587674000	0.1	0.1
No. 3619671600	0.1	0.1
No. 3651784800	0.1	0.1
No. 3683913600	0.1	0.1
No. 3716058000	0.1	0.1
No. 3748318000	0.1	0.1
No. 3780693600	0.1	0.1
No. 3813184800	0.1	0.1
No. 3845791600	0.1	0.1
No. 3878414000	0.1	0.1
No. 3911052000	0.1	0.1
No. 3943805600	0.1	0.1
No. 3976674800	0.1	0.1
No. 4009659600	0.1	0.1
No. 4042760000	0.1	0.1
No. 4075976000	0.1	0.1
No. 4109307600	0.1	0.1
No. 4142754800	0.1	0.1
No. 4176317600	0.1	0.1
No. 4210096000	0.1	0.1
No. 4243989600	0.1	0.1
No. 4278008400	0.1	0.1
No. 4312142400	0.1	0.1
No. 4346391600	0.1	0.1
No. 4380756000	0.1	0.1
No. 4415235600	0.1	0.1
No. 4449830400	0.1	0.1
No. 4484540400	0.1	0.1
No. 4519365600	0.1	0.1
No. 4554306000	0.1	0.1
No. 4589361600	0.1	0.1
No. 4624532400	0.1	0.1
No. 4659818400	0.1	0.1
No. 4695219600	0.1	0.1



AAT2-0449  
A

IOWA DEPARTMENT OF TRANSPORTATION  
OFFICE OF MATERIALS  
TEST REPORT - BITUMINOUS AGGREGATES  
LAB LOCATION - AMES

LAB NO.: AAT2-0449

MATERIAL.....:GF 50 CRUMB RUBBER  
INTENDED USE.....:A.R.C. BINDER  
PRODUCER.....:ROUSH  
PROJECT NO.....:NHS-169-6(43) --19-94  
COUNTY.....:WEBSTER  
UNIT OF MATERIAL:GF - 50 RUBBER GRANULES  
SAMPLED BY.....:C. ANDERSON  
DATE SAMPLED: 08/24/92      DATE RECEIVED: 08/27/92      DATE REPORTED: 08/27/92

CONTRACTOR:MATHY CONST.

SENDER NO.:CA2-123

-----  
SIEVE NO. 10 - 100.0

LAB NUMBER	AAT2-0449
SIEVE ANALYSIS %	
#30	98.0
#50	33.0

COPIES TO:  
CENTRAL LAB

GEOLOGY

V. MARKS

DISPOSITION:

\*\*\*\*\*

SIGNED: ORRIS J. LANE, JR.  
TESTING ENGINEER

### Marshall Stability, Creep and Resilient Modulus Testing

<u>Test</u>	<u>Material</u>	<u>Conventional</u>	<u>ARC</u>
Marshall Stability	¾ - inch binder, 50 blows	2,436	1,790
Creep	¾ - inch binder, 50 blows	88	77
Resilient Modulus	¾ - inch binder, 50 blows	710,000	580,000