

**IMPROVED AGGREGATE  
GRADATION FOR  
PORTLAND CEMENT CONCRETE  
MIXES**

**Final Report  
for  
Project HR-563**

**October 1996**

**Project Development Division**



**Iowa Department  
of Transportation**

Final Report  
for  
Research Project HR-563

IMPROVED AGGREGATE GRADATION FOR  
PORTLAND CEMENT CONCRETE MIXES

by  
Todd D. Hanson  
Pavement Materials Engineer  
515-239-1649

Iowa Department of Transportation  
Project Development Division  
Office of Materials  
Ames, Iowa 50010

October 1996

TECHNICAL REPORT TITLE PAGE

---

<b>1. REPORT NO.</b>	<b>2. REPORT DATE</b>
HR-563	October 1996

---

<b>3. TITLE AND SUBTITLE</b>	<b>4. TYPE OF REPORT &amp; PERIOD COVERED</b>
Improved Aggregate Gradation for Portland Cement Concrete Mixes	Final Report from 9-95 to 9-96

---

<b>5. AUTHOR(S)</b>	<b>6. PERFORMING ORGANIZATION ADDRESS</b>
Todd Hanson Pavement Materials Engineer	Iowa Department of Transportation Materials Department 800 Lincoln Way Ames, Iowa 50010

---

**7. ACKNOWLEDGEMENT OF COOPERATING ORGANIZATIONS**

---

**8. ABSTRACT**

Improving the aggregate gradation for a portland cement concrete mix may result in higher compressive strengths. With an improved gradation, the cement factor may be reduced to achieve a more economical concrete mix since cement is the most expensive component in a portland cement concrete mix. This project located on I-80 westbound in Scott County, Iowa examined three different mixes.

1. Standard Class C mix with project aggregates.
2. Standard Class C mix with an improved aggregate gradation.
3. Standard Class C mix with an improved aggregate gradation and 10% cementitious reduction.

---

<b>9. KEY WORDS</b>	<b>10. NO. OF PAGES</b>
Portland cement concrete Gradation	18

## TABLE OF CONTENTS

	Page
Introduction.....	1
Objective.....	1
Project Description.....	1
Materials.....	2
Scope.....	2
Construction.....	3
Strength Testing.....	4
Gradation.....	5
Discussion of Results.....	5
Summary and Conclusions.....	6
Acknowledgments.....	7
Figure Captions.....	8
Figures.....	9-18

### DISCLAIMER

The contents of this report reflect  
The views of the author and do not  
necessarily reflect the official views  
of the Iowa Department of  
Transportation. This report does  
not constitute any standard,  
specification or regulation.

## **Introduction**

This research examined the addition of 9.5 mm (3/8") chips to the aggregate in a portland cement concrete mix to achieve an improved gradation. Concrete mixes produced with an improved gradation of aggregates should have greater compressive strengths and improved workability.

Three different mixes were placed on this project as follows:

Std. Mix- Standard Iowa D.O.T. "C" mix with project aggregates

Mix 1 - Standard Iowa D.O.T. mix with 35% of the coarse aggregate replaced with 9.5 mm (3/8") chips

Mix 2 - Standard Iowa D.O.T. mix with 35% of the coarse aggregate replaced with 9.5 mm (3/8") chips and 10% cementitious reduction.

## **Objective**

The objective of the research was to evaluate the feasibility of reducing the cement factor in a portland cement concrete mix with an improved gradation and still achieve comparable compressive strengths.

## **Project Description**

The project was located on I-80 from just west of the Stockton Interchange (MP 280.78) to west of the Walcott Interchange (MP 283.23) and at the I-280 Interchange (MP 289.06) in Scott County. (Figure 1) The work involved replacing 4.687 miles of 4-lane interstate highway at two locations. A 305 mm (12 inch) plain doweled and jointed PCC pavement was designed to replace

the 35 year old pavement.

The test sections were placed between September 13 and September 15, 1995. The sections are located on the westbound roadway of I-80 at the following locations:

Std. Mix- Station 213+81 to 236+66, and the remainder of project

Mix 1 - Station 190+44 to 213+81

Mix 2 - Station 190+44 to 179+62 and 159+60 to 147+41.

### **Materials**

The following materials were used:

Cement - LaFarge, Davenport Type I

Fly Ash - Louisa Class C

Coarse Aggregate - Linwood Quarry, Scott County (A82008)

Fine Aggregate - Milan-Big Island, Illinois (AIL504)

Air Entraining - Daravair 1000, W.R. Grace

Water Reducer - WRDA-82, W.R. Grace

Refer to Figures 2 and 3 for the concrete absolute volumes and mix proportions.

### **Scope**

The research examined the standard Iowa Department of Transportation Class C concrete mix versus a Class C mix with the gradation modified by the addition of 9.5 mm (3/8") chips and a

Class C mix with the gradation modified by the addition of 9.5 mm (3/8") chips and a 10% cementitious reduction. Two test sections were placed with the modified gradation mixes while the remainder of the project used the standard Class C mix. Nine beams and nine cylinders were cast from each mix type.

### **Construction**

McCarthy Improvement was the successful bidder for the 4.687 mile inlay at two locations. The research sections were placed between September 13th and 15th, 1995. Temperatures during the construction of the research sections ranged from daytime highs of 24 to 29°C (76 to 85°F) and overnight lows of 13 to 16°C (55 to 60°F). Nine beams and nine cylinders were fabricated at the plant from each of the three concrete mixes for 7, 14, and 28 day strengths, air content, and slump were determined for each mix (Figure 4). The plastic air content at the plant was approximately 5% higher than that at the grade due to air loss during transport. All beams and cylinders were covered with plastic and placed in a wet sand pit until they were transferred to the central laboratory in Ames. During transporting to the central lab, the beams and cylinders were covered with wet burlap.

For convenience, the beams and cylinders were fabricated on September 13th from the plant mixed standard Class C concrete mix. The concrete mix exhibited fairly good workability and finishability in the slab.

Mix 1 was placed on September 14th from station 190 + 44 to 213 + 81 westbound. The beams

and cylinders were fabricated from the concrete mix with 35% of the coarse aggregate replaced with 9.5 mm (3/8") chips. While fabricating the beams, it was noted that the mix seemed to be harder to move around than the standard concrete mix. This phenomenon may be due to the particle shape, cubical vs. rounded, of the 9.5 mm (3/8") chips or the extra mortar content. It was noted that the finishers had a slight amount of trouble with finishing if they got too far behind the paver, but otherwise the mix was fairly workable in the slab.

Mix 2 was placed on September 15th from station 179 + 62 to 190 + 44 westbound. The conveyor belt that introduced the 9.5 mm (3/8") chips into the plant broke down and paving with this mix was suspended. An additional section of Mix 2 was placed on September 16th from 147 + 41 to 159 + 60 until the 9.5 mm (3/8") chips stockpile was used up. This mix exhibited fairly good workability and finishability.

### **Strength Testing**

Three cylinders and three beams were tested for compression and modulus of rupture from each mix at each of the following times: 7 days, 14 days, and 28 days. The results of the tests are shown in Figure 5. The data is shown in Figure 6 as modulus of rupture versus time and in Figure 7 as compressive strength versus time. Mix 1, with the improved gradation, showed a marked increase in strength over the standard mix with approximately a 34% increase in modulus of rupture and approximately a 30% increase in compressive strength.

Mix 2 with the improved gradation and 10% cementitious reduction exhibited strengths similar to

those achieved by the standard mix with the standard gradation. Lowering the cement factor and using a more uniform gradation will allow a more economical concrete mix, since cement is the most expensive component in a concrete mix.

### **Gradation**

The standard mix used in this project was a C3WRC20. The C3 mix uses 55% coarse aggregate and 45% fine aggregate. For mixes 1 and 2, 35% of the coarse aggregate was replaced with 9.5 mm (3/8") chips. The combined gradations for both aggregate blends are shown in Figure 8. The combined aggregate gradation was plotted as percent passing (Figure 9). The plot indicates that the addition of the 9.5 mm (3/8") chips provides a more uniform gradation than the standard aggregate gradation.

Increasing the amount retained on the 9.5 mm (3/8") to 1.18 mm (#16) sieves provides a more uniform aggregate gradation. The percent retained on each sieve was plotted as shown in Figure 10. The plot indicates an increase in material retained on the 4.75 mm (#4) and 2.36 mm (#8) sieves over the standard project aggregates. Using the plot of percent retained on individual sieves is a useful tool in evaluating the combined aggregate particle distribution.

### **Discussion of Results**

The improvement towards a more uniform gradation produces a mix capable of higher compressive and flexural strengths. Reducing the cementitious content of a concrete mix with an improved gradation of aggregates will tend to produce concretes with compressive strengths

similar to those achieved by concrete mixes with a more gap graded aggregate structure.

This field research verifies research performed in the laboratory<sup>1</sup>.

Improving the aggregate gradation of concrete mixes is sometimes difficult due to availability of a aggregate in the 9.5 mm (3/8") and lower sizes. Aggregate producers tend to remove the 9.5 mm (3/8") and lower portions of concrete stone for other purposes. During this project, there was some difficulty acquiring the 9.5 mm (3/8") chips due to the aggregate producer needing the chips at their asphalt plant. The aggregate producers need to be made aware of changes needed in production of concrete stone.

The workability of Mix 1 was somewhat stiff compared to Mix 2, perhaps due to particle shape of the 9.5 mm (3/8") chips or maybe due to excess mortar content. Using a mix design program, such as Shilstone, could help to determine proper aggregate proportions for optimum workability.

### **Summary and Conclusions**

Based on the results of this project, the following is concluded:

1. Higher compressive strengths may be achieved with a more uniform combined gradation of aggregates.
2. Reducing the cement factor in concrete mixes with a more uniform combined gradation of

<sup>1</sup>Ouyang, C., "Coarse Aggregate Gradations for P.C. Concrete", Iowa Department of Transportation, MLR-94-8, 1995, 11 pp

aggregates produces a concrete with compressive and flexural strengths similar to those achieved by concrete mixes with a more gap graded combined gradation of aggregates.


3. Providing a more uniform gradation of combined aggregates does not necessarily achieve a concrete mix with improved workability.

### **Acknowledgments**

The author wishes to extend appreciation to the East Central Iowa Transportation Center Materials personnel for their efforts in this project. We also would like to thank McCarthy Improvement Inc. for their cooperation during this project.


### **Figure Captions**

1. Project Location Map
2. Basic Absolute Volumes
3. Mix Proportions
4. Mix Locations and Concrete Test Results
5. Compressive Strength and Flexural Strength
6. Modulus of Rupture vs. Age
7. Compressive Strength vs. Age
8. Combined Aggregate Gradations
9. Combined Aggregate Gradation, % Passing
10. Combined Aggregate Gradation, % Retained



**LOCATION MAP**  
**SCOTT COUNTY**

**Figure 1 - Project Location Map**



**Figure 2 - Basic Absolute Volumes - IM-80-8(160)279--13-82**

	<b>Standard Mix</b>	<b>Mix 1</b>	<b>Mix 2</b>
<b>Cement</b>	0.086	0.086	0.078
<b>Fly Ash</b>	0.025	0.025	0.022
<b>Water</b>	0.146	0.146	0.131
<b>Fine Aggregate</b>	0.307	0.307	0.319
<b>Coarse Aggregate</b>	0.376	0.244	0.2535
<b>3/8" Chips</b>	-	0.132	0.1365
<b>Air</b>	0.06	0.06	0.06

**Figure 3 - Mix Proportions (lbs./cu. yd.) - IM-80-8(160)279--13-82**

<b><u>Mix</u></b>	<b><u>Cement</u></b>	<b><u>Fly Ash</u></b>	<b><u>Fine Aggregate</u></b>	<b><u>Coarse Aggregate</u></b>	<b><u>3/8" Chips Aggregate</u></b>	<b><u>Water</u></b>
Standard	457	114	1381	1698	-	218
Mix 1	457	114	1381	1104	594	218
Mix 2	411	103	1435	1145	616	210

**Figure 4 - Mix Locations and Concrete Test Results**  
**IM-80-8(160)279--13-82**

<u>Mix</u>	<u>Locations</u>	<u>Slump (in.)</u>	<u>% Air*** at Plant</u>	<u>% Air at Grade</u>
Standard	213+81 to 236+66*	2 1/4"	12.0	7.6
Mix 1	190+44 to 213+81	1/2"	11.5	7.8
Mix 2	190+44 to 179+62 & 159+60 to 147+41**	1 3/4"	12.5	7.6

\* Standard mix used throughout project.

\*\* Gap due to conveyor belt break.

\*\*\* Lost approximately 5% air on transport.

**Figure 5 - Compressive Strength and Flexural Strength****Compressive Strength, psi, 4 1/2" X 9" Cylinders**


<b><u>Mix</u></b>	<b><u>7 Day</u></b>	<b><u>14 Day</u></b>	<b><u>28 Day</u></b>
Standard	3440	4200	4160
Mix 1	4650	5120	5420
Mix 2	3430	3520	4480

**Modulus of Rupture, psi, 6" X 6" X 20" Beams**

<b><u>Mix</u></b>	<b><u>7 Day</u></b>	<b><u>14 Day</u></b>	<b><u>28 Day</u></b>
Standard	480	540	530
Mix 1	640	690	700
Mix 2	460	510	490


**Figure 6 - Modulus of Rupture vs. Age**

IM-80-8(160)279--13-82



# Figure 7 - Compressive Strength vs. Age

IM-80-8(160)279--13-82



### Figure 8 - Combined Aggregate Gradations

#### Standard Mix - Project Aggregates IM-80-8(160)279--13-82


Sieve Size	Coarse Aggregate	Fine Aggregate	Combined Gradation
26.4 mm (1")	100		100.0
19 mm (3/4")	70		83.5
13 mm (1/2")	36		64.8
9.5 mm (3/8")	13	100	52.2
4.75 mm (#4)	3.1	94	44.0
2.36 mm (#8)	2.2	87	40.4
1.18 mm (#16)		74	34.5
600 µm (#30)		44	21.0
300 µm (#50)		8.2	4.9
150 µm (#100)		0.5	1.4
75 µm (#200)	1.6	0.1	1.3

#### Mix 1 & Mix 2 - 35% Coarse Aggregate Replaced with Chips IM-80-8(160)279--13-82

Sieve Size	Coarse Aggregate	9.5 mm Chips	Fine Aggregate	Combined Gradation
26.4 mm (1")	100			100.0
19 mm (3/4")	70			89.3
13 mm (1/2")	33	100		76.0
9.5 mm (3/8")	6	92	100	64.9
4.75 mm (#4)	1.2	32	95	49.3
2.36 mm (#8)	1	8.2	88	41.5
1.18 mm (#16)			75	35.7
600 µm (#30)			42	20.8
300 µm (#50)			6.1	4.7
150 µm (#100)			0.2	2.0
75 µm (#200)	0.6	0.7	0.1	0.4

**Figure 9 - Combined Aggregate Gradation**

IM-80-8(160)279--13-82



**Figure 10 - Combined Aggregate Gradation, % Retained**

IM-80-8(160)279--13-82

