



**SPECIAL PROVISIONS
FOR
SITE REMOVALS**

**Pottawattamie County
ESL-000R (1)--7S-78**

**Effective Date
November 17, 2009**

THE STANDARD SPECIFICATIONS, SERIES OF 2009, ARE AMENDED BY THE FOLLOWING ADDITIONS AND MODIFICATIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

090026.01 DESCRIPTION.

This work consists of general site removals to allow for replacement and/or installation of new infrastructure improvements. Generally, an existing storm sewer pipe and wood poles with communication wire need to be removed and disposed of off-site in accordance with all local, state and federal regulations. Materials removed become the property of the Contractor. Also the existing Iowa Interstate Railroad sign located at the existing entrance to the facility and the existing speed limit sign within the facility need to be removed and re-installed during staging and phasing of construction as shown on the plans.

090026.02 MATERIALS.

A. Removal of materials includes:

1. 48" diameter corrugated metal pipe. Condition unknown.
2. Wood communication poles approximately 40' in length.
3. Communications wires from pole line, coated and approximately 1" in diameter.

B. Existing signs shall be removed and re-installed at locations designated on the plans to allow for staging during construction. Existing signs shall be salvaged and installed in-kind at locations designated on the plans during the proper phase of construction.

090026.03 CONSTRUCTION.

- A.** Remove and dispose of approximately 160 lineal feet of 48" corrugated metal pipe across existing entrance road to the existing facility currently open on the upstream end connected to a storm sewer drainage catch basin on the downstream end. Earthen/aggregate material disturbed during removal may be used for backfill around pipe replacement at discretion of the Engineer. No separate payment will be made for excavation or backfill.
- B.** Remove and dispose of communication wire currently attached to wood pole line to limits designated on the plans. No separate payment will be made for removal and disposal of communication wire.
- C.** Remove and dispose of treated wooden poles to limits designated on the plans.
- D.** Backfill and tamp loose dirt as a result of pole removal. Do not leave any open holes or depressions. No separate payment will be made for backfill and tamping of pole holes.
- E.** The removal of the pole line is included within the area designated for seed, fertilize and mulch and therefore already accounted for in stabilizing the disturbed area. No separate payment will be made for disturbance and subsequent seed, fertilize and mulch for removal of the pole line.
- F.** The signs to be removed/relocated and re-installed shall be done so as to utilize the same signs and post without damaging. The installation of the signs shall be done in-kind as is currently provided. Any defective or damaged material shall be replaced by the Contractor at no additional expense.

090026.04 METHOD OF MEASUREMENT.

- A.** The corrugated pipe removal and disposal shall be measured per lineal foot removed.
- B.** The removal and disposal of the wood poles and communication wire will be measured per each pole removed. Removal of the communication wire is considered incidental to removal of the poles.
- C.** The removal and re-installation of signs shall be measured per each sign per each re-location.

090026.05 BASIS OF PAYMENT.

- A.** The corrugated metal pipe removal will be paid at the contract unit bid price per lineal foot removed, which shall include all necessary labor and equipment. Excavation is considered incidental to the removal of the pipe.
- B.** The removal and disposal of the wood poles and communication wire will be paid for at the contract unit price bid per each pole removed, which shall include all necessary labor and equipment. Removal and disposal of communication wire, backfill and tamping of holes is considered incidental to removal of the poles.
- C.** The removal and re-installation of signs shall be paid at the contract unit price bid per sign per re-location, which shall include all necessary material, labor and equipment. It is the intent to use the sign and supporting apparatus as it currently exists for re-location. No separate payment will be made for defective material replacement due to damage by Contractor.