44'-1"

DRYWALL AND HAT CHANNEL
TO BE PROVIDED BY DOT

EXISTING GLAZED BLOCK WALLS
TO BE FURRED OUT WITH 1" HAT
CHANNEL 24" OC AND 5/8" GYP
BOARD TAPED AND FINISHED
SMOOTH PRIMED AND READY FOR
DOT TO PAINT

RADIATOR AND STEAM LINES
UNDER ALMOST EVERY WINDOW

DOT ELECTRICIANS TO BRING
OUT EXISTING ELECTRICAL
BOXES TO FACE OF DRYWALL

33'-5 1/2 "

1ST FLOOR (PHASE 1)